

Semi-Automatic Classification Plugin Documentation

Выпуск 8.1.3.1

Luca Congedo

мар. 27, 2024

Оглавление

| 1 | Introduction | 1 |
|---|--|--|
| 2 | 2.4 Installation in macOS ^{$'$} | 3 3 15 20 24 |
| 3 | 3.1 SCP menu 3.2 SCP dock 3.3 Working toolbar | 118 |
| 4 | Brief Introduction to Remote Sensing14.1Basic Definitions14.2Multispectral satellites14.3SAR satellites14.4Land Cover Classification14.5Image processing14.6Image conversion to reflectance14.7Conversion to Temperature14.8References1 | l 27 l 31 l 33 l 46 l 50 l 54 |
| 5 | 5.1 Tutorial 1: Basic Land Cover Classification 1 5.2 Tutorial 2: Managing input bands, the Band set tab 1 5.3 Tutorial 3: Downloading free satellite images, the Download product tab 1 | 174 174 |
| 6 | Thematic Tutorials 1 | 75 |
| 7 | Frequently Asked Questions17.1Plugin installation17.2Pre processing17.3Processing17.4Warnings17.5Errors1 | 182 183 185 |

| 7.6 | Various | | | | • | | | | • | | | | | | | | • | | | • | | • | | | • | | | • | | | | | • | | | | | | • | | | | • | • | | | • | • | | | • | • | | | • | | | | • | | | | | • | 1 | 18 | ;7 | |
|-----|---------|--|--|--|---|--|--|--|---|--|--|--|--|--|--|--|---|--|--|---|--|---|--|--|---|--|--|---|--|--|--|--|---|--|--|--|--|--|---|--|--|--|---|---|--|--|---|---|--|--|---|---|--|--|---|--|--|--|---|--|--|--|--|---|---|----|----|--|
|-----|---------|--|--|--|---|--|--|--|---|--|--|--|--|--|--|--|---|--|--|---|--|---|--|--|---|--|--|---|--|--|--|--|---|--|--|--|--|--|---|--|--|--|---|---|--|--|---|---|--|--|---|---|--|--|---|--|--|--|---|--|--|--|--|---|---|----|----|--|

Глава 1

Introduction

Developed by Luca Congedo (ing.congedoluca@gmail.com), the **Semi-Automatic Classification Plugin** (SCP) is a free open source plugin for QGIS that allows for the semi-automatic classification (also known as supervised classification) of remote sensing images. It provides several tools for the download of free images, the preprocessing, the postprocessing, and the raster calculation.

The **overall objective** of *SCP* is to provide a set of intertwined tools for raster processing in order to make an automatic workflow and ease the land cover classification, which could be performed also by people whose main field is not remote sensing.

SCP exploits the parallel processing of the tools provided by Remotior Sensus, a Python package that allows for the processing of remote sensing images and GIS data.

This user manual provides information about the *Plugin Installation* (c. 3) of SPC and the *The Interface* of SCP (c. 29), with detailed information about all the functions. In addition, the *Brief Introduction to Remote Sensing* (c. 123) illustrates the basic concepts and definitions which are required for using the SCP.

For more information and tutorials visit the official site



How to cite:

Congedo, Luca, (2021). Semi-Automatic Classification Plugin: A Python tool for the download and processing of remote sensing images in QGIS. Journal of Open Source Software, 6(64), 3172, https://doi.org/10.21105/joss.03172

Brief history:

The first version of the SCP was developed by Luca Congedo in 2012 for the «ACC Dar Project» in order to create a tool for the classification of land cover in an affordable and automatic fashion; following versions of SCP were developed as personal commitment to the remote sensing field and open source philosophy. SCP version 6 was developed in the frame of Luca Congedo's PhD in Landscape and Environment at Sapienza University of Rome. SCP version 7 and version 8 as personal commitment to the remote sensing field and open source philosophy.

License:

Except where otherwise noted, content of this work is licensed under a Creative Commons Attribution-ShareAlike 4.0 International License.

Semi-Automatic Classification Plugin is free software: you can redistribute it and/or modify it under the terms of the GNU General Public License as published by the Free Software Foundation, version 3 of the License. Semi-Automatic Classification Plugin is distributed in the hope that it will be useful, but WITHOUT ANY WARRANTY; without even the implied warranty of MERCHANTABILITY or FITNESS FOR A PARTICULAR PURPOSE. See the GNU General Public License for more details. You should have received a copy of the GNU General Public License along with Semi-Automatic Classification Plugin. If not, see http://www.gnu.org/licenses/.

Translators:

Language: Author name

Глава 2

Plugin Installation

The Semi-Automatic Classification Plugin requires the installation of GDAL, OGR, NumPy, SciPy and Matplotlib .


This chapter describes the installation of the Semi-Automatic Classification Plugin for the supported Operating Systems.

2.1 Installation in Windows 64 bit

2.1.1 QGIS download and installation

- Download the latest QGIS version 64 bit from here ;
- Execute the QGIS installer with administrative rights, accepting the default configuration.

Now, QGIS is installed.




2.1.2 Installation of required dependencies

The Semi-Automatic Classification Plugin requires Remotior Sensus, GDAL, NumPy and SciPy for most functionalities. Optionally, scikit-learn and PyTorch are required for machine learning.

Therefore, we need to install the dependencies that are not included in the QGIS installation.

- Close QGIS;
- From the Start menu, open OSGeo4W Shell (administrative rights may be required);



• Enter the following command:

pip3 install --upgrade remotior-sensus scikit-learn torch

Follow the same procedure for updating the dependencies.

COBET: In case the library Remotior Sensus is not found, an automatic procedure will try to download it in the plugin directory, allowing for using the main functions of the Semi-Automatic Classification Plugin; however, this is not recommended as library Remotior Sensus won't be updated, and scikit-learn and PyTorch functions will not work. Alternatively, one may follow *Advanced installation using Conda* (c. 24).

2.1.3 Semi-Automatic Classification Plugin installation

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| Q Untitl | ed Pr | oject - | – QGIS | | | | | | | | | |
|-----------------|-------|---------|--------|----------|----------|----------|----------------|------------------|-------------|----------|------------|--------------|
| Project | Edit | View | Layer | Settings | Plugins | Vector | <u>R</u> aster | <u>D</u> atabase | <u>W</u> eb | Mesh | Processing | <u>H</u> elp |
| | - | | | 3 😭 | 🌲 Mar | nage and | Install Plu | ugins | | | D C | |
| | | | | Ng ∎a | nt 👌 Pyt | hon Cons | sole | | Ct | rl+Alt+P | | 160 |

• From the menu All, select the Semi-Automatic Classification Plugin and click the button Install plugin;



• The SCP should be automatically activated; however, be sure that the Semi-Automatic Classification Plugin is checked in the menu Installed (the restart of QGIS could be necessary to complete the SCP installation);


| All | Plugin installed successfully | 6 |
|-----------------------------------|--|---|
| Installed | Q. Search | |
| _ | search Layers | |
| Not installed | segreg | Semi-Automatic Classification Plugin |
| | 🝅 Seismic Positioning Data Importer | |
| Install from ZIP | select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the |
| | 🛸 Select Within | supervised classification of remote sensing images, providing tools |
| Settings | V 📴 Semi-Automatic Classification Plugin | for the download, the preprocessing and postprocessing of |
| | Sen2Cor Adapter | images. |
| | send2GE | |
| | 💁 Sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for |
| | 🛸 SentinelHub | the supervised classification of remote sensing images, providing tools for the |
| | 🛸 Serval | download, the preprocessing and postprocessing of images. Search and download is |
| | 🍅 Servicios WMS - IDES Cali | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several |
| | shape Tools | algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please |
| | shapefile Encoding Fixer | visit https://fromgistors.blogspot.com . |
| | shLocator | the needed of the second |
| | 🍅 shptoobs | ☆☆☆☆☆ 435 rating vote(s), 762194 downloads |
| | simple WCS 2 | |
| | simpleSvg | Category Bactor |
| | 🛸 SLD4raster | Category Raster |
| | sleuth Inputs | ▼ Upgrade All Uninstall Plugin Reinstall Plugin |
| | + CLVD (Community, Edition) | Opgrade Air Opgrade A |

2.1.4 Configuration of the plugin

Now, the Semi-Automatic Classification Plugin is installed and a dock and a toolbar should be added to QGIS. Also, a SCP menu is available in the Menu Bar of QGIS. It is possible to move the toolbar and the dock according to your needs, as in the following image.

| Project Edit View Layer Settings Plugins Vector Raster | <u>D</u> atabase <u>W</u> eb <u>M</u> esh SCP | Processing Help | | | | |
|---|---|------------------|---|---|------------------------|-------------|
| 🗅 📄 🗟 🖪 😭 💕 🥠 🧌 🌾 🖊 🦏 | 🔛 🔀 🔍 🗮 🔆 🗴 | | 👂 🍭 - 🛛 🔣 - 📑 - 🌄 - 🛶 - | | | |
| 🕵 🔎 🛛 RGB = 🕘 👻 െ 🔎 🔍 ROI | 🔀 🕂 🕐 Dist 0.010000 | \$ Min 60 \$ | Max 100 💲 🗩 💿 Preview 🔚 💟 🕇 0 | S 200 S 200 | 人般地 | 🐞 » |
| SCP Dock Ø 🗷 | 88 | | Semi-Automatic Classification Plugin | | <u> </u> | - ¤ × |
| Image: Second secon | Filter Filter Band set Download products Basic tools Processing Script Script Script Script Help Help About | Band set ta | Band set definition Active band set 1 Date Nat Band name | | Multiplic Multiplic | Tool 😔 Help |
| MC ID 1 CName Macroclass 1 | | | Band quick settings Wavelength Band order | 👻 🚺 Wavelen band | nuDabe 202 - | |
| Autosave 🗹 Signature | | 66 B 🛒 | Band set tools | | | |
| SCP Dock Layers | | 🔁 🗗 🙀 | Create virtual raster Create raster of ban Build of band set (stack bands) | d band overview Band calc expressio | RUN 💽 | |
| Q. Type to locate (Ctrl+K) | | Coordinate -0.92 | , 107 - Cale 1.1401393 | | uei 💮 ti 30.432 | |

The configuration of available RAM is recommended in order to reduce the processing time. From the SCP menu (c. 29) select Settings > Processing .



In the *Settings* (c. 109), set the Available RAM (MB) to a value that should be half of the system RAM. For instance, if your system has 2GB of RAM, set the value to 1024MB.

| | Semi-Aı | tomatic Classification P | lugin | + _ □ × |
|--|--|--------------------------|--|--------------------|
| Filter | System Available RAM (MB) CPU threads Calculation process | | | 1024 € 2 € E |
| Band calc | Play sound when finished | | Raster compression | |
| Script | SMTP process notification | | | |
| 🝷 淋 Settings | SMTP server | user | password | |
| Debug Interface Processing setting | Send email of completed pro | cess to | | ▼ remember |
| Help | Temporary directory | | | |
| P About | External programs GDAL installation directory | | | |

2.1.5 Update of required dependencies

The dependency Remotior Sensus is frequently updated. The Semi-Automatic Classification Plugin can check automatically if a new version is available, and display a message in the $SCP \ dock$ (c. 31).




It is recommended to close QGIS and update Remotior Sensus following the same installation steps described in *Installation of required dependencies* (c. 4).

2.2 Network installation in Windows 64 bit

2.2.1 QGIS download and installation

- Download the latest QGIS version 64 bit using the OSGeo4W network installer from here ;
- Execute the QGIS installer with administrative rights and select Advanced Install;



• Select Install from Internet; proceed selecting the default installation directory and the preferred network configuration;

| OSGeo4W S | etup - Choose Download Site(s) | - | | \times |
|-----------|---|-----|---|----------|
| | wnload Site site from this list, or add your own sites to the list | | | ۲ |
| | Available Download Sites: | | | |
| | https://download.osgeo.org https://ftp.osuosl.org https://www.norbit.de | | | |
| User URL: | | Ado | i | |

The Semi-Automatic Classification Plugin requires Remotior Sensus, GDAL, NumPy and SciPy for most functionalities. Optionally, scikit-learn and PyTorch are required for machine learning.

• In the menu Select packages select All > Desktop > qgis-full-free; also select All > Libs > python3-remotior-sensus, All > Libs > python3-scikit-learn and All > Libs > python3-torch;

| es ges to install | | | | (|
|-----------------------------|---|--|---|---|
| Clear | | | | ◯ Keep ◯ Prev Curr ◯ Exp View Category |
| New | B | S | Size | Package |
| Skip | n/a | n/a | 43,390k | ggis: QGIS Desktop |
| Skip | n/a | n/a | 124,635k | qgis-dev: QGIS nightly build of the development branch |
| Skip | n/a | n/a | 1k | qgis-dev-full: QGIS nightly build of the development branch (metap |
| Skip | n/a | n/a | 1k | qgis-dev-full-free: QGIS nightly build of the development branch (m |
| Skip | nja | n/a | 1,195,930k | qgis-dev-pdb: Debugging symbols for QGIS nightly build of the dev |
| Skip | nja | n/a | 1k | qgis-full: QGIS Desktop Full (meta package) |
| 3.32.3-1 | \times | | 1k | qgis-full-free: QGIS Desktop Full Free (meta package) |
| Skip | nja | nja | 43,590k | qgis-ltr: QGIS Desktop (long term release) |
| Skip | n/a | n/a | 106,748k | qgis-tr-dev: QGIS nightly build of the long term release branch |
| Skip | nía | nía | 1k | ggis-tr-dev-full: QGIS nightly build of the long term release branch |
| | ges to install Clear O Skip O Skip | ges to install Clear Skip Skip Skip | ges to install Clear Skip New B S Skip Na Skip Na Skip Na Skip Na Skip Na Skip Skip Na Skip Skip Na Skip Skip | Clear Other B S Size Image: Skip n/a n/a 43,390k Image: Skip n/a n/a 124,635k Image: Skip n/a n/a 124,635k Image: Skip n/a n/a 124,635k Image: Skip n/a n/a 1k Image: Skip n/a n/a 43,590k Image: Skip n/a n/a 106,748k |

| elect Packag | tup - Select Packages jes ages to install | | | | | |
|----------------------|--|-------------|------------|------|------|--|
| Search | Clear | | | | | ○ Keep ○ Prev O Curr ○ Exp View Categor |
| Category | New | В., | S | Size | | Package |
| Category | () Skip | n/a | n/a | | 59k | python3-rasterio: Fast and direct raster I/O for use with Numpy an |
| | Skip | nía | nía | | | python3-rasterstats: Summarize geospatial raster datasets based of |
| | Skip | nía | nía | | | python3-regex: Alternative regular expression module, to replace r |
| | € 0.1.4-1 | | | | | python3-remotior-sensus; Remotior Sensus is software to process |
| | Skip | nía | n/a | | | python3-reportlab: The Reportlab Toolkit |
| | () Skip | nía | n/a | | | python 3-requests: Python HTTP for Humans. |
| | Skip | n/a | n/a | | | python3-retrying: Retrying |
| | Skip | n/a | n/a | | | python3-tree: R-Tree spatial index for Python GIS |
| | Skip | n/a | n/a | | | python3-scikit-leam: A set of python modules for machine learning |
| | Skip | n/a | n/a | | | python3-scipy: Fundamental algorithms for scientific computing in |
| | A Skin | nía | nía | 2 | 0.6k | nuthon 3-seahom: seahom: statistical data visualization |
| < | | | | | | > |
| Hide obsolete | packages | | | | | |
| OSGeo4W Set | tup - Select Packages | | | | | - 0 |
| elect Packag | ges ages to install | | | | | (|
| Search | | | | | | |
| Category | New | В | S | Size | | O Keep O Prev) Curr O Exp View Category Package |
| Calegory | | | | | 0.01 | |
| | Skip | n/a | nja | | 66k | python3-remotior-sensus: Remotior Sensus is software to process |
| | Skip | n/a | n/a | | | python3-reportlab: The Reportlab Toolkit |
| | Skip Skip | n/a | nja n/a | 0 | | python3-requests: Python HTTP for Humans. python3-retrying: Retrying |
| | Skip | nja nja | nja nja | | | python3-tree: R-Tree spatial index for Python GIS |
| | 0.23.2-2 | | nja | | | python3-scikit-leam: A set of python modules for machine learning |
| | Skip | n/a | nja | | | python3-scipy: Fundamental algorithms for scientific computing in |
| | () Skip | nía | nía | | | python3-seabom: seabom: statistical data visualization |
| | () Skip | nía | n/a | | | python3-segregation: Analytics for spatial and non-spatial segrega |
| | Skip | n/a | n/a | | | python3-send2trash: Send file to trash natively under Mac OS X, |
| < | A Chin | - | n/o | 0 | | har aberrari literi blind bealawab vinez valaatavtaa Caadtin |
| ►] Hide obsolete | packages | | | | | |
| OSC and M. Sat | tup - Select Packages | | | | | - 0 |
| elect Packad | Selection and the selection of the selec | | | | | |
| Select packa | ages to install | | | | | · |
| Search | Clear | | | | | ○ Keep ○ Prev O Curr ○ Exp View Category |
| Category | New | B | | Size | | Package |
| | Skip | nía | nja | | | |
| | Skip | nía | nja | | | python3-threadpoolctl: threadpoolctl |
| | Skip | nía | nja | | | python3-tobler: TOBLER: Areal Interpolation |
| | Skip | nja | nía | | | python3toml: Python Library for Tom's Obvious, Minimal Languag |
| | Skip | nía | nía | | | python3tomli: A lil' TOML parser |
| | 0 2.0.1-1 | \boxtimes | | | | python3-torch: Tensors and Dynamic neural networks in Python v |
| | Skip | nía | nja | | | python3-tornado: Tornado is a Python web framework and async |
| | Skip | nía | nía | | | python3tqdm: Fast, Extensible Progress Meter |
| | Skip | nía | nía | | 75k | python3-traitlets: Traitlets Python configuration system |
| | | | | | - | |
| | Skip | nía nía | nía nía | | | python3-typing-extensions: Backported and Experimental Type H nython3-typidata: Provider of IANA time zone data |

• Click Next and accept to install the required dependencies;

| - | Unmet Dependencies Found owing packages are required but have not been selected. | (|
|----------|---|---|
| api-ms-w | in-core-path-HACK (0.0.1-5) | ^ |
| • | Hack to make python 3.9 work on Windows 7 | |
| | Required by: python3-core | |
| arrow-cp | p (7.0.0-6) | |
| | Apache Arrow C++ library (runtime) | |
| | Required by: gdal-dev308-runtime, gdal307-runtime | |
| avce00 | (2.0.0-3) | |
| | The AVCE00 commandline utilities for Arc/Info E00 conversion | |
| | Required by: grass8 | |
| base | (1.0.0-20) | |
| | OSGen4W hase parkage | ~ |
| < | | > |

The download of the programs will start, and QGIS will be installed along with the required dependencies.

| Q Untitled Project — QGIS | | | - 0 × |
|--|---|---|-------------------|
| | Jugins Vect <u>o</u> r <u>R</u> aster <u>D</u> atabase <u>W</u> eb <u>M</u> esh Proge | | |
| 🗋 🗁 🗟 🔂 😭 🚺 | R @ Q Q 👯 🤤 🤁 | Α 🗓 🗠 🖫 🖤 😋 🔣 - 🖬 - 🧞 - 🔍 - 🍕 🗮 🌞 Σ 🗐 | • 🔤 • 🤛 🛞 • |
| 🧏 📽 V. 🖊 🖷 🖬 🛛 | 🕻 🖉 / 🖯 🖯 - 😘 k - 🖬 | 🖥 🖂 ð 🕻 🖕 🖉 🔍 👒 🛥 🔍 🤫 🤫 🤫 🤗 🤗 | 2 |
| Layers | 0 🕱 | | |
| <u>≪</u> (<u>1</u>), (1), (1), (1), (1), (1), (1), (1), (1 | | | |
| | | | |
| Q. Type to locate (Ctrl+K) | ady | Coordinate 0,266° 0,206° 🗞 Scale 1:1685323 💌 🚔 Magnifier 100% 💠 Rotation 0,0° 💠 | Render @EPSG:4326 |

2.2.2 Semi-Automatic Classification Plugin installation

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| 🔍 Untit | led Pr | oject - | - QGIS | | | | | | | | | |
|---------|--------|---------|--------|----------|--------|----------|---------------|------------------|-------------|--------------|------------|-------|
| Project | | | | | | | | <u>D</u> atabase | <u>W</u> eb | <u>M</u> esh | Processing | Help |
| | | | | <u>3</u> | 🌲 Mai | nage and | l Install Plu | ugins | | | DC | |
| | | | | N 🗖 a | ne Pyt | hon Cons | sole | | Ct | rl+Alt+F | | 1 F 🔯 |

• From the menu All, select the Semi-Automatic Classification Plugin and click the button Install plugin;

| All | Q Search | | | | | |
|------------------|---|---|--|--|--|--|
| | search Layers | | | | | |
| Installed | 🖕 Segreg | Semi-Automatic Classification Plugin | | | | |
| | 🚖 Seismic Positioning Data Importer | | | | | |
| Not installed | Select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the | | | | |
| | 🚖 Select Within | supervised classification of remote sensing images, providing tools | | | | |
| Install from ZIP | Semi-Automatic Classification Plugin | Plugin for the download, the preprocessing and postprocessing of | | | | |
| | sen2Cor Adapter | images. | | | | |
| Settings | send2GE | | | | | |
| se | sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for | | | | |
| | 🚖 SentinelHub | the supervised classification of remote sensing images, providing tools for the | | | | |
| | Serval Servicios WMS - IDES Cali | download, the preprocessing and postprocessing of images. Search and download is | | | | |
| | | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the | | | | |
| | shape Tools | installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please | | | | |
| | Shapefile Encoding Fixer | visit https://fromgistors.blogspot.com . | | | | |
| | shLocator | visit netps// nongisters/biogsportcom i | | | | |
| | shptoobs | ☆☆☆☆☆☆ 435 rating vote(s), 762194 downloads | | | | |
| | simple WCS 2 | , , , , , , , , , , , , , , , , , , , | | | | |
| | simpleSvg | The second | | | | |
| | sLD4raster | Tags raster, analysis, landsat, land cover, landscape, classification, remote sensing, mask, accuracy, clip, | | | | |
| | 🚖 Sleuth Inputs | spectral signature, supervised classification, sentinel | | | | |
| | SLYR (Community Edition) | Mare info beneration but braken and marchine | | | | |
| | snail | | | | | |

• The SCP should be automatically activated; however, be sure that the Semi-Automatic Classification Plugin is checked in the menu Installed (the restart of QGIS could be necessary to complete the SCP installation);


| All | Plugin installed successfully | E |
|------------------|--|---|
| Installed | Q Search | |
| | 💁 Search Layers | |
| Not installed | segreg | Semi-Automatic Classification Plugin |
| | 🚖 Seismic Positioning Data Importer | |
| Install from ZIP | select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the |
| | select Within | supervised classification of remote sensing images, providing tool |
| Settings | V 📴 Semi-Automatic Classification Plugin | for the download, the preprocessing and postprocessing of |
| | sen2Cor Adapter | images. |
| | send2GE | 5 |
| | sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for |
| | sentinelHub | the supervised classification of remote sensing images, providing tools for the |
| | serval | download, the preprocessing and postprocessing of images. Search and download is |
| | 🚖 Servicios WMS - IDES Cali | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the |
| | shape Tools | installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please |
| | Shapefile Encoding Fixer | visit https://fromgistors.blogspot.com . |
| | shLocator | |
| | shptoobs | ★★★★★ 435 rating vote(s), 762194 downloads |
| | Simple WCS 2 | |
| | simpleSvg | Category Raster |
| | 🚖 SLD4raster | |
| | sleuth Inputs | Upgrade All Uninstall Plugin Reinstall Plugin |
| | - CLVD (Community, Edition) | Copyrade Air |

2.2.3 Configuration of the plugin

Now, the Semi-Automatic Classification Plugin is installed and a dock and a toolbar should be added to QGIS. Also, a SCP menu is available in the Menu Bar of QGIS. It is possible to move the toolbar and the dock according to your needs, as in the following image.

| Project Edit View Layer Settings Plugins Vector Raster | | Pro <u>c</u> essing <u>H</u> elp | o | | |
|---|--|----------------------------------|---|--|-------------------------|
| Image: Science of the scienc | E 🕂 💽 Dist 0.010000 | t Min 60 | Max 100 🗘 🖽 💽 Preview 📑 🚺 🖬 o 💠 Semi-Automatic Classification Plugin | S 200 🕏 🛤 🛝 🕀 🕀 | * <u>*</u> * <u>*</u> * |
| Image: Second | Filter Filter | Filter Band set ta | Band set definition Active band set 1 📮 Date NaT | Root directory Center wavelength Multiplic | Tool 💿 Help |
| | C Postprocessing Band calc Script Settings Debug Interface Processing setting | | | | • |
| | if User manual ④ Help About | | | | |
| Image: Constraint of the second sec | | | A Band quick settings Wavelength Band order | Wavelen band nuBabe 20 | |
| C Type to locate (Ctrl+K) | | | Band set tools Create virtual raster of band set (stack bands) | nd overview Band calc expressio RUN | |

The configuration of available RAM is recommended in order to reduce the processing time. From the SCP menu (c. 29) select Settings > Processing .



In the *Settings* (c. 109), set the Available RAM (MB) to a value that should be half of the system RAM. For instance, if your system has 2GB of RAM, set the value to 1024MB.

| | Semi-Automat | ic Classification Plugin | | + _ □ × |
|--|---|--------------------------|------------|----------------------|
| Filter Band set Download products Basic tools Preprocessing Band processing | System Available RAM (MB) CPU threads Calculation process | | | 1024 ↓ 2 ↓ Heb |
| Postprocessing Band calc Script | Play sound when finished SMTP process notification | ✔ Raster c | ompression | |
| Settings Debug Interface Processing setting Setting | SMTP server | user | password | ✓ remember |
| Help About | Temporary directory Temporary directory External programs GDAL installation directory | | | |
| | | | | |

2.2.4 Update of required dependencies

The dependency Remotior Sensus is frequently updated. The Semi-Automatic Classification Plugin can check automatically if a new version is available, and display a message in the $SCP \ dock$ (c. 31).



It is recommended to close QGIS and update Remotior Sensus following the same installation steps described in *QGIS download and installation* (c. 8).

In case the library Remotior Sensus is outdated, it is possible to open the OSGeo4W Shell (administrative rights may be required):



and run the following command:

```
pip3 install --upgrade remotior-sensus
```

2.3 Installation in Debian/Ubuntu Linux

2.3.1 QGIS download and installation

• Open a terminal and type:

sudo apt-get update

- Press Enter and type the user password;
- Type in a terminal:

```
sudo apt-get install qgis python3-matplotlib python3-scipy
```

• Press Enter and wait until the software is downloaded and installed.

Now, QGIS is installed.

| 🔇 Untitled Project — QGIS | | | - 0 × |
|----------------------------|--|--|--------------------------------------|
| | is <u>Plugins Vector R</u> aster <u>D</u> atabase <u>W</u> eb <u>M</u> esh Pro | | |
| | | a 🔏 🗓 🧠 💺 🗓 🕓 🌫 🔣 - 🖬 - 🖕 - 🛛 | 🔍 🔤 🌞 \Sigma 🔲 - 🛲 - 🍃 🍭 - |
| 🦛 📽 Vi 🖊 🖷 🔛 | 🖸 🖉 🖉 🖉 🖉 🖓 🖓 🖓 🖓 | To in the second | 🧠 🐏 🌏 📲 |
| Layers | 0 X | | |
| 《 創 ● 〒 5 - 13 前 1 | | | |
| | | | |
| Q. Type to locate (Ctrl+K) | Ready | Coordinate 0,266° 0,206° 🕷 Scale 1:1685323 💌 🔒 Magnifier 100% | Rotation 0,0 ° 🗘 🗸 Render @EPSG:4326 |

2.3.2 Installation of required dependencies

The Semi-Automatic Classification Plugin requires Remotior Sensus, GDAL, NumPy and SciPy for most functionalities. Optionally, scikit-learn and PyTorch are required for machine learning.

Therefore, we need to install the dependencies that are not included in the QGIS installation.

- Close QGIS;
- Open the terminal (administrative rights may be required);
- Enter the following command:

pip3 install --upgrade remotior-sensus scikit-learn torch

Предупреждение: In case you get an error message related to externally managed environment, you may use (at the risk of breaking the OS or the Python installation) the option --break-system-packages; alternatively, it is possible to create a virtual environment python3 -m venv env, install the packages in it, and start QGIS from the activated environment.

Follow the same procedure for updating the dependencies.

COBET: In case the library Remotior Sensus is not found, an automatic procedure will try to download it in the plugin directory, allowing for using the main functions of the Semi-Automatic Classification Plugin; however, this is not recommended as library Remotior Sensus won't be updated, and scikit-learn and PyTorch functions will not work. Alternatively, one may follow *Advanced installation using Conda* (c. 24).

2.3.3 Semi-Automatic Classification Plugin installation

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| 🔇 Untit | led Pr | oject - | – QGIS | | | | | | | | | |
|---------|--------|---------|--------|------|----------|----------|-------------|----------|-------------|----------|------------|--------------|
| | | | | | | | | Database | <u>W</u> eb | Mesh | Processing | <u>H</u> elp |
| | | | | a 🛀 | 🌲 Mar | nage and | Install Plu | igins | | | D C | |
| | | • | | S ∎a | nt 👌 Pyt | hon Cons | sole | | Ct | rl+Alt+P | | |

• From the menu All, select the Semi-Automatic Classification Plugin and click the button Install plugin;

| All | Q Search | |
|------------------|---|---|
| Installed | Search Layers Segreg Seismic Positioning Data Importer Select by relationship Select Within | Semi-Automatic Classification Plugin |
| 1nstall from ZIP | Semi-Automatic Classification Plugin Sen2Cor Adapter | supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. |
| o cuingo | Send2GE Sentinel-2 Download Sentinel-12 Download Servicios WMS - IDES Cali Shape Tools Shape Tools Shapefile Encoding Fixer Shocator Shptoobs Simple WCS 2 Simple Sig Supple to the senter Sen | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Search and download is available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . ★★★★★★★★★★★★★★★★★★★★★★★★★★★★★ |
| | SLD4raster Sleuth Inputs SLYR (Community Edition) Snal Code(a) attribute | classification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel Upgrade All Install Plugin |

• The SCP should be automatically activated; however, be sure that the Semi-Automatic Classification Plugin is checked in the menu Installed (the restart of QGIS could be necessary to complete the SCP installation);


| All | Plugin installed successfully | C |
|--------------------------------------|--|--|
| Installed | Q Search | |
| | 💁 Search Layers | |
| Not installed | segreg | Semi-Automatic Classification Plugin |
| | 🚖 Seismic Positioning Data Importer | |
| Install from ZIP | select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the |
| | 🚖 Select Within | supervised classification of remote sensing images, providing tools |
| Settings | V 💀 Semi-Automatic Classification Plugin | for the download, the preprocessing and postprocessing of |
| | Sen2Cor Adapter | images. |
| | send2GE | indgest |
| | Sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for |
| | sentinelHub | the supervised classification of remote sensing images, providing tools for the |
| | serval | download, the preprocessing and postprocessing of images. Search and download is |
| | Servicios WMS - IDES Cali | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several |
| | shape Tools | algorithms are available for the land cover classification. This plugin requires the |
| | Shapefile Encoding Fixer | installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . |
| | shLocator | visit https://iongistors.biogspot.com |
| | shptoobs | → ☆☆☆☆☆ 435 rating vote(s), 762194 downloads |
| | Simple WCS 2 | |
| | simpleSvg | |
| | sLD4raster | Category Raster |
| | Sleuth Inputs | |
| | CLVD (Community Edition) | Upgrade All Uninstall Plugin Reinstall Plugin |

2.3.4 Configuration of the plugin

Now, the Semi-Automatic Classification Plugin is installed and a dock and a toolbar should be added to QGIS. Also, a SCP menu is available in the Menu Bar of QGIS. It is possible to move the toolbar and the dock according to your needs, as in the following image.

| Project Edit View Layer Settings Plugins Vector | aster <u>D</u> atabase <u>W</u> eb <u>M</u> esh SCP | Processing Help | | | |
|--|--|----------------------------|--|--|----|
| 🗋 🖿 🖥 🖪 🕄 💕 🦛 🖓 🖊 | 🖏 🎇 🕅 🔍 🔤 🌞 🕽 | Σ | 🖓 🔍 - 🛛 🔣 - 🔂 - 🎝 | | |
| 👧 🔎 🖲 RGB = 🕘 💌 െ 🙈 🔎 🖲 RG | I 🔀 🕂 🕓 Dist 0.010000 | \$ Min 60 \$ | Max 100 💲 争 💿 Preview 🔚 🚺 T 0 | 🕈 🖸 200 🗘 🗰 🐘 🏦 🏠 🐁 | >> |
| SCP Dock @B | | | Semi-Automatic Classification Plugin | ↑ _ □ > | × |
| Statistical Signature list Filter MCID * CID Name Type Col | Filter Band set Download products Basic tools Basic tools Basic tools Postprocessing Band calc Script Script Script Cebug Interface Processing setting Focessing setting User manual | Filter Band set ta 1 | Band set definition Active band set 1 Date NaT | Root directory Center wavelength Multiplic 단 문 문 문 문 문 문 문 문 문 문 문 문 문 문 문 문 문 문 | |
| Image: SCP Dock Layers Image: Type to locate (Ctrl+k) | 🕃 Help | v | Image: settings Band quick settings Wavelength Band order Band set tools Create virtual raster Create virtual raster Create virtual raster (stack bands) | Wavelen band nubabe 202 * I band overview Band calc expressio | |

The configuration of available RAM is recommended in order to reduce the processing time. From the SCP menu (c. 29) select Settings > Processing .



In the *Settings* (c. 109), set the Available RAM (MB) to a value that should be half of the system RAM. For instance, if your system has 2GB of RAM, set the value to 1024MB.

| | Semi-Aut | omatic Classification P | lugin | ↑ _ 0 | □ × |
|--|---|-------------------------|---|-------|-------------|
| Filter Filter Filter Filter Filter Filter Filter Filter Foreprocessing Filter Foreprocessing Filter Foreprocessing Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter Filter F | Semi-Aut System Available RAM (MB) CPU threads Calculation process V Play sound when finished SMTP process notification SMTP server SMTP server Send email of completed proce Temporary directory | user | Iugin ✓ Raster compression password | 1024 | Tool 🛞 Help |
| Help | | | | | |

2.3.5 Update of required dependencies

The dependency Remotior Sensus is frequently updated. The Semi-Automatic Classification Plugin can check automatically if a new version is available, and display a message in the $SCP \ dock$ (c. 31).




It is recommended to close QGIS and update Remotior Sensus following the same installation steps described in *Installation of required dependencies* (c. 16).

2.4 Installation in macOS

2.4.1 QGIS download and installation

- Download the latest QGIS version from here ;
- Execute the QGIS installer with administrative rights, accepting the default configuration.

Now, QGIS is installed.



2.4.2 Installation of required dependencies

The Semi-Automatic Classification Plugin requires Remotior Sensus, GDAL, NumPy and SciPy for most functionalities. Optionally, scikit-learn and PyTorch are required for machine learning.

Therefore, we need to install the dependencies that are not included in the QGIS installation.

- Close QGIS;
- Open the terminal (administrative rights may be required);
- Type the following command (you may need to adapt the path /*Applications/QGIS.app* to the actual QGIS installation directory):

/Applications/QGIS.app/Contents/MacOS/bin/pip3 install --upgrade remotior-sensus_ →scikit-learn torch

or in case you installed QGIS LTR:

```
/Applications/QGIS-LTR.app/Contents/MacOS/bin/pip3 install --upgrade remotior-sensus⊔
→scikit-learn torch
```


```
COBET: In case of error messages such as scikit-learn is already installed, you can just run / Applications/QGIS.app/Contents/MacOS/bin/pip3 install --upgrade remotior-sensus torch
```

Follow the same procedure for updating the dependencies.

COBET: In case the library Remotior Sensus is not found, an automatic procedure will try to download it in the plugin directory, allowing for using the main functions of the Semi-Automatic Classification Plugin; however, this is not recommended as library Remotior Sensus won't be updated, and scikit-learn and PyTorch functions will not work. Alternatively, one may follow *Advanced installation using Conda* (c. 24).

2.4.3 Semi-Automatic Classification Plugin installation

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;



• From the menu All, select the Semi-Automatic Classification Plugin and click the button Install plugin;

| Search Layers Segreg Seimic Positioning Data Importer Select Within Select Within Select Within Senti-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sentinel-2Download Sentinel-2Download Servia Shape Tools Shape Tools Shape Tools Shape File Encoding Fixer Shucator Shucator Shucator SingleSvg SLD4raster Sleuth Inputs SLV4raster Sleuth Inputs Stril | All | Q. Search | | | | | |
|--|------------------|--|---|--|--|--|--|
| Not installed Not install from ZIP Select by relationship Select Within Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sential-12 Download Serval Serval Servicios WMS - IDES Cali Shape Tools Shape File Encoding Fixer Shlocator Shlocator Single WCS 2 Single WCS 2<th></th><th>search Layers</th><th></th> | | search Layers | | | | | |
| Not installed Not install from ZIP Select by relationship Select Within Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sential-12 Download Serval Serval Servicios WMS - IDES Cali Shape Tools Shape File Encoding Fixer Shlocator Shlocator Single WCS 2 Single WCS 2<th>Installed</th><th>🖕 Segreg</th><th>Semi-Automatic Classification Plugin</th> | Installed | 🖕 Segreg | Semi-Automatic Classification Plugin | | | | |
| Install from ZIP Select Within Install from ZIP Select Within Settings Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Servidos WMS - IDES Call Shapefile Encoding Fixer Shapefile Encoding Fixer Shucator Sinple WCS 2 SingleSvg SLD4raster Sleuth Inputs SLYR (Community Edition) Stand Strater | | 🚖 Seismic Positioning Data Importer | | | | | |
| Install from ZIP Select Within Settings Semi-Automatic Classification Plugin Settings Semi-Automatic Classification Plugin Settings Sentinel-ZDownload Sentinel-ZDownload Sentinel-ZDownload Serval Serval Serval Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing of images. Search and download is available for the land cover classification. This plugin requires the lang cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shape Tools Simple WCS 2 Simple Svig Subcrater Sleuth Inputs Seluth Inputs Struct Simple Svig SL/R (community Edition) Simal | Not installed | select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the | | | | |
| Install from ZIP Semi-Automatic Classification Plugin Senital from ZIP Senital from ZIP Semi-Automatic Classification Plugin Senital from ZIP Senital from ZIP | | 🚖 Select Within | | | | | |
| Settings Sen2Cor Adapter Settings Sen2Cor Adapter Sentinel+2Download Entinel+1ub Serval Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images. providing tools for the download, the preprocessing and postprocessing of images. Search and download is available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shapefile Encoding Fixer Simple WCS 2 Simple Syg SLD4raster Steuth Inputs Surger caster, analysis, landsat, land cover, landscape, classification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel Synd Stream | Install from ZIP | 🖕 Semi-Automatic Classification Plugin | | | | | |
| Settings Sendage Settings Sendage Settings Sentinel-2Download Sentinel-2Download Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotib. For more information please visit https://fromgistors.blogspot.com . Shiptobs Simple WCS 2 Simple Svig SluPraster Sleuth Inputs Surger cassification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel Strik (Community Edition) Strik (community Edition) | | sen2Cor Adapter | | | | | |
| SentinelHub Serval Shapefile Encoding Fixer Shapefile Encoding | Settings | send2GE | | | | | |
| Servial Shape Tools | | Sentinel-2 Download | | | | | |
| Servicios WMS - IDES Cal Shape Tools Shape Tools Shape file Encoding Fixer Shapefile Encoding Fixer Shapefile Encoding Fixer Shapefile Encoding Fixer Shapefile Shapefile Encoding Fixer Shapefile Encoding Fixer | | sentinelHub | | | | | |
| algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shore to be been been been been been been been | | serval | | | | | |
| Shape Tools Shape To | | | | | | | |
| Shapefile Encoding Fixer ShLocator Shlocator | | shape Tools | | | | | |
| Shlocator Shptoobs Simple WCS 2 Simple Svg SLP4raster Sleuth Inputs SLYR (Community Edition) String | | Shapefile Encoding Fixer | | | | | |
| Simple WCS 2 SimpleSvg SLO4raster Sleuth Inputs SLYR (Community Editon) Snal | | shLocator | visit riteps.// nongistors.biogspot.com . | | | | |
| Simple WCS 2 SimpleSvg SLD+raster Sleuth Inputs SLYR (Community Edition) Snal | | shptoobs | \Rightarrow | | | | |
| SLP4raster Classification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel SLYR (Community Edition) Solid | | simple WCS 2 | | | | | |
| SLD+raster Classification, remote sensing, mask, accuracy, clip, Sleuth Inputs SLYR (Community Edition) Snal | | simpleSvg | These maters and six fundant land around he desired | | | | |
| Seuth Inputs Spectral signature, supervised classification, sentinel Strat | | sLD4raster | | | | | |
| SLYR (Community Edition) | | Sleuth Inputs | | | | | |
| S Snail | | SLYR (Community Edition) | | | | | |
| | | snail | Vuograde All | | | | |

• The SCP should be automatically activated; however, be sure that the Semi-Automatic Classification Plugin is checked in the menu Installed (the restart of QGIS could be necessary to complete the SCP installation);


| All | Plugin installed successfully | C |
|------------------|--|--|
| Installed | Q Search | |
| - | search Layers | |
| Not installed | segreg | Semi-Automatic Classification Plugin |
| | 🎓 Seismic Positioning Data Importer | |
| Install from ZIP | 🐀 Select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the |
| | 🚖 Select Within | supervised classification of remote sensing images, providing tools |
| Settings | V 💯 Semi-Automatic Classification Plugin | for the download, the preprocessing and postprocessing of |
| | sen2Cor Adapter | images. |
| and a second | 🚖 Send2GE | indgest |
| | 🚖 Sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for |
| | 🛸 SentinelHub | the supervised classification of remote sensing images, providing tools for the |
| | 🚖 Serval | download, the preprocessing and postprocessing of images. Search and download is |
| | 🍅 Servicios WMS - IDES Cali | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several |
| | shape Tools | algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please |
| | 🚖 Shapefile Encoding Fixer | visit https://fromgistors.blogspot.com . |
| | shLocator | |
| | 🍅 shptoobs | All the second s |
| | simple WCS 2 | , , , , , , , , , , , , , , , , , , , |
| | simpleSvg | Contraction Destant |
| | 🚖 SLD4raster | Category Raster |
| | sleuth Inputs | Upgrade All Uninstall Plugin Reinstall Plugin |
| | + CLVD (Camerally, Edition) | Opgrade Air Opgrade Air Opgrade Air |

2.4.4 Configuration of the plugin

Now, the Semi-Automatic Classification Plugin is installed and a dock and a toolbar should be added to QGIS. Also, a SCP menu is available in the Menu Bar of QGIS. It is possible to move the toolbar and the dock according to your needs, as in the following image.

| Project Edit View Layer Settings Plugins Vector Raster | | Processing Help | > · | | | |
|---|--|-----------------------|--|--|---|--------|
| Image: Science of the scienc | E 🕂 💽 Dist 0.010000 | t Min 60 | Max 100 🗘 😰 💿 Preview 📑 🚺 🖬 o 💠 Semi-Automatic Classification Plugin | S 200 🗘 KMU 🛛 🕹 🕅 🖗 | * = = = | » × |
| Image: Second | Filter Filter | Filter Band set ta | Band set definition Active band set 1 📮 Date NaT Band name | Root directory Center wavelength Multiplic | Tool 🙁 Help | Tool |
| | C Postprocessing Band calc Script Settings Debug Interface Processing setting | | | | ▲ ↓ ↓ | |
| | if User manual ④ Help About | | | | | |
| Image: Constraint of the second sec | | | Band quick settings Wavelength Band order | Wavelen band nubabe 2 | | |
| C Type to locate (Ctrl+K) | | | Band set tools Create virtual raster of band set (stack bands) | nd overview. Band calc expressio | | |

The configuration of available RAM is recommended in order to reduce the processing time. From the SCP menu (c. 29) select Settings > Processing .



In the *Settings* (c. 109), set the Available RAM (MB) to a value that should be half of the system RAM. For instance, if your system has 2GB of RAM, set the value to 1024MB.

| | Semi-Automat | ic Classification Plugin | | + _ □ × |
|--|---|--------------------------|------------|----------------------|
| Filter Band set Download products Basic tools Preprocessing Band processing | System Available RAM (MB) CPU threads Calculation process | | | 1024 ↓ 2 ↓ Hep |
| Postprocessing Band calc Script | Play sound when finished SMTP process notification | ✔ Raster c | ompression | |
| Settings Debug Interface Processing setting Setting | SMTP server | user | password | ▼ remember |
| Help About | Temporary directory Temporary directory External programs GDAL installation directory | | | |
| | | | | |

2.4.5 Update of required dependencies

The dependency Remotior Sensus is frequently updated. The Semi-Automatic Classification Plugin can check automatically if a new version is available, and display a message in the $SCP \ dock$ (c. 31).



It is recommended to close QGIS and update Remotior Sensus following the same installation steps described in *Installation of required dependencies* (c. 21).

2.5 Advanced installation using Conda

2.5.1 QGIS download and installation with the dependencies

The Semi-Automatic Classification Plugin requires Remotior Sensus, GDAL, NumPy and SciPy for most functionalities.

QGIS and the dependencies can be installed using a *Conda* environment (if you don't know *Conda* please read https://conda-forge.org/docs). For instance, you can use Miniforge to create a *Conda* environment.

Once installed conda, open the terminal and run the following commands to create a new environment:

```
$ conda create -c conda-forge --name environment python=3.10
Proceed ([y]/n)? y
$ conda activate environment
```

Now install QGIS and the dependencies (it could take some time):

\$ conda install -c conda-forge qgis gdal remotior-sensus scikit-learn pytorch

Now, QGIS is installed. To launch it run in the terminal:

| \$ qgis | | | |
|-----------------------------|--|---|---------------------|
| Q Untitled Project — QGIS | | | - 0 × |
| | Plugins Vector Raster Database Web Mesh Prog | cessng Hep 2 Α 🗓 🧠 🖶 🛄 🕓 😂 : 🔣 - 📄 - 🗞 - 🛶 - 🔍 🖄 🜞 Σ | |
| 🦛 😵 V° 🖉 🖷 🔛 | M. // B. / • *** kx • 2 | I ≤ B B + + I = ¶ = ¶ = ¶ = ¶ = ¶ = ¶ | 👌 😰 |
| Layers 🤞 🕼 🔍 🌄 일 🛪 🖬 🖬 🗔 | 8 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Q. Type to locate (Ctrl+K) | Ready | Coordinate 0,266° 0,206° 🛞 Scale 1:1685323 💌 🚔 Magnifier 100% 🗘 Rotation 0,0° | ₽ Render ⊕EPSG:4326 |

2.5.2 Semi-Automatic Classification Plugin installation

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| 🔇 Untit | ed Pr | oject - | – QGIS | | | | | | | | | |
|---------|-------|---------|---------------|-------------|---------|-----------------|----------------|------------------|-------------|-----------|------------|-------|
| Project | Edit | View | <u>L</u> ayer | Settings | Plugins | Vect <u>o</u> r | <u>R</u> aster | <u>D</u> atabase | <u>W</u> eb | Mesh | Processing | Help |
| | | 🌲 Mai | nage and | Install Plu | ugins | | | DC | | | | |
| | | | | SJ ∎a | ne Pyt | hon Cons | ole | | Ct | rl +Alt+P | | 1 L 🔯 |

• From the menu All, select the Semi-Automatic Classification Plugin and click the button Install plugin;

| Search Layers Segreg Seimic Positioning Data Importer Select Within Select Within Select Within Senti-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sentinel-2Download Sentinel-2Download Servia Shape Tools Shape Tools Shape Tools Shape File Encoding Fixer Shucator Shucator Shucator SingleSvg SLD4raster Sleuth Inputs SLV4raster Sleuth Inputs Stril | All | Q. Search | | | | | | | |
|--|------------------|--|---|--|--|--|--|--|--|
| Not installed Not install from ZIP Select by relationship Select Within Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sential-12 Download Serval Serval Servicios WMS - IDES Cali Shape Tools Shape File Encoding Fixer Shlocator Shlocator Single WCS 2 Single WCS 2<th></th><th>search Layers</th><th></th> | | search Layers | | | | | | | |
| Not installed Not install from ZIP Select by relationship Select Within Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Sential-12 Download Serval Serval Servicios WMS - IDES Cali Shape Tools Shape File Encoding Fixer Shlocator Shlocator Single WCS 2 Single WCS 2<th>Installed</th><th>🖕 Segreg</th><th>Semi-Automatic Classification Plugin</th> | Installed | 🖕 Segreg | Semi-Automatic Classification Plugin | | | | | | |
| Install from ZIP Select Within Install from ZIP Select Within Settings Seni-Automatic Classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Senitel-2Download Settings Servidos WMS - IDES Call Shapefile Encoding Fixer Shapefile Encoding Fixer Shucator Sinple WCS 2 SingleSvg SLD4raster Sleuth Inputs SLYR (Community Edition) Stand Strater | | 🚖 Seismic Positioning Data Importer | | | | | | | |
| Install from ZIP Select Within Settings Semi-Automatic Classification Plugin Settings Semi-Automatic Classification Plugin Settings Sentinel-ZDownload Sentinel-ZDownload Sentinel-ZDownload Serval Serval Serval Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing of images. Search and download is available for the land cover classification. This plugin requires the lang cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shape Tools Simple WCS 2 Simple Svig Subcrater Sleuth Inputs Seluth Inputs Struct Simple Svig SL/R (community Edition) Simal | Not installed | select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the | | | | | | |
| Install from ZP Semi-Automatic Classification Plugin Settings Senital-2 Download Settings Senital-2 Download Senital-2 Download Senital-2 Download Serval Senital-2 Download Serval Senital-2 Download Serval Serval Serval Serval Shape Tools Shapefile Encoding Fixer Shlocator SinpleSvg Stub Traster SumpleSvg Stub Traster SumpleSvg Stub Traster Stub Traster | | 🚖 Select Within | | | | | | | |
| Settings Sen2Cor Adapter Settings Sen2Cor Adapter Sentinel+2Download Entinel+1ub Serval Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images. providing tools for the download, the preprocessing and postprocessing of images. Search and download is available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shapefile Encoding Fixer Simple WCS 2 Simple Syg SLD4raster Steuth Inputs Surger caster, analysis, landsat, land cover, landscape, classification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel Synd Stream | Install from ZIP | 🖕 Semi-Automatic Classification Plugin | | | | | | | |
| Settings Sendage Settings Sendage Settings Sentinel-2Download Sentinel-2Download Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for the supervised classification of remote sensing images, providing tools for the download, the preprocessing and postprocessing of images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotib. For more information please visit https://fromgistors.blogspot.com . Shiptobs Simple WCS 2 Simple Svig SluPraster Sleuth Inputs Surger cassification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel Strik (Community Edition) Strik (community Edition) | | sen2Cor Adapter | | | | | | | |
| SentinelHub Serval Shapefile Encoding Fixer Shapefile Encoding | Settings | send2GE | | | | | | | |
| Servial Shape Tools | | Sentinel-2 Download | | | | | | | |
| available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Simple WCS 2 Simple Sigue | | sentinelHub | | | | | | | |
| algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please visit https://fromgistors.blogspot.com . Shore to be been been been been been been been | | serval | | | | | | | |
| Shape Tools Shape To | | 🚖 Servicios WMS - IDES Cali | | | | | | | |
| Shapefile Encoding Fixer ShLocator | | shape Tools | | | | | | | |
| Shlocator Shptoobs Simple WCS 2 Simple Svg SLP4raster Sleuth Inputs SLYR (Community Edition) String | | Shapefile Encoding Fixer | | | | | | | |
| Simple WCS 2 SimpleSvg SLO4raster Sleuth Inputs SLYR (Community Editon) Snal | | shLocator | visit riteps.// nongistors.biogspot.com . | | | | | | |
| Simple WCS 2 SimpleSvg SLD+raster Sleuth Inputs SLYR (Community Edition) Snal | | shptoobs | \Rightarrow | | | | | | |
| SLP4raster Classification, remote sensing, mask, accuracy, clip, spectral signature, supervised classification, sentinel SLYR (Community Edition) Solid | | simple WCS 2 | | | | | | | |
| SLD+raster Classification, remote sensing, mask, accuracy, clip, Sleuth Inputs SLYR (Community Edition) Snal | | simpleSvg | These maters and six fundant land around he desired | | | | | | |
| Seuth Inputs Spectral signature, supervised classification, sentinel Strat | | sLD4raster | | | | | | | |
| SLYR (Community Edition) | | Sleuth Inputs | | | | | | | |
| S Snail | | SLYR (Community Edition) | | | | | | | |
| | | snail | Vuograde All | | | | | | |

• The SCP should be automatically activated; however, be sure that the Semi-Automatic Classification Plugin is checked in the menu Installed (the restart of QGIS could be necessary to complete the SCP installation);


| All | Plugin installed successfully | 6 |
|--------------------------------------|--|--|
| Installed | Q. Search | |
| | 💁 Search Layers | |
| Not installed | segreg | Semi-Automatic Classification Plugin |
| | 🚖 Seismic Positioning Data Importer | |
| Install from ZIP | 🚖 Select by relationship | The Semi-Automatic Classification Plugin (SCP) allows for the |
| | 🚖 Select Within | supervised classification of remote sensing images, providing tools |
| Settings | V 💯 Semi-Automatic Classification Plugin | for the download, the preprocessing and postprocessing of |
| | sen2Cor Adapter | images. |
| | send2GE | |
| | 🐀 Sentinel-2 Download | Developed by Luca Congedo, the Semi-Automatic Classification Plugin (SCP) allows for |
| | 🚖 SentinelHub | the supervised classification of remote sensing images, providing tools for the |
| | 🚖 Serval | download, the preprocessing and postprocessing of images. Search and download is |
| | 🍅 Servicios WMS - IDES Cali | available for ASTER, Landsat, MODIS, Sentinel-2, and Sentinel-3 images. Several |
| | 🚖 Shape Tools | algorithms are available for the land cover classification. This plugin requires the installation of GDAL, OGR, Numpy, SciPy, and Matplotlib. For more information please |
| | 🚖 Shapefile Encoding Fixer | visit https://fromgistors.blogspot.com . |
| | shLocator | visit neepsity nongisters brogsport com . |
| | 🚖 shptoobs | ☆☆☆☆☆☆ 435 rating vote(s), 762194 downloads |
| | 🚖 Simple WCS 2 | |
| | 🚖 SimpleSvg | Colonia Destas |
| | 🚖 SLD4raster | Category Raster |
| | 🚖 Sleuth Inputs | ▼ Upgrade All Uninstall Plugin Reinstall Plugin |
| | - CIMP (Community, Falters) | ▼ Opgrade Air |

2.5.3 Configuration of the plugin

Now, the Semi-Automatic Classification Plugin is installed and a dock and a toolbar should be added to QGIS. Also, a SCP menu is available in the Menu Bar of QGIS. It is possible to move the toolbar and the dock according to your needs, as in the following image.

| Project Edit View Layer Settings Plugins Vector Raster | | Processing Help | > · | | | |
|---|--|-----------------------|--|--|--|--------|
| Image: Science of the scienc | E 🕂 💽 Dist 0.010000 | t Min 60 | Max 100 🗘 😰 💿 Preview 📑 🚺 🖬 o 💠 Semi-Automatic Classification Plugin | S 200 🗘 KMU 🛛 🕹 🕅 🖗 | * = = = | » × |
| Image: Second | Filter Filter | Filter Band set ta | Band set definition Active band set 1 📮 Date NaT Band name | Root directory Center wavelength Multiplic | Tool 🙁 Help | Tool |
| | C Postprocessing Band calc Script Settings Debug Interface Processing setting | | | | ▲ ↓ ↓ ↓ | |
| | if User manual ④ Help About | | | | | |
| Image: Constraint of the second sec | | | Band quick settings Wavelength Band order | Wavelen band nubabe 2 | | |
| C Type to locate (Ctrl+K) | | | Band set tools Create virtual raster of band set (stack bands) | nd overview. Band calc expressio | | |

The configuration of available RAM is recommended in order to reduce the processing time. From the SCP menu (c. 29) select Settings > Processing .



In the *Settings* (c. 109), set the Available RAM (MB) to a value that should be half of the system RAM. For instance, if your system has 2GB of RAM, set the value to 1024MB.


| | Semi-Automat | ic Classification Plugin | | + _ □ × |
|--|--|--------------------------|------------|----------------------|
| Filter Band set Download products Basic tools Preprocessing Band processing | System Available RAM (MB) CPU threads Calculation process | | (| 1024 ↓ 2 ↓ Hep |
| Postprocessing Band calc Script | Play sound when finished SMTP process notification | V Raster c | ompression | |
| Settings Debug Interface Processing setting | SMTP server | user | password | ✓ remember |
| User manual Help About | Send email of completed process to Temporary directory | | | |
| | External programs | | | |

2.5.4 Update of required dependencies

The dependency Remotior Sensus is frequently updated. The Semi-Automatic Classification Plugin can check automatically if a new version is available, and display a message in the $SCP \ dock$ (c. 31).



It is recommended to close QGIS and update Remotior Sensus using activating the conda environment and running the command:



Глава З

The Interface of SCP

The SCP interface is composed of several parts that are described in detail in the following paragraphs. The following video provides a brief introduction to the tools.

https://www.youtube.com/watch?v=gvSSO5LPw8s

3.1 SCP menu

The *SCP menu* allows for the selection of the main functions of the *Main Interface Window* (c. 45), the *Spectral Signature Plot* (c. 114), and the *Scatter Plot* (c. 118).





Рис. 1: SCP menu



3.2 SCP dock

The *SCP dock* allows for the the creation of ROIs (Regions Of Interest) and spectral signatures required for the classification of a *Band set* (c. 45). The *Training input* (c. 33), created with *SCP*, stores the ROI polygons and spectral signatures; depending on the algorithm, the training could be performed using ROI polygons (e.g. *Random Forest* (c. 142)) or spectral signatures (e.g. *Spectral Angle Mapping* (c. 138)).

ROIs are polygons used for the definition of the spectral characteristics of land cover classes. Spectral signatures of classes are calculated from the ROIs or can be imported from other sources (see *Import signatures* (c. 54)). It is worth pointing out that classification is always based on spectral signatures.

SCP allows for the creation of *temporary ROI polygons* using a region growing algorithm or drawn manually with the tools provided in the *Working toolbar* (c. 41). These are *temporary ROI polygons* because the ROI creation is an interactive process, and one can refine the geometry according to photointerpretion. Then, one can save *temporary ROI polygons* in the *Training input* (c. 33) which is the actual input for classifications.

The *Training input* (c. 33) is composed of a vector part that stores the geometries and a spectral signature part, which are managed by SCP. A temporary layer is added to QGIS but the actual file is saved and modified during the editing in SCP.

In SCP, land cover classes (and ROIs) are defined with a system of Classes (Class ID) and Macroclasses (Macroclass ID) (see Classes and Macroclasses (c. 135)) that are used for the classification process; each Macroclass ID is related to a Macroclass Information (e.g. macroclass name) and each Class ID is related to a Class Information (e.g. class name), but only Macroclass ID and Class ID are used for the classification process.

The use of the *Macroclass ID* or *Class ID* for classifications is defined with the option Use MC ID or C ID in the *Algorithm* (c. 76). Using *Macroclass ID* instead of *Class ID* is useful to group materials that




Рис. 2: SCP dock

belong to the same land cover class but have spectral signatures that are distant enough to be considered as different materials (e.g., different types of vegetation).

The classification can be performed for the entire image (see *Algorithm* (c. 76)) or for a part of it creating a *Classification preview* (c. 44).

The *SCP dock* contains the following tabs:

Home (c. 33)

SCP news (c. 33)

Training input (c. 33)


ROI & Signature list (c. 36)

ROI options (c. 41)

The left side of SCP dock contains buttons for accessing the main functions of SCP.

3.2.1 Home

The tab *Home* contains the buttons for accessing the main functions of *SCP*:



SCP news

This section displays news about the SCP and related services. News are downloaded on startup (internet connection required). It can be enabled or disabled in the settings *Settings* (c. 109).

3.2.2 Training input

This tool allows for the creation of the training input file (.scpx) required for storing ROIs and spectral signatures. The training input file is created according to the characteristics of the *active band set* defined in *Band set* (c. 45). A new training input file should be created for every *band set*, unless the *band sets* have the same spectral characteristics and coordinate reference system.




Рис. 3: Ноте

| SCP Dock | | | 0 🗙 |
|-----------------|--------------|--------------|-------|
| ř – L | aining input | | × |
| ROI & Signat | ture list | | |
| Filter | | | |
| E MC ID | C ID Nam | е Туре | Color |
| Filter MC ID | | | |
| | | | |
| tions | | | |
| ROI options | | | |
| | | | |
| <i>s</i> | | | |
| | | | |
| | | | |
| 🕒 🔝 | | | |
| 🔶 MC ID 🛛 1 | MC Name | Macroclass 1 | |
| CID 1 | C Name | Class 1 | |
| | ✓ Autosav | e 🗸 Signatu | ire |
| SCP Dock | | | |

Рис. 4: Training input

| Tool symbol and name | Description |
|-------------------------------|--|
| | open a training input file; ROIs and spectral signatures are loaded in $ROI \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$ |
| • | create an empty training input file (.scpx); the vector part of the training input is loaded in QGIS; also a backup file is created (a file .scpx.backup in the same directory as the file .scpx) when the QGIS project is saved; to use the backup file simply rename it deleting the ending .backup extension and open it as training input |
| Training input T | it displays the path to the training input file |
| × | remove the training input |

The training input is displayed in QGIS as vector file. ROIs and spectral signatures are displayed in the $ROI \& Signature \ list \ (c. 36).$

Предупреждение: In order to avoid data loss, do not edit the vector *Training input* using the QGIS tools. Use only the tools of *SCP* for managing the *Training input*.

ROI & Signature list

The tab ROI & Signature list displays the ROI polygons and spectral signatures contained in the training input file. The tab ROI & Signature list is structured as tree list, where every ROI is grouped in the corresponding Macroclass.

A filter for names can be defined in *Filter* \square .

The tree list *ROI* & Signature list has the following fields:

- *MC ID*: Macroclass ID is the root of corresponding ROIs and signatures; it can be edited with a single click; if the ID of a spectral signature is set 0, then pixels belonging to this signature are labelled as unclassified; every listed ROIs or signatures has a selection checkbox (only the spectral signatures checked in this list are used for the classification process);
- *C ID*: Class ID; it can be edited with a single click;
- *Name*: Macroclass and Class Name; it can be edited with a single click;
- *Type*: type of the item:
 - R =only ROI polygon;
 - -S =only spectral signature;
 - $-R\underline{S} = \text{both ROI and spectral signature;}$
- Color: C ID color; double click to select a color for the class that is used in the classification; if the ID of a spectral signature is set 0, then pixels belonging to this signature are labelled as unclassified;

Changes in the ROI & Signature list are applied to the file Training input (c. 33) only when the QGIS project is saved (but there is also the option \checkmark Autosave). ROIs can be edited, deleted and merged from this list.

| MC I | D - | CID | Name | Туре | Color |
|------|-----|-----|-----------------|------|-------|
| - 1 | | | Water | | |
| ~ | 1 | 1 | Lake | R&S | |
| ~ | 1 | 7 | Lake2 | R&S | |
| - 2 | | | Built-up | | |
| ~ | 2 | 2 | Buildings | R&S | |
| ~ | 2 | 8 | Small buildings | R&S | |
| - 3 | | | Vegetation | | |
| V | 3 | 3 | Crops | R&S | |
| ~ | 3 | 5 | Vegetation | R&S | |
| ~ | 3 | 6 | Vegetation2 | R&S | |
| - 4 | | | Bare soil | | |
| V | 4 | 4 | Low vegetation | R&S | |

Рис. 5: ROI & Signature list example

COBET: According to Algorithm (c. 76), classifications performed using C ID have the colors defined for classes in the ROI & Signature list (c. 36); classifications performed using MC ID have the colors defined for the macroclasses.

If an item is a ROI polygon, double click the item to zoom to that ROI in the map. Items in the list can be highlighted with the mouse left click.

Cobet: ROIs and spectral signatures can be imported from other sources (see *Import signatures* (c. 54)) and exported (see *Export signatures* (c. 54)).

The following tools are available.

| Tool symbol and name | Description |
|-------------------------|--|
| | merge highlighted spectral signatures or ROIs obtaining a new signature calculated as the average of signature values for each band (covariance matrix is excluded) |
| | calculate spectral signatures of highlighted ROIs using the <i>active band set</i> in <i>Band set</i> $(c. 45)$ |
| | delete highlighted ROIs and signatures |
| | show the ROI spectral signature in the <i>Spectral Signature Plot</i> (c. 114); spectral signature is calculated from the <i>Band set</i> (c. 45) |
| <u>e</u> | add highlighted ROIs to the <i>Scatter Plot</i> (c. 118) |
| | open the tab <i>Import signatures</i> (c. 54) |
| | open the tab $Export signatures$ (c. 54) and export highlighted items |

ROI & Signature list is complementary to the Working toolbar (c. 41) and it allows for saving ROIs to the Training input (c. 33) defining classes and macroclasses. A Band set (c. 45) must be defined before

| Tool symbol and name | Description |
|-------------------------------|--|
| MC ID | ROI Macroclass ID |
| MC Name T | ROI Macroclass Name |
| C ID | ROI Class ID |
| C Name T | ROI Class Name |
| | undo of ROI creation from the <i>Training input</i> (c. 33); it is possible to undo a maximum of 10 actions |
| | redo ROI creation in the <i>Training input</i> (c. 33) |
| Autosave | if checked, automatically save the ROI & Signature list to the Training input (c. 33) every time a ROI is saved |
| Signature | if checked, while saving a ROI, the spectral signature thereof is calculated (from <i>Band set</i> (c. 45) pixels under ROI polygon) and saved to <i>Training input</i> (c. 33) (calculation time depends on the band number of the <i>active band set</i> in <i>Band set</i> (c. 45)) |
| | save the temporary ROI to the <i>Training input</i> (c. 33) using the defined classes and macroclasses; ROI is displayed in the <i>ROI</i> \mathcal{C} Signature list (c. 36) |

the ROI creation, and ROI polygons must be inside the area of the Band set.

Right click menu

A right click on $ROI \ & Signature \ list$ (c. 36) allows for opening a menu containing several functions to manage ROIs and spectral signatures.

| 🔎 Zoom to |
|------------------------|
| Check/uncheck |
| Clear selection |
| Collapse/expand all |
| Change MC ID |
| Change color |
| 🏠 Merge items |
| Calculate signatures |
| Delete items |
| 🖉 Add to spectral plot |
| ᄰ Add to scatter plot |
| 2 Properties |
| 🛃 Import |
| 🚮 Export |

Рис. 6: Right click menu

| Tool symbol and name | Description |
|-------------------------------|---|
| Joo m to | zoom to highlighted items (if ROI polygons) in the map |
| Check/unc | check or uncheck highlighted items |
| Clear selection | clear selection of highlighted items |
| Collapse/e | collapse or expand all macroclasses |
| Change MC ID | edit the macroclass of highlighted items (using the value $MC ID$ is displayed in ROI is Signature list (c. 36)); if a macroclass is selected, the function is performed to all the included items |
| Change color | select a color for the highlighted items; if a macroclass is selected, the function is performed to all the included items |
| Merge items | merge highlighted spectral signatures or ROIs obtaining a new signature calculated as the average of signature values for each band (covariance matrix is excluded); if a macroclass is selected, the function is performed to all the included items |
| Calculate signatures | calculate spectral signatures of highlighted ROIs using the <i>active band set</i> in <i>Band set</i> (c. 45); if a macroclass is selected, the function is performed to all the included items |
| Delete items | delete highlighted ROIs and signatures; if a macroclass is selected, the function is performed to all the included items; |
| Add to spectral plot | show the ROI spectral signature in the <i>Spectral Signature Plot</i> (c. 114); spectral signature is calculated from the <i>Band set</i> (c. 45); if a macroclass is selected, the function is performed to all the included items |
| Add to scatter plot | add highlighted ROIs to the <i>Scatter Plot</i> (c. 118); if a macroclass is selected, the function is performed to all the included items |
| ff Properties | show the properties of highlighted items; |
| $\boxed{\underbrace{Import}}$ | open the tab Import signatures (c. 54) |
| Export | open the tab <i>Export signatures</i> (c. 54) and export highlighted items |

3.2.3 ROI options

ROI options are useful for displaying pixel values or improving the creation of ROIs.

| Tool symbol and name | Description |
|---|--|
| Displaț | if the ROI creation pointer is active (see <i>Working toolbar</i> (c. 41)), the pixel value of selected vegetation index is displayed on the map; vegetation indices available in the combo box are: * NDVI (Normalized Difference Vegetation Index); NDVI requires the near-infrared and red bands; * EVI (Enhanced Vegetation Index); EVI requires the blue, near-infrared and red bands converted to reflectance; wavelengths must be defined in the <i>Band set</i> (c. 45); * Custom; use the custom expression defined in the following line |
| T | set a custom expression; expression is based on the <i>Band set</i> and bands such as band 1 is referred to as «b1», band 2 as «b2» and so on; also reference to band names such as « $\#$ NIR $\#$ » or « $\#$ RED $#$ » can be used |
| Rapid ROI b. 10 | if checked, temporary ROI is created with region growing using only one <i>Band set</i> (c. 45) band (i.e. region growing is rapider); the band is defined by the <i>Band set</i> number; if unchecked, ROI is the result of the intersection between ROIs calculated on every band (i.e. region growing is slower, but ROI is spectrally homogeneous in every band) |
| Auto- plot | calculate automatically the temporary ROI spectral signature and display it in the <i>Spectral Signature Plot</i> (c. 114) (MC Name of this spectral signature is set tempo_ROI) |
| Auto- refresh ROI | calculate automatically a new temporary ROI while <i>Region growing parameters</i> in the <i>Working toolbar</i> (c. 41) are being changed |
| | defines the maximum number of action for undo and redo ROIs; the higher is the number, the more is the required memory |

3.3 Working toolbar

The Working toolbar allows for creating temporary ROIs and classification previews.

- Image control (c. 43)
- Temporary ROI (c. 43)
- Classification preview (c. 44)

The functions are described in detail in the following paragraphs.

| SCP Dock | 9 X |
|--|------------|
| B □ Display NDVI ▼ P ✓ Rapid ROI b. 1 ‡ | |
| ✓ Rapid ROI b. 1 ♀ Image: Auto-plot Auto-refresh ROI Maximum training buffer 5 ♀ Storido IO2 Storido IO2 | |
| | |
| SCP Dock | |

Рис. 7: ROI options

| 📆 🔎 🖲 RGB = 🛛 - | - 🔊 🔊 🔊 🔊 🗸 | E 🗄 | Dist 0.010000 | \$ Min 60 | \$ Max 100 | ¢ 🔎 | 💿 Preview 🚦 | 0 T | \$ 200 | ¢ KML |
|-----------------|-------------|-----|----------------------|-----------|------------|-----|-------------|-----|--------|-------|
| | | | | | | | | | | |


Рис. 8: Working toolbar

3.3.1 Image control

| Tool symbol and name | Description |
|-------------------------------|--|
| | show the Main Interface Window (c. 45) |
| \geqslant | zoom the map to the extent of the <i>active band set</i> in <i>Band set</i> (c. 45); |
| • <i>RGB</i> = • | use the button to show/hide the <i>active band set</i> in <i>Band set</i> (c. 45) in the map; from the list select a <i>Color Composite</i> (c. 133) that is applied to the <i>Band set</i> (c. 45); new color composites can be entered typing the band numbers separated by - or ; or , (e.g. RGB = 4-3-2 or RGB = 4;3;2 or RGB = 4,3,2) |
| % | display the input image stretching the minimum and maximum values according to cumulative count of current map extent |
| a | display the input image stretching the minimum and maximum values according to standard deviation of current map extent |

3.3.2 Temporary ROI

A temporary ROI is a temporary polygon displayed in the map, which can be saved permanently in the *Training input* (c. 33). A temporary ROI can be drawn manually or using a *Region Growing Algorithm* (c. 134) (i.e. the image is segmented around a pixel seed including spectrally homogeneous pixels).



Region growing parameters: the following parameters are required for the ROI creation using a region growing algorithm on the *Band set* (c. 45):

| Tool symbol and name | Description |
|-------------------------------|--|
| Dist 10 | set the interval which defines the maximum spectral distance between the seed pixel and the surrounding pixels (in radiometry unit) |
| | set the minimum area of a ROI (in pixel unit); this setting overrides the Range radius until the minimum ROI size is reached; if Rapid ROI on band is checked, then ROI will have at least the size defined Min ROI size; if Rapid ROI on band is unchecked, then ROI could have a size smaller than Min ROI size |
| | set the maximum width of a ROI (i.e. the side length of a square, centred at the seed pixel, which inscribes the ROI) in pixel unit |

3.3.3 Classification preview

Classification preview allows for displaying temporary classifications (i.e. classification previews). Classification previews are useful for testing the algorithm in a small area of the *Band set* (c. 45), before classifying the entire image which can be time consuming.

Classification preview is performed according to the parameters defined in Algorithm (c. 76).

Предупреждение: ROIs and previews are performed on the active *Band set* (c. 45).

After the creation of a new preview, old previews are placed in QGIS Layers inside a layer group named Class_temp_group and are deleted when the QGIS session is closed.

Предупреждение: Classification previews are automatically deleted from disk when the QGIS session is closed; a QGIS message (that can be ignored) could ask for the path of missing layers when opening a previously saved project.

| Tool symbol and name | Description |
|-------------------------|---|
| | zoom the map to the extent of the last $Classification preview$ (c. 44) |
| • Preview | use the button to show/hide the last $Classification \ preview$ (c. 44) in the map |
| | activate the pointer for the creation of a <i>Classification preview</i> (c. 44); left click the map to start the classification process and display the classification preview |
| | create a new $Classification \ preview$ (c. 44) centred at the same pixel as the previous one |
| T 1 | change dynamically the classification preview transparency, which is useful for comparing the classification to other layers |
| S 1\$ | size of the preview in pixel unit (i.e. the side length of a square, centred at the clicked pixel) |
| KML | create a KML file of the QGIS view |

3.4 Main Interface Window

The Main Interface Window is composed of several tabs described in detail in the following paragraphs. Tabs can be selected through the tree menu at the left side or from the SCP menu (c. 29).

3.4.1 Band set

- Band set definition (c. 46)
- Band quick settings (c. 47)
- Band set table (c. 48)
- Band set tools (c. 48)

Image input in SCP is named *band set*. This tab allows for the definition of one or multiple *band sets* to be used as input for classification and other tools.

Band sets are identified by numbers. The active band set (i.e. the one selected in Band set definition (c. 46)) is used as input for several tools in SCP dock (c. 31) and the Working toolbar (c. 41). Other SCP tools allow for the selection of band set numbers.

The *Band set* definition is saved with the QGIS project.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Following a video tutorial about this tool.

https://www.youtube.com/watch?v=DQXfBPke2J4

| 1 | | Semi-Automa | tic Classification Plugin | | | <u>+ -</u> |
|---|----------------|---|---------------------------------------|-----------------------------|----------------------|--------------|
| er Band set | Filter | Band set definition Active band set 1 🗘 Date NaT | | Root directory | | |
| Download Basic tools Preprocess Band process | Band set table | e Band name | Center wavelength Multiplie | icative Factor Additive Fac | tor Wavelength | n unit |
| Postproces Band calc Script Settings User manu Help About | | | | | | • |
| | | | | | | |
| | | ₹ Band quick settings | | | | |
| | | Wavelength Band order Band set tools Create virtual raster Greate virtual raster (stack bands) Greate set | id band overviews 🗌 Band calc express | | t band number 💌 Date | 2020-01-01 ¥ |

Рис. 9: *Band set*

Band set definition

A *band set* is basically a list of bands defined as the following table.

| Band name | Center wavelength | Multiplicative Factor | Additive Factor | Wavelen≀ P unit | Path | Date |
|--|--|---------------------------------------|---------------------------------|--------------------|------|------------------------------|
| name of the band (it cannot be edited) | center of the wavelength of the band | multiplicative rescaling factor | additive rescaling factor | - | | image acquisition date |

It is possible to add to the *active band set* one or more bands already loaded in QGIS, or select files that are not loaded. A *Date* can be assigned to a *band set* which can be later used in other tools to select *band sets* by date. Also, a *Root directory* for band paths can be defined, which can be useful to create projects with relative paths.

The following tools are available.

| Tool symbol and | Description |
|-----------------|--|
| name | |
| | open file explorer and add raster files (preferably single band raster) to the $active \ band \ set$ |
| Ð | open a window to select rasters already loaded in QGIS and add them to the $active\ band\ set$ |
| 1 | move highlighted bands upward |
| + | move highlighted bands downward |
| b. | sort automatically bands by name, giving priority to the ending numbers of name |
| | remove highlighted bands from the <i>active band set</i> |
| × | clear all bands from active band set |
| ↓ | import a previously saved <i>active band set</i> from file |
| 1 | export the <i>active band set</i> to a file |

It is possible to define a multiplicative rescaling factor and additive rescaling factor for each band (for instance using the values in Landsat metadata), which are used on the fly (i.e. pixel value = original pixel value * multiplicative rescaling factor + additive rescaling factor) during the processing.

The *Center wavelength* of bands should be defined in order to use several functions of *SCP*. If the *Center wavelength* of bands is not defined, the band number is used and some *SCP* tools will be disabled.

Band quick settings

These tools allow for quickly set attributes of the *active band set*.

| Tool symbol and name | Description |
|----------------------|---|
| Wavelength | rapid definition of band center wavelength for the following satellite sensors: * Band order * ASTER * GeoEye-1 * GOES * Landsat 8 OLI * Landsat 7 ETM+ * Landsat 4-5 TM * Landsat 1, 2, and 3 MSS * MODIS * Pleiades * QuickBird * RapidEye * Sentinel-2 * Sentinel-3 * SPOT 4, 5, and 6 * WorldView-2 and WorldView-3 |
| | open a csv file of wavelength values (center wavelength separated by comma or new line) |
| Wavelength unit | select the wavelength unit among: Band number: no unit, only band number μm: micrometres nm: nanometres |
| | set the date of acquisition |

Band set table

The table on the left side is the *Band set table*. It includes the list of all the defined *band sets* (the names of the first bands are displayed), which can be selected with a left click. Double click on a table item can be used to define the *Active band set*.

A *Filter* can be used to display *band sets* in the table matching a name.

The following tools are available for managing band sets.

| Tool symbol and name | Description |
|----------------------|--|
| 10 | add a new empty band set |
| | remove highlighted band sets |
| 2 | sort band sets by date |
| • | move highlighted band sets upward |
| • | move highlighted band sets downward |
| | display the RGB color composite of selected $band\ sets$ (a virtual raster is added in QGIS) |

Band set tools

Band set tools are tools that can be executed directly on *Active band set*. Multiple tools can be selected by the corresponding check box. This can also be useful to automate the processing during image conversion.

| Tool symbol and name | Description |
|---|---|
| Create virtual raster of band set | create a multiband virtual raster of Active band set |
| Create raster of band set (stack bands) | stack bands in a single multiband raster |
| Build band overview | build band overview of Active band set |
| Band calc expression | execute the expression defined in $Band \ calc$ (c. 99) |
| | execute selected tools |

3.4.2 Download products

• *Search* (c. 49)

- Search parameters (c. 50)
- Product list (c. 51)
- Download (c. 51)
- Login data (c. 52)
 - Login Harmonized Landsat Sentinel-2 (c. 53)

| _ | Login | Copernicus | Data Spa | ce Ecosystem | (c. | 53 |) |
|---|-------|------------|----------|--------------|-----|----|---|
| | | | | | | | |

| | Semi-/ | Automatic Classification Plugin | | | + _ □ × |
|--|--|--|---|---|---|
| 🔎 Search 👗 Login data | | | | | 50 Tool |
| Search parameters UL X (Lon) | Y (Lat) | LR X (Lon) | Y (Lat) | 1 | ● Show + 문 |
| Products Sentinel-2 Results 20 Advanced search | | Date from 2022-02-17 💌 to 202 | 2-09-10 💌 | Max c | loud cover (%) 100 🖨 |
| Add OpenStreetMap to the map | (© <u>OpenStreetMap</u> contributor | s. The cartography is licensed as CC BY- | -SA. <u>Tile Usage Policy</u>) Filter | | |
| product | image | product_id a | icquisition_date clou | | |
| | | | | | |
| | | | | Preview | |
| ∢ Download | | | • | | |
| | | | ✔ 8A ✔ 9 ✔ 10 | ✔ 11 ✔ 12 | Ancillary data |
| | Search parameters UL X (Lon) Products Sentinel-2 • Results 20 • Advanced search im Add OpenStreetMap to the map Product list product list Download Bands V 1 V 2 V | Search Login data Search parameters Uk (Lon) Uk (Lon) Y (Lat) Products Sentinel-2 Results 20 th Advanced search Image Product list product image Image Image Image Image Image Image Image Image Image Image Image Image | Search parameters UL X (Lon) Vroducts Sentinel-2 * Date from 2022-02-17 * to 202 Results 20 * Advanced search | Search Login data Search parameters UL V(Lon) Y(Lat) LR X(Lon) Y(Lat) Products Sentinel-2 Date from 2022-02-17 to 2022-09-10 Results 20 Advanced search Image OpenStreetMap to the map (@ OpenStreetMap contributors. The cartography is licensed as CC BY-SA. Tile Usage Policy) Filter Product ist Filter Filter product image product_id acquisition_date clou 4 | Search Login data Search parameters U UL Y (Lat) Products Sentinel-2 Date from 2022-02-17 to 2022-09-10 Max comparameters Max comparameters UL X (Lon) Y (Lat) Products Sentinel-2 Date from 2022-02-17 to 2022-09-10 Results 20 Advanced search Filter Filter Product Ist Filter Filter product image product_id acquisition_date clou Image product_id acquisition_date clou Preview Image product_id acquisition_date clou Preview Image Image Product_id acquisition_date clou Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Image Imag |



The tab *Download products* includes the tools for searching and downloading free remote sensing images. The search and download is performed through Remotior Sensus. Also, automatic conversion to reflectance of downloaded bands is available.

COBET: Information about APIs of this tool in Remotior Sensus at this link .

An internet connection is required and free registration could be required depending on the download service.

Following a video tutorial about this tool.

https://www.youtube.com/watch?v=NwL2f5Nrn3U

Search

The Search tool allows for searching and downloading:

- Sentinel-2: Copernicus Sentinel-2 images (Level-1C and Level-2A) acquired from 2015 to present days;
- Landsat_MPC: Landsat Collection images acquired from August 1982 to present days, such as Landsat 5, 7, 8, 9 (data retrieved from Microsoft Planetary Computer);
- Sentinel-2_MPC: Copernicus Sentinel-2 Level-2A acquired from 2015 to present days (data retrieved from Microsoft Planetary Computer);
- Landsat_HLS: Landsat from Harmonized Landsat Sentinel-2 by NASA which are surface reflectance data product (generated with Landsat 8, Landsat 9, and Sentinel-2 data acquired from 2013 to present days) with observations every two to three days at 30m spatial resolution (more information about the project);
- Sentinel-2_HLS: Sentinel-2 from Harmonized Landsat Sentinel-2 by NASA which are surface reflectance data product (generated with Landsat 8, Landsat 9, and Sentinel-2 data acquired from

2013 to present days) with observations every two to three days at 30m spatial resolution (more information about the project);

- *MODIS_09Q1_MPC*: MODIS Surface Reflectance 8-Day (250m) (data retrieved from Microsoft Planetary Computer);
- *MODIS_11A2_MPC*: MODIS Land Surface Temperature 8-Day (data retrieved from Microsoft Planetary Computer);
- *ASTER_MPC*: ASTER L1T (data retrieved from Microsoft Planetary Computer);
- Copernicus_DEM_30_MPC: Copernicus DEM GLO-30 (data retrieved from Microsoft Planetary Computer);

The download of Harmonized Landsat Sentinel-2 requires credentials defined in Login data (c. 52).

Search parameters

Define the search area by entering the coordinates (longitude and latitude) of an Upper Left (UL) point and Lower Right (LR) point and select a product to search. Optional settings are date of acquisition, maximum cloud cover, number of results (the fewer the results, the faster is the query).

The definition of a search area is required before searching the images.

| Tool symbol and name | Description |
|--|---|
| UL 1\$ | set the UL longitude X (Lon) and the UL latitude Y (Lat) |
| LR 1\$ | set the LR longitude X (Lon) and the LR latitude Y (Lat) |
| • Show | show or hide the search area in the map; |
| + | define a search area by left click to set the UL point and right click to set the LR point; the search area is displayed in the map |
| Products | set the search product |
| Date from | set the starting date of acquisition |
| to 1980 v | set the ending date of acquisition |
| $\begin{array}{c} Max & cloud \\ cover & (\%) \\ \hline 1 \\ \hline \end{array}$ | maximum cloud cover in the product |
| Results 10 | maximum number of products returned by the search |
| Advanced search T | some services (e.g. Sentinel-2) allows for entering search parameters; for instance, it is possible to enter the name of a granule (e.g. 33TTG) |
| Filter T | set a filter such as the Product ID (e.g. LC81910312015006LGN00); it is possible to enter multiple Product IDs separated by comma or semicolon (e.g. LC81910312015006LGN00, LC81910312013224LGN00); filter is applied to resulting products in the search area |
| Find 风 | find the products in the search area; results are displayed inside the table in $Product$ list (c. 51); results are added to previous results |
| Add OpenStreetMa to the map | this button allows for the display of OpenStreetMap tiles (© OpenStreetMap contributors) in the QGIS map as described in https://wiki.openstreetmap.org/wiki/QGIS . The cartography is licensed as CC BY-SA (Tile Usage Policy) |

COBET: Search results (and the number thereof) depend on the defined area extent and the range of dates. In order to get more results, perform multiple searches defining smaller area extent and narrow acquisition dates (from and to).

Product list

The table *Product list* contains the results of the search. Click on any item (highlight the item) to display the image preview thereof (not all the products include image previews). Resulting products are saved with the QGIS project.

The table includes the following fields.

| produ | imag | prodı | acqui | $cloud_{_}$ | zone_p | row | \min_{-} | \min_{-} | max_ | max_ | collec | size | previ | uid | ref_url |
|-------|--------------|-----------------|----------------------------|----------------------------|-------------------------------------|------------|---------------------|--------------------|---------------------|--|--------|------|-------|-------------------|------------------|
| - | imag nam(| ID of the | acqui date of the | of cloud cover in | zone or WRS path depend | WRS row | latitı of the | longi of the | latitı of the | $\begin{array}{c} \mathrm{longi}_{1} \\ \mathrm{of} \\ \mathrm{the} \end{array}$ | | - | | of the item | reference URL |

The following tools are available.

| Tool symbol and name | Description |
|-------------------------|---|
| | display preview of highlighted images in the map; preview is roughly georeferenced on the fly (not all the products include a preview) |
| | remove highlighted images from the list |
| × | remove all images from the list |
| $\mathbf{+}$ | import the product list from an XML file |
| 1 | export the product list to an XML file |

Download

Download the products in the *Product list* (c. 51). During the download it is recommended not to interact with QGIS.

Depending on the download service, it is possible to select single bands for download.

| Tool symbol and name | Description |
|-------------------------------|---|
| Band X | select bands for download |
| Ancillary data | if checked, the metadata files are selected for download |
| | select or deselect all bands |
| Only if preview on Layers | if checked, download only those images listed in $Product \ list$ (c. 51) which are also listed in the QGIS layer panel |
| Preprocess images | if checked, bands are automatically converted after the download |
| \bigcirc Load bands in QGIS | if checked, bands are loaded in QGIS after the download |
| 1 | export the download links to a text file (.csv) |
| RUN | start the download process of all the products listed in $Product \ list$ (c. 51) |

Login data

| | | Semi-Automatic Classification Plugin 🔶 | - 🗆 X |
|------|-----------------------------|---|--------|
| Filt | er F Band set | 🔎 Search 👗 Login data | 5 Tool |
| • | Basic tools | Login Harmonized Landsat Sentinel-2 (<u>https://urs.earthdata.nasa.gov</u>) | ۲ |
| • | Preprocessing | User Password remember | Help |
| | Band processing | Login Copernicus Data Space Ecosystem (<u>https://dataspace.copernicus.eu/</u>) | Ρ |
| | Postprocessing Band calc | User Password remember | |
| | Script | | |
| | 🕺 Settings | | |
| | User manual Help | | |
| | Help About | | |
| L 1 | About | | |
| | | | |
| | | | |
| | | Download | |
| | | Bands 🗸 1 🗸 2 🗸 3 🗸 4 🗸 5 🗸 6 🗸 7 🗸 8 🗸 8A 🗸 9 🗸 10 🗸 11 🗸 12 🗸 Ancillary data | |
| | | ✓ Only if preview in Layers ✓ Preprocess images 🗌 Load bands in QGIS 🗌 Virtual download 👔 🔃 | |

Рис. 11: Login data

Login Harmonized Landsat Sentinel-2

The download of Harmonized Landsat Sentinel-2 requires to login using EOSDIS Earthdata credentials (https://urs.earthdata.nasa.gov) One can register for free at https://urs.earthdata.nasa.gov/users/new .

| Tool symbol and name | Description |
|----------------------|---|
| User T | enter the user name |
| Password 💶 🎈 | enter the password |
| 🔽 remember | if checked, remember user name and password locally in QGIS |

| Предупреждение: | $_{ m If}$ | remember | is | checked, | the | password | is | stored | unencrypted | in | QGIS |
|-----------------|------------|----------|----|----------|-----|----------|----|--------|-------------|----|------|
| registry. | | | | | | | | | | | |

Login Copernicus Data Space Ecosystem

Г

The download of Sentinel-2 is available also using Copernicus Data Space Ecosystem credentials (https://dataspace.copernicus.eu). One can register for free at https://dataspace.copernicus.eu .

| Tool symbol and name | Description |
|----------------------|---|
| User 💶 🔹 | enter the user name |
| Password T | enter the password |
| ✓ remember | if checked, remember user name and password locally in QGIS |

| Предупреждение: | If \checkmark | remember | is | checked, | the | password i | is stored | unencrypted | in | QGIS |
|-----------------|-----------------|----------|----|----------|-----|------------|-----------|-------------|----|------|
| registry. | | | | | | | | | | |

3.4.3 Basic tools

The tab Basic tools includes several tools for manipulating input data.

Export signatures

| | Semi-Automatic Classification Plugin | + _ D X |
|-----------------------|---|---------|
| lter | | |
| <i>i</i> Band set | Export | |
| 👆 Download products | Export as training file (*.scpx) | |
| Basic tools | | |
| Export signatures | Export geometries as shapefile (*.shp) or geopackage (*.gpkg) | |
| 🛃 Import signatures | Export spectral signatures as CSV file (.csv) | |
| Multiple ROI creation | Export spectral signatures as CSV file (CSV) | |
| 🙀 RGB composite | | |
| Signature threshold | | |
| Preprocessing | | |
| 🔖 Band processing | | |
| Postprocessing | | |
| 🛗 Band calc | | |
| script | | |
| 🔆 Settings | | |
| User manual | | |
| 🕑 Help | | |
| 🤛 About | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



This tool allows for exporting the signatures highlighted in the ROI & Signature list (c. 36).

| Tool symbol and name | Description |
|--|--|
| Export as SCP file | create a new .scp file and export highlighted ROIs and spectral signatures as <i>SCP</i> file (.scpx) |
| Export as shapefile or geopackage | export highlighted ROIs (spectral signature data excluded) as a new shapefile (.shp) or geopackage (.gpkg) |
| Export spectral signatures as CSV file | open a directory, and export highlighted spectral signatures as individual CSV files (.csv) separated by semicolon (;) |

Import signatures

- Import library file (c. 55)
- Import vector (c. 55)
- Download USGS Spectral Library (c. 56)

The tab *Import signatures* allows for importing spectral signatures from various sources.

Import library file

| | Semi-Automatic Classification Plugin | + <u>-</u> | • × |
|-----------------------|---|------------|------|
| Filter | | | |
| and set | Download USGS Spectral Library | | Tool |
| 👆 Download products | Import vector | _ | |
| 👻 📐 Basic tools | | | ۲ |
| Export signatures | Import library file | | Help |
| 🛃 Import signatures | | _ | þ |
| Multiple ROI creation | Select a file: training file (*.scpx); USGS library (*.zip); ASTER library (*.txt); CSV (*.csv) | | |
| RGB composite | | _ | |
| Signature threshold | | | |
| Preprocessing | | | |
| 🕨 🏟 Band processing | | | |
| Postprocessing | | | |
| 🛗 Band calc | | | |
| Script | | | |
| 🕨 🔆 Settings | | | |
| User manual | | | |
| Help | | | |
| P About | | | |
| | | | |
| | | | |

Рис. 13: Import library file

This tool allows for importing spectral signatures from various sources: a previously saved *Training input* (c. 33) (.scpx file); a USGS Spectral Library (.asc file); a previously exported .csv file. In case of USGS Spectral Library, the library is automatically sampled according to the image band wavelengths defined in the *Band set* (c. 45), and added to the *ROI* & *Signature list* (c. 36);

| Tool symbol and name | Description |
|----------------------|---|
| Select a file | open a file to be imported in the <i>Training input</i> (c. 33) |

Import vector

| | | Semi-Automatic Classification | Plugin | | + _ C | × |
|--|------------------------------|-------------------------------|------------|------------------------------------|-----------------|--------|
| Filter | Download USGS Spectral Lib | prary | | | | too |
| Band Set Download products E Basic tools | Import vector | | | | | • ⊛ |
| Export signatures | Select a vector (*.shp;*.gpk | .g) | | | | Help |
| Multiple ROI creation | Vector fields | | | | | |
| 🙀 RGB composite | MC ID field | MC Name field | C ID field | C Name field | | |
| Signature threshold | | - | • | • | | |
| Preprocessing | | • | | | • | |
| 🕨 🏟 Band processing | | | | Calculate sig. | Import vector 🚺 | |
| 🕨 🚭 Postprocessing | | | | | | |
| 🔛 Band calc | | | | | | |
| Script | | | | | | |
| 🕨 🔆 Settings | | | | | | |
| User manual | | | | | | |
| Help | | | | | | |
| P About | Import library file | | | | | |

Рис. 14: Import vector

This tool allows for importing a vector (shapefile or geopackage), selecting the corresponding fields of the *Training input* (c. 33).

| Tool symbol and name | Description |
|----------------------|---|
| Select a vector | open a vector |
| MC ID field | select the vector field corresponding to MC ID |
| MC Name field | select the vector field corresponding to MC Name |
| $C \ ID \ field$ | select the vector field corresponding to C ID |
| C Name field | select the vector field corresponding to C Name |
| Calculate sig. | if checked, the spectral signature is calculated while the ROI is saved to $Training$ input (c. 33) |
| Import vector | import all the vector polygons as ROIs in the $Training input$ (c. 33) |

Download USGS Spectral Library

| | Semi-Automatic Classification Plugin | • - | • × |
|-----------------------|---|----------|------|
| Filter | | | |
| and set | Download USGS Spectral Library | | Tool |
| Le Download products | | | 2 |
| Basic tools | Select a chapter | * | ۲ |
| Export signatures | | | Ŧ |
| Import signatures | Select a library | * | Help |
| Multiple ROI creation | Import spectral library | | |
| RGB composite | | | |
| Signature threshold | Library Description (requires internet connection) | | |
| Preprocessing | | | |
| Band processing | | | |
| Postprocessing | | | |
| Band calc | | | |
| Script | | | |
| Settings | | | |
| User manual | | | |
| Help | | | |
| P About | | | |
| | | | |
| | | _ | |
| | USGS Spectral Library Version 7 downloaded from https://crustal.usgs.gov/speclab/QueryAll07a.php. Reference: Kokaly, R.F., Clark, R.N., Swayze, G.A., Livo, K.E., Hoefen, T.M., Pearson, N.C., Wise, R.A., Benzel, W.M., Lowers, H.A., Driscoll, R.L., and Klein, A.J., 2017, USGS Spectra | | |
| | Library Version 7: U.S. Geological Survey Data Series 1035, 61 p., https://doi.org/10.3133/631035. | | |
| | , , | | |
| | Import vector | | |
| | Import library file | | |
| | | <u> </u> | |
| 1 | | | |

Рис. 15: Download USGS Spectral Library

The tab *Download USGS Spectral Library* allows for the download of the USGS spectral library (Clark, R.N., Swayze, G.A., Wise, R., Livo, E., Hoefen, T., Kokaly, R., Sutley, S.J., 2007, USGS digital spectral library splib06a: U.S. Geological Survey, Digital Data Series 231).

The libraries are grouped in chapters including Minerals, Mixtures, Coatings, Volatiles, Man-Made, Plants, Vegetation Communities, Mixtures with Vegetation, and Microorganisms.

An internet connection is required.

| Tool symbol and name | Description |
|-------------------------------|---|
| Select a chapter | select one of the library chapters; after the selection, chapter libraries are shown in $Select\ a\ library$ |
| Select a library | select one of the libraries; the library description is displayed in the frame <i>Library description</i> |
| Import spectral library | download the library and add the sampled spectral signature to the <i>ROI</i> \bigotimes <i>Signature list</i> (c. 36) using the parameters defined for class and macroclass; the library is automatically sampled according to the image band wavelengths defined in the <i>active band set</i> in <i>Band set</i> (c. 45), and added to the <i>ROI</i> \bigotimes <i>Signature list</i> (c. 36) |

COBET: Spectral libraries downloaded from the USGS Spectral Library can be used with Minimum Distance or Spectral Angle Mapping algorithms, but not Maximum Likelihood because this algorithm needs the covariance matrix that is not included in the spectral libraries.

Multiple ROI Creation

- Create random points (c. 58)
- Point coordinates and ROI definition (c. 58)

| | Semi-Automatic Classification Plugin | ↑ _ □ X |
|--|---|---------|
| Filter Band set Download products Basic tools Import signatures Import signatures Import signatures Signature threshold Perprocessing Band processing Band calc Script Settings User manual Help About | Create random points Number of points 100 ‡ inside grid 10000 ‡ min distance 100 ‡ Create points stratified for the values raster > 0 of first band of band set Image: Create point coordinates and ROI definition X Y MC ID MC Name C ID C Name Min Max Dist Rapid ROI b | • нер |
| | Run Calculate sig. | |



This tab allows for the automatic creation of ROIs, useful for the rapid classification of multi-temporal images, or for accuracy assessment. Given a list of point coordinates and ROI options, this tool performs the region growing of ROIs. Created ROIs are automatically saved to the *Training input* (c. 33). The *active band set* in *Band set* (c. 45) is used for calculations.

Create random points

| Tool symbol and name | Description |
|---|---|
| Number of points | set a number of points that will be created when <i>Create points</i> is clicked |
| inside grid 1 1 1 1 1 | if checked, the <i>band set</i> area is divided in cells where the size thereof is defined in the combobox (image unit, usually meters); points defined in Number of random points are created randomly within each cell |
| $\begin{array}{ c c }\hline & & min \\ \hline distance \\ \hline 1 \\ \hline \end{array}$ | if checked, random points have a minimum distance defined in the combobox (image unit, usually meters); setting a minimum distance can result in fewer points than the number defined in <i>Number of points</i> |
| Create points | create random points inside the <i>band set</i> area |
| stratified for the values T | if checked, create random points inside the values defined in the expression calculated for the first band of the defined band set; the expression must include the variable raster ; multiple expressions can be entered separated by semicolon (;) but the total number of stratified points is the same as the defined <i>Number of points</i> |
| of the first band of band set | defines the band set in \checkmark stratified for the values |

Point coordinates and ROI definition

The table Point coordinates and ROI definition contains the following fields.

| Х | Y | MC ID | MC Name | C ID | C Name | Min | Max | Dist | Rapid ROI band |
|------------|------------|------------|------------|-------------|--------------|--------|--|---|---|
| X coord | Y coord | Macr ID | Name | Class ID | Class Nam | minimu | the maximu width of a ROI (in pixel unit) | the interval which defines the maximum spectral distance between the seed pixel and the surrounding pixels (in radiometry unit) | if a band number is defined, ROI is created only using the selected band, similarly to <i>Rapid</i> <i>ROI band</i> in <i>ROI &</i> <i>Signature list</i> (c. 36) |

The following tools are available.

| Tool symbol and name | Description |
|-------------------------------|--|
| • | add a new row to the table; all the table fields must be filled for the ROI creation |
| | delete the highlighted rows from the table |
| Ŧ | import a point list from text file or a point shapefile to the table; in case of text file, every line must contain values separated by tabs of X, Y, MC ID, MC Name, Class ID, C Name, Min, Max, Dist, and optionally the Rapid ROI band; in case of shapefile, only point coordinates are imported |
| | export the point list to text file |
| Calculat sig. | if checked, the spectral signature is calculated while the ROI is saved to <i>Training input</i> (c. 33) |
| | start the ROI creation process for all the points and save ROIs to the <i>Training input</i> (c. 33) |

RGB composite

- *RGB composite* (c. 60)
- Automatic RGB (c. 60)

| | Semi-Automatic Classification Plugin | + _ = × |
|-----------------------|--------------------------------------|---------|
| Filter | | |
| 🥌 Band set | RGB composite | Tool |
| 👆 Download products | RGB | |
| 👻 📐 Basic tools | 1 3-2-1 | |
| Export signatures | 2 4-3-2 | U U Hep |
| 🛃 Import signatures | 3 74-3 | ē |
| Multiple ROI creation | | |
| RGB composite | | |
| Signature threshold | | |
| Preprocessing | | |
| Band processing | | |
| Postprocessing | | |
| 🛗 Band calc | | |
| Script | | |
| 🕨 🔆 Settings | | |
| User manual | | |
| Help | | × |
| P About | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | Automatic RGB | |
| | | |
| | Band combinations 🚺 | |
| | | |



This tab allows for managing the RGB *Color Composite* (c. 133) used in the list RGB = of the *Image* control (c. 43).

RGB composite

The table RGB composite contains the field RGB that allows for entering an RGB combination.

| Tool symbol and name | Description |
|----------------------|---|
| • | move highlighted RGB combination upward |
| + | move highlighted RGB combination downward |
| a b- | automatically sort RGB combinations by name |
| Ŧ | add a row to the table |
| | remove highlighted rows from the table |
| × | clear all RGB combinations from $RGB \ list$ |
| 1 | export the $RGB \ list$ to a file (i.ecsv) |
| 4 | import a previously saved $RGB\ list\ from\ file\ (i.e.\ .csv)$ |

Automatic RGB

| Tool symbol and name | Description |
|----------------------|--|
| Band combinations | add the combinations of all bands (i.e. permutation) to the <i>RGB composite</i> (c. 60) (e.g. 1-2-3, 1-2-4,, 3-2-1) |

Signature threshold

- Signature threshold (c. 61)
- Automatic thresholds (c. 61)

This tab allows for the definition of a classification threshold (only for Minimum Distance, Maximum Likelihood, and Spectral Angle Mapping algorithms) for each spectral signature. All the signatures contained in the *Training input* (c. 33) are listed. Thresholds defined in this tool are applied to classification only if *Threshold* value in *Algorithm* (c. 76) is 0.

This is useful for improving the classification results, especially when spectral signatures are similar. Thresholds of signatures are saved in the *Training input* (c. 33).

If threshold is 0 then no threshold is applied and all the image pixels are classified. Depending on the selected Algorithm (c. 76) the threshold value is evaluated differently:

- for Minimum Distance, pixels are unclassified if distance is greater than threshold value;
- for Maximum Likelihood, pixels are unclassified if probability is less than threshold value (max 100);
- for Spectral Angle Mapping, pixels are unclassified if spectral angle distance is greater than threshold value (max 90).

| | | Sem | ii-Automatic Cla | ssification Plugin | | | + <u>-</u> | • × |
|-----------------------|------------------|-----------|------------------|--------------------|------------------------------------|------------------------|------------|--------------------------|
| Filter | Signature thre | shold | _ | _ | | _ | | 🌄 Tool |
| Le Download products | MC ID | MC Name | C ID | C Name | Ainimum Distance aximum Likelihoo | Spectral Angle Mapping | | _ |
| Basic tools | | | | | | | - | ~ |
| Export signatures | | | | | | | | E E |
| Import signatures | | | | | | | | Help |
| Multiple ROI creation | | | | | | | | |
| RGB composite | | | | | | | | |
| Signature threshold | | | | | | | | |
| Preprocessing | | | | | | | | |
| Band processing | | | | | | | | |
| Postprocessing | | | | | | | | |
| Band calc | | | | | | | × | |
| Script | | | | | | | | |
| > X Settings | | | | | | | | |
| User manual | | | | | | | | |
| Help | | | | | | | | |
| About | | | | | | | | |
| About | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | Automatic thr | ocholde | | | | | | |
| | | | | | | | | |
| | Set threshold 0. | .0000 🗘 🚺 | | | Set threshold = $\sigma \star 1.0$ | | | |
| | | | | | | | | |
| | | | | | | | _ | |
| | | | | | | | | |
| | | | | | | | | |



Signature threshold

The table *Signature threshold* contains the following fields.

| MC ID | MC Name | C ID | C Name | MD Threshold | | MD Threshold | | old ML Threshold | | SAM Threshold | |
|-------|---------------------------------|------|---------------------------|---|----|--------------|--|------------------|------------|---|---------------------------|
| 0 | signature Macroclas: Name | 0 | signatur Class Name | Minimu Distant thresho value edited | ce | this be | Maximu Likeliho thresho value edited | bod | this be | Spectral Mapping threshold; value can be | Angle this e edited |

• **Ex**: reset all signatures thresholds to 0 (i.e. no threshold used);

Automatic thresholds

| Tool symbol and name | Description |
|--------------------------------|--|
| Set threshold | set the defined value as threshold for all the highlighted signatures in the table |
| Set threshold = * 1\$ | for all the highlighted signatures, set an automatic threshold calculated as the distance (or angle) between mean signature and (mean signature + ($*$ v)), where is the standard deviation and v is the defined value; currently works for Minimum Distance and Spectral Angle Mapping |

3.4.4 Preprocessing

The tab *Preprocessing* provides several tools for data manipulation which are useful before the actual classification process.

Clip raster bands

- Clip band set (c. 62)
- Clip coordinates (c. 63)

| | | Semi-Automa | tic Classification P | lugin | | | | + <u>-</u> |
|--------------------------|---|----------------|----------------------|-------|---|----|------------|------------|
| Filter | | | | | | | | |
| 🗃 Band set | Clip band set | | | | | | | |
| 👆 Download products | Select input band set | 1 | | | * | | | |
| Basic tools | 0 | atta | | | | | | |
| Preprocessing | Output name prefix | clip | | | | | | |
| 🍃 Clip raster bands | Create virtual raster output | | | | | | | |
| 🎦 Image conversion | Clip coordinates | | | _ | | _ | | |
| 💋 Masking bands | chp coordinates | | | | | | | |
| 🎥 Mosaic band sets | Use coordinates for clipping | UL X | Y | LR X | Y | | Show | + |
| 🛞 Reproject raster bands | | | | | | | | |
| 💔 Split raster bands | Use vector for clipping | | | | | | * | Q |
| 🜌 Stack raster bands | | Lise vector fi | ield for output name | | | | | |
| 🛃 Vector to raster | | | icid for output nume | | | | | |
| Band processing | Use temporary ROI for clippin | ng | | | | | | |
| Postprocessing | | | | | | | | |
| 🛗 Band calc | | | | | | | | |
| Script | | | | | | | | |
| 🕺 Settings | | | | | | | | |
| User manual | | | | | | | | |
| 😨 Help | | | | | | | | |
| 🤛 About | | | | | | | | |
| | | | | | | | | |
| | Run | _ | _ | _ | | _ | _ | _ |
| | Kun | | | | | | | |
| | | | | | | 50 | ript 📃 RUN | 10 |
| | | | | | | 30 | ipt 🙀 Kok | |

Рис. 19: Clip multiple rasters

This tab allows for cutting several image bands at once, using a rectangle defined with point coordinates or a boundary defined with a vector.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Clip band set

| Tool symbol and name | Description |
|---|--|
| Select input band set | select the input <i>Band set</i> (c. 45) to be clipped |
| \bigcirc Use value as NoData $\boxed{10}$ | if checked, set the value for NoData pixels (e.g. pixels outside the clipped area) |
| Output name prefix T | set the prefix for output file names (default is clip) |

Clip coordinates

Set the Upper Left (UL) and Lower Right (LR) point coordinates of the rectangle used for clipping; it is possible to enter the coordinates manually. Alternatively use a vector.

| Tool symbol and name | Description |
|----------------------------------|---|
| • Use coordinates for clipping | if checked, use defined coordinates for clipping bands |
| UL X 1 | set the UL X coordinate |
| UL Y 1 | set the UL Y coordinate |
| LR X 1 | set the LR X coordinate |
| LR Y 10 | set the LR Y coordinate |
| Show | show or hide the clip area drawn in the map |
| + | define a clip area by drawing a rectangle in the map; left click to set the UL point and right click to set the LR point; the area is displayed in the map |
| Use vector for clipping | if checked, use the selected vector (already loaded in QGIS) for clipping; UL and LR coordinates are ignored |
| Use vector field for output name | if checked, a vector field is selected for clipping while iterating through each vector polygon and the corresponding field value is added to the output name |
| • Use temporary ROI for clipping | if checked, use a $Temporary\ ROI$ (c. 43) for clipping; UL and LR coordinates are ignored |
| U | refresh layer list |
| | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Image conversion

- Image conversion (c. 64)
- *Metadata* (c. 65)

This tool allows for the conversion of several products to reflectance. Depending on the processing level of the source product, the conversion can be to the physical measure of Top Of Atmosphere reflectance (TOA), or the application of a simple atmospheric correction using the DOS1 method (Dark Object Subtraction 1), which is an image-based technique (for more information about conversion to TOA and DOS1 correction, see *Image conversion to reflectance* (c. 150)). In case the source product is already provided as surface reflectance level, the rescaling factors are applied to convert the DN to decimal values.

The following products can be processed:

- **Sentinel-2** images Level-1C;
- Sentinel-2 images Level-2A;
- Landsat 1, 2, 3 MSS, 4, 5, 7, 8, 9 images Collection 2 Level-2;

| . | Semi-Automatic Classification Plugin | + - | . 🗆 🗙 |
|--|--|------------|-------|
| Filter | | | 2 |
| and set | Conversion to reflectance and temperature | | Tool |
| La Download products | Directory containing bands | | 1 |
| Basic tools | | | ۲ |
| Preprocessing | Select metadata file (optional) | | Help |
| Not the second s | ✔ Use value as NoData 0 🗘 | | đ |
| Image conversion | | | |
| 💋 Masking bands | Apply DOS1 atmospheric correction | | |
| Mosaic band sets | ✓ Create Band set and use Band set tools ● Create a new Band set | | |
| 🛞 Reproject raster bands | | _ | |
| 💔 Split raster bands | Metadata | | |
| 😹 Stack raster bands | product spacecraft processing_level band_name product_path scale | | |
| Vector to raster | presente pre | - | |
| Band processing | | | |
| Postprocessing | | | |
| 🔛 Band calc | | | |
| Script | | | |
| Settings | | | |
| User manual | | | |
| Help | | | |
| P About | | | |
| | 4 | - | |
| | Run | in a state | |
| | Kun | | |
| | Script 📰 RUN | | |
| | | | |
| | | | |

Рис. 20: Image conversion

• Harmonized Landsat Sentinel-2.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Image conversion

Once the input is selected, available bands are listed in the metadata table.

| Tool symbol and | Description |
|--|--|
| name | |
| Directory containing bands | open a directory containing product bands; names of bands must end with the corresponding number; if the metadata file is included in this directory then $Metadata$ (c. 65) is automatically filled |
| Select metadata file | select the metadata file if not included in the <i>Directory containing bands</i> ; for Sentinel-2, the metadata file is a .xml file whose name contains MTD_MSIL1C. |
| Use value as NoData | if checked, pixels having NoData value are not counted during conversion and the DOS1 calculation of DNmin; it is useful when image has a black border (usually pixel value = 0) |
| Apply DOS1 atmospheric correction | if checked, the $DOS1$ Correction (c. 151) is applied to all the bands |
| Create Band set and use Band set tools | if checked, bands are added to the active $Band \ set$ after the conversion; also, the $Band \ set$ is processed according to the tools checked in the $Band \ set$ (c. 45) |
| • Add bands in a new Band set | if checked, bands are added to a new empty $Band\ set$ after the conversion |

Cobet: For the best spectral precision one should download Surface Reflectance products (e.g., for

Sentinel-2 the Level-2A Products).

Предупреждение: For Sentinel-2 L2A images downloaded as .zip file, all the .jp2 files must be moved inside the same directory and renamed according to the band number in the ending (e.g. from name_02_10m.jp2 to name_02.jp2).

Metadata

Metadata are required for the process to identify the product. If the *Metadata* file is not inside the input directory, one can define the file path in *Select metadata file*. In the *Metadata*, all the bands found in are listed.

The table *Metadata* contains the following fields.

| produ | c spacecı | processin | band | prodı | scale | offset | nodat | date | k1 | k2 | band | e_su | earth_sun_distance |
|----------------|----------------|---|------------|-----------|------------|------------|-------------|----------------------------|-----------------|---|------|--------|--------------------|
| name (e.g., | name (e.g., | processin level of the product (e.g., Level- 2) | of the | of the | of the | of the | value of | of acquisi of the | paramet(for | paramet [,] for Landsat thermal | numl | irradi | |

It is possible to remove bands from the table, to exclude these bands from the conversion.

| Tool symbol and name | Description |
|----------------------|---|
| | remove highlighted bands from the table <i>Metadata</i> |

Bands having different spatial resolution are not resampled at this stage. However, when using these bands in a classification process, all the bands are resampled on the fly to the highest spatial resolution with nearest neighbor.

| Tool symbol and name | Description |
|----------------------|--|
| | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Cobet: To reduce file size, output files are saved as data type UInt16 with scale 0.0001, which are interpreted as Float32 type by GDAL.

Masking bands

• Mask of band set (c. 67)

| | | Semi | Automatic Classification Plugin | | • <u>-</u> | • × |
|--------------------------|---------------------------|--------|---------------------------------|------------|------------|--------------------------|
| ilter | | | | | | 20 |
| 🕳 Band set | Mask of band set | | | | | Tool |
| Lownload products | Select input band set 1 | * | | | | <u> </u> |
| Basic tools | | | | | | (i) |
| Preprocessing | Select the classification | | | * | Q | Help |
| 🏂 Clip raster bands | Mask class values | [| | | | þ |
| Mage conversion | Wask class values | | | | | |
| 💋 Masking bands | Use buffer of pixel size | 1 | * * | | | |
| Mosaic band sets | Output No Data solution | 00750 | | | | |
| 🛞 Reproject raster bands | Output NoData value | -32768 | • | | | |
| 💔 Split raster bands | Create virtual raster out | but | | | | |
| 😹 Stack raster bands | _ | | | | | |
| 🛃 Vector to raster | Output name prefix | _ | nask_ | | | |
| 🔸 🗼 Band processing | | | | | | |
| Postprocessing | | | | | | |
| 🔛 Band calc | | | | | | |
| Script | | | | | | |
| 🕺 🕺 Settings | | | | | | |
| User manual | | | | | | |
| Help | | | | | | |
| P About | | | | | | |
| | Run | | | | | |
| | | | | | | |
| | | | | Script RUN | | |

Рис. 21: Masking bands

This tool allows for masking bands, based on the values of a raster mask, creating an output masked band for each band of the *Band set* (c. 45). NoData is set in all the bands of the *Band set* (c. 45) for pixels corresponding to the mask.

COBET: Information about APIs of this tool in Remotior Sensus at this link .

Mask of band set

| Tool symbol and name | Description |
|--------------------------------|---|
| Select input band set | select the input <i>Band set</i> (c. 45) to be masked |
| Select the classification | select a classification raster (already loaded in QGIS) which contains a mask class |
| Mask class values T | refresh layer list set the class values to be masked; class values must be separated by , and - can be used to define a range of values (e.g. 1, 3-5, 8 will select classes 1, 3, 4, 5, 8); if the text is red then the expression contains errors |
| Use buffer of pixel size | if checked, a buffer is created for masked area, corresponding to the defined number of pixels; this can be useful to dilate masked area |
| Output NoData value | set the value of NoData pixels corresponding to the mask |
| Output name prefix T | set the prefix for output file names (default is mask_) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Mosaic of band sets

• Mosaic of band sets (c. 68)

This tool allows for the mosaic of band sets, merging the corresponding bands of two or more band sets defined in the *Band set* (c. 45). An output band is created for every corresponding set of bands in the band sets. NoData values of one band set are replaced by the values of the other band sets.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

| | Se | mi-Automatic Classification Plugin | | ◆ _ □ × |
|--------------------------|------------------------------|------------------------------------|----------------|---------|
| Filter | Mosaic of band sets | | | Tool |
| 🥌 Band set | | | | 8 |
| 👆 Download products | Band set list | 1, 2 | | |
| 🕨 🔜 Basic tools | Use value as NoData | 0 | | ۲ |
| ✓ ► Preprocessing | Ose value as Nobata | • | | Help |
| 🍟 Clip raster bands | Create virtual raster output | | | P |
| Mage conversion | Output and fin | | | |
| 💋 Masking bands | Output prefix | mosaic_ | | |
| Mosaic band sets | Output name | band_ | | |
| 🛞 Reproject raster bands | | | | |
| M Split raster bands | | | | |
| 🧾 Stack raster bands | | | | |
| Vector to raster | | | | |
| 🕨 🏟 Band processing | | | | |
| Postprocessing | | | | |
| Band calc | | | | |
| Script | | | | |
| 🕨 🔆 Settings | | | | |
| User manual | | | | |
| 💽 Help | | | | |
| P About | | | | |
| | Run | | | |
| | | | | - |
| | | | Script 🗾 RUN 💦 | |
| | | | | |
| 1 I | | | | |

Рис. 22: Mosaic band sets

Mosaic of band sets

| Tool symbol and name | Description |
|------------------------------------|--|
| Band set list | list if band sets defined in the $Band set$ (c. 45); in case of overlapping images, the pixel values of the first band set in the list are assigned |
| | if checked, set the value of NoData pixels, ignored during the calculation |
| Create virtual raster output | if checked, output is created as virtual raster .vrt composed of as many .tif files as the number of threads defined in $System$ (c. 112); for large rasters this can speed up the process |
| Output name prefix T | set the prefix for output file names (default is mosaic) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Reproject raster bands

• Reproject raster bands (c. 70)

This tab allows for reprojecting bands in a Band set (c. 45) and perform other raster operations.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|--|--|-------------|
| Filter | Reproject and resample band set Select input band set ① Align to raster □ same extent as reference ▼ ● Use EPSG code | Tool 📀 Help |
| Image conversion Masking bands Mosaic band sets Reproject raster bands Stack raster bands Stack raster bands Vector to raster Band processing | X resolution Y resolution Output type Auto Change output NoData value 32768 Output name prefix reproj Virtual outp | • • |
| Postprocessing Band calc Script Settings User manual Help About | Compress LZW | |
| | Run Script RUN | |

Рис. 23: Reproject raster bands

Reproject raster bands

| Tool symbol and name | Description |
|---|--|
| Select input band set | select the input $Band set$ (c. 45) to be reprojected |
| Align to raster | if checked, use the same coordinate reference system and pixel size as the selected reference |
| same extent as reference | if checked, the output extent will be the same as the reference |
| Q | refresh layer list |
| Use EPSG code | if checked, use the EPSG code for defining the output coordinate reference system |
| X resolution T | set X pixel resolution |
| Y resolution T | set Y pixel resolution |
| Resample pixel | if checked, new pixel size will be the original size times this factor |
| Resampling method | select the resampling method; options are: nearest_neighbour, average, sum, maximum, minimum, mode, median, first_quartile, third_quartile |
| Output type | select the output raster type; options are: Auto (same as input), Float32, Int32, UInt32, Int16, UInt16, Byte |
| Change output NoData value | if checked, set a new value for NoData pixels |
| Output name prefix | set the prefix for output file names (default is reproj) |
| Compress T | if checked, set the compression method (e.g., LZW, DEFLATE) |
| | add this function to the $Script$ (c. 108) |
| RUN 🗯 | run this function |

Split raster bands

• Raster list (c. 71)

| | Semi-Automatic Classification Plugin | | ◆ _ □ × |
|---------|---|----------------|---------|
| Filter | | | |
| Filter | Split raster bands Select a multiband raster Output name prefix split | • | Tool |
| P About | Run | Script 🔜 RUN 눩 | |

Рис. 24: Split raster bands

Split a multiband raster to single bands.

Совет: Information about APIs of this tool in Remotior Sensus at this link .

Raster list

| Tool symbol and name | Description |
|-----------------------------|---|
| Select a multiband raster | select the input raster |
| U | refresh layer list |
| Output name prefix T | set the prefix for output file names (default is split) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Stack raster bands

• Stack band set (c. 72)

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|--------------------------|--------------------------------------|--------------------------|
| Filter | | |
| and set | Stack band set | Tool |
| 👆 Download products | Select input band set 1 💠 | |
| 🕨 🔜 Basic tools | | Help |
| ✓ ► Preprocessing | | 퓬 |
| 🏂 Clip raster bands | | q |
| Mage conversion | | |
| 💋 Masking bands | | |
| Mosaic band sets | | |
| 🛞 Reproject raster bands | | |
| 🚧 Split raster bands | | |
| Stack raster bands | | |
| Vector to raster | | |
| 🕨 🏟 Band processing | | |
| Postprocessing | | |
| 🔛 Band calc | | |
| Script | | |
| Settings | | |
| User manual | | |
| Help | | |
| 🔛 About | | |
| | Run | |
| | Script 📰 RUN | N 💽 |

Рис. 25: Stack raster bands

Stack all the bands in a Band set (c. 45) into a multiband raster.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Stack band set

| Tool symbol and name | Description |
|-----------------------|---|
| Select input band set | select the input $Band set$ (c. 45) to be stacked |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Vector to raster

This tab allows for the conversion of a vector (polygon) to raster format.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

| | Semi-Automatic Classification Plugin | ↑ _ O > |
|--|---|---------|
| Filter Filter Filter Filter For processing Kasking bands Kas | Semi-Automatic Classification Plugin Convert vector to raster Select the vector Use the value field of the vector Use constant value 1 \$elect the reference raster Pixel size Iminimum extent Select the type of conversion pixel_center Use value as NoData 0 | |
| About | Run Script | RUN 💽 |

Рис. 26: Vector to raster

Convert vector to raster

| Tool symbol and name | Description |
|---------------------------------------|--|
| Select the vector | select a vector already loaded in QGIS |
| U | refresh layer list |
| ● Use the value field of the vector 🔍 | if checked, the selected field is used as attribute for the conversion; pixels of the output raster have the same values as the vector attribute |
| ● Use constant value 🔯 | if checked, the polygons are converted to raster using the selected constant value |
| Select the reference raster | select a reference raster; pixels of the output raster have the same size and alignment as the reference raster |
| Q | refresh layer list |
| Pixel size T | set the size of pixel of output raster |
| Minimum extent | if checked, the output raster has the minimum vector extent; otherwise, output extent is the same as the <i>Select the reference raster</i> |
| Select the type of conversion | select the type of conversion among: <i>pixel_center</i>: during the conversion, vector is compared to the reference raster; output raster pixels are attributed to a polygon if pixel center is within that polygon <i>all_touched</i>: during the conversion, vector is compared to the reference raster; output raster pixels are attributed to a polygon if pixel touches that polygon <i>area_based</i>: during the conversion, output raster pixels are attributed based on area proportion of polygons |
| Area precision | for <i>area_based</i> method, the higher the value, the higher is the precision in the calculation of area proportion (and the time required for calculation) |
| Use value as NoData | if checked, set a value for NoData pixels |
| Script | add this function to the $Script$ (c. 108) |
| | run this function |

3.4.5 Band processing

The tab Band processing provides several functions that can be applied to the Band set (c. 45).

Classification

- *Input* (c. 76)
- Algorithm (c. 76)
 - Maximum Likelihood (c. 76)
 - Minimum Distance (c. 78)
 - Multi-layer Perceptron (c. 79)
 - Random Forest (c. 80)
 - Spectral Angle Mapping (c. 82)
 - Support Vector Machine (c. 83)
- *Run* (c. 84)

| | Semi-Automatic Classification Plugin | + _ □ × |
|---|--|--------------------------|
| Filter | | |
| Band set Download products Basic tools | Input Select input band set 1 Use input normalization Z-score Linear scaling | Tool |
| Preprocessing | Use training 💿 Macroclass ID 💫 Class ID | Help |
| Band processing | Algorithm | Ē |
| Classification Combination Combination Combination Evaluation Erosion Sieve Neighbor Combined PocA Combined Band calc Script Script Settings User manual Help About | Maximum Likelihood Use Single threshold 0.0000 + Signature threshold Save signature raster Calculate classification confidence raster | |
| | Minimum Distance | |
| | Multi-Layer Perceptron | |
| | Random Forest | |
| | Spectral Angle Mapping | |
| | Support Vector Machine | |
| | Run | |
| | Load classifier Save classifier 😭 Script 🌉 RUN | |
| | | |

Рис. 27: Classification

This tab allows for the classification of the *Band set* (c. 45) using the spectral signatures checked in *ROI* \mathcal{C} Signature list (c. 36). Several classification options are set in this tab which affect the classification process also during the *Classification preview* (c. 44).

This tool allows for the selection of one the following algorithms:

- Maximum Likelihood (c. 76)
- Minimum Distance (c. 78)

- Multi-layer Perceptron (c. 79)
- Random Forest (c. 80)
- Spectral Angle Mapping (c. 82)
- Support Vector Machine (c. 83)

Also, it is possible to save and load a trained classifier.

Совет: Information about APIs of this tool in Remotior Sensus at this link .

Input

| Tool symbol and name | Description |
|---|---|
| Select input band set 1 | select the input $Band set$ (c. 45) to be classified |
| ✓ Use input normalization [●] | if checked, normalize the input based on the selected method |
| • Z-score | if checked with <i>Use input normalized</i> , Z-score normalization of input is performed |
| • Linear scaling | if checked with \smile Use input normalized, Linear scaling normalization of input is performed |
| Use training $\stackrel{\textcircled{\bullet}}{\bullet}$ Macroclass ID | if checked, the classification is performed using |
| Use training \bigcirc Class ID the Macroclass ID (code <i>MC ID</i> of the signature) | if checked, the classification is performed using the Class ID (code $C ID$ of the signature) |

Algorithm

This tool allows for the selection of the classification algorithm. The algorithm tab includes the available parameters.

Maximum Likelihood

Use the Maximum Likelihood (c. 137) algorithm.

| | Semi-Automatic Classification Plugin | ↑ _ 0 | □ × |
|---------------------|--|-------|----------|
| Filter | | | |
| and set | Input | | Tool |
| Lownload products | Select input band set 1 🕒 Use input normalization) Z-score 🔿 Linear scaling | | <u> </u> |
| 🕨 🚬 Basic tools | | | ۲ |
| Preprocessing | Use training 🖲 Macroclass ID i Class ID | | Help |
| 👻 🏟 Band processing | Algorithm | | þ |
| Classification | Maximum Likelihood | | |
| Section 2010 | Maximum Likelihood | | |
| Dilation | Use 🗌 Single threshold 🛛 0.0000 🗘 🗌 Signature threshold 💽 | | |
| Erosion | | | |
| Sieve Neighbor | Save signature raster | | |
| Neighbor PCA | Calculate classification confidence raster | | |
| PCA Postprocessing | | | |
| Band calc | | | |
| Script | | | |
| > 🔆 Settings | | | |
| User manual | | | |
| Help | | | |
| 🤛 About | | | |
| | Minimum Distance | | |
| | Multi-Layer Perceptron | | |
| | Random Forest | | |
| | Spectral Angle Mapping | | |
| | Support Vector Machine | | |
| | Run | | |
| | Load classifier Save classifier 😭 Script 🌉 F | RUN 💽 | |

Рис. 28: Maximum Likelihood

| Tool symbol and name | Description |
|--|--|
| Use single threshold | if checked, it allows for the definition of a classification threshold (applied to all the spectral signatures); pixels are unclassified if probability is less than threshold value (max 100) |
| Signature threshold | if checked, thresholds $Signature threshold$ (c. 60) are evaluated |
| | open the <i>Signature threshold</i> (c. 60) for the definition of signature thresholds |
| Save signature | if checked, in addition to the classification raster, for each spectral signature a raster is saved in the same output directory, which represents the distance between pixel and signature |
| Calculate classification confidence raster | if checked, calculate classification confidence raster |

Minimum Distance

| | Semi-Automatic Classification Plugin | + _ □ × |
|--|--|----------|
| Filter | | <u>.</u> |
| 🥩 Band set | Input | Tool |
| Level Download products | Select input band set 🛽 🌲 🗌 Use input normalization 💿 Z-score 🔘 Linear scaling | |
| Basic tools Preprocessing | Use training Macroclass ID Class ID |) Help |
| Preprocessing Band processing | | |
| Classification | Algorithm | |
| Combination | Maximum Likelihood | |
| Dilation | Minimum Distance | |
| Erosion | | |
| B Sieve | Use 🗌 Single threshold 🛛 0.0000 💠 🗔 Signature threshold 💽 | |
| Neighbor | | |
| VZ PCA | Save signature raster | |
| Postprocessing | Calculate classification confidence raster | |
| 🔛 Band calc | | |
| Script | | |
| > 🔆 Settings | | |
| User manual | | |
| 🔅 Help | | |
| About | | |
| | Multi-Layer Perceptron | |
| | Random Forest | |
| | Spectral Angle Mapping | |
| | Support Vector Machine | |
| | Run | |
| | Load classifier Save classifier Script 💽 RUN | v 💽 |

Рис. 29: Minimum Distance

Use the Minimum Distance (c. 136) algorithm.

| Tool symbol and name | Description |
|--|---|
| Use single threshold | if checked, it allows for the definition of a classification threshold (applied to all the spectral signatures); pixels are unclassified if distance is greater than threshold value |
| Signature threshold | if checked, thresholds $Signature threshold$ (c. 60) are evaluated |
| | open the <i>Signature threshold</i> (c. 60) for the definition of signature thresholds |
| Save signature | if checked, in addition to the classification raster, for each spectral signature a raster is saved in the same output directory, which represents the distance between pixel and signature |
| Calculate classification confidence raster | if checked, calculate classification confidence raster |

Multi-layer Perceptron

| | Semi-Aı | itomatic Cla | assificatio | on Plugin | | | ۰. | - • × |
|--------------------------|--------------------------------------|--------------|-------------|---------------|--------------------|------------|----------|-------|
| Filter | | | | | | | | 2 |
| and set | Input | | | | | | | Tool |
| 👆 Download products | Select input band set 1 | Use input no | ormalizatio | n 🖲 Z-score 🤇 | C Linear scaling | | | |
| Basic tools | | | | 0 | ,, , | | | ۲ |
| Preprocessing | Use training 💿 Macroclass ID 🛛 🔿 | Class ID | | | | | | Help |
| 👻 🏟 Band processing | Algorithm | | | | | | | þ |
| Classification | Maximum Likelihood | | | | | | | |
| Section 2017 | | | | | | | | |
| Dilation | Minimum Distance | | | | | | | |
| Erosion | Multi-Layer Perceptron | | | | | | | |
| Sieve | | | | | | | <u> </u> | |
| Neighbor | Use framework 💿 scikit-learn 🔾 | PyTorch | | | | | | |
| VZ PCA | Hidden layer sizes | 100 | | | | | | |
| Postprocessing | Hidden layer sizes | 100 | | | | | | |
| Band calc | Max iter | 200 🌲 | Activation | relu | Alpha | 0.01000 🌲 | | |
| > X Settings | | | | | | | | |
| User manual | Training proportion | 0.90 👻 | Batch size | auto | Learning rate init | 0.0010 🌲 | | |
| Help | Cross validation | | | | | | | |
| About | Find best estimator with steps | 5 🜲 | | | | | | |
| | Calculate classification confident | ce raster | | | | | | |
| | Random Forest | | | | | | | |
| | Spectral Angle Mapping | | | | | | | |
| | Support Vector Machine | | | | | | | |
| | Run | _ | _ | _ | _ | _ | | |
| | | | | | | | | |
| | Load classifier | | | 1 | Save classifier | 🔶 Script 💼 | RUN 款 | |
| | | | | | | | F | |
| | | | | | | | | |

Рис. 30: Multi-layer Perceptron

Use the Multi-Layer Perceptron (c. 142) algorithm.

| Tool symbol and name | Description |
|--|--|
| Use framework ${ullet}$ scikit-learn | if checked, use scikit-learn framework (read this) |
| Use framework • PyTorch | if checked, use PyTorch framework (read about this) |
| Hidden layer sizes | list of values separated by comma, where each value defines the number of neurons in a hidden layer (e.g.: 200, 100 for two hidden layers of 200 and 100 neurons respectively) |
| Max iter | set the maximum number of iterations |
| Activation T | set the activation function (default: relu) |
| Alpha 10 Training proportion | set the weight decay (also L2 regularization term) for Adam optimizer set the proportion of data to be used as training and the remaining part as test |
| Batch size T Learning rate init | set the number of samples per batch for optimizer; if auto, the batch is the minimum value between 200 and the number of samples set initial learning rate |
| | if checked, perform cross validation |
| Find best estimator with steps | if checked, find the best estimator iteratively with a number of steps |
| Calculate classification confidence raster | if checked, calculate classification confidence raster |

Random Forest

Use the Random Forest (c. 142) algorithm.

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|---------------------|--|----------|
| Filter | | 59 |
| and set | Input | Tool |
| Lownload products | Select input band set 1 🕀 🕒 Use input normalization 💿 Z-score 🔘 Linear scaling | <u> </u> |
| 🕨 🚬 Basic tools | | ۲ |
| Preprocessing | Use training 🖲 Macroclass ID i Class ID | Hep |
| 👻 🏟 Band processing | Algorithm | <u>a</u> |
| Classification | Maximum Likelihood | |
| Combination | | |
| L Dilation | Minimum Distance | |
| Erosion | Multi-Layer Perceptron | |
| Sieve | 🕅 Random Forest | |
| Neighbor PCA | Kandom Forest | |
| PCA Postprocessing | Number of trees 10 🗘 Minimum number to split 2 📮 Max features | |
| Band calc | | |
| Script | One-Vs-Rest | |
| > X Settings | ✓ Cross validation | |
| User manual | | |
| Help | Balanced class weight | |
| About | Find best estimator with steps 5 | |
| _ | | |
| | Calculate classification confidence raster | |
| | | |
| | | |
| | Spectral Angle Mapping | |
| | | |
| | Support Vector Machine | |
| | Run | |
| | | |
| | Load classifier T Script 🜉 R | UN 💦 |
| | | |
| 1 | | |

Рис. 31: Random Forest

| Tool symbol and name | Description |
|---|---|
| Number of trees 10 Minimum number to split 10 | set the number of trees set the minimum number of samples required to split an internal node |
| Max features | for node splitting, if empty all features are considered; if sqrt the square root of all the features, if integer number the number of features; if float number a fraction of all the features |
| One-Vs-Rest | if checked, perform One-Vs-Rest classification (read more) |
| Cross validation | if checked, perform cross validation |
| ✓ Balanced class weight | if checked, balanced weight is computed inversely proportional to class frequency |
| Find best estimator with steps | if checked, find the best estimator iteratively with a number of steps |
| Calculate classification confidence raster | if checked, calculate classification confidence raster |

Spectral Angle Mapping

| | Semi-Automatic Classification Plugin | + _ □ × |
|---------------------|--|--------------------------|
| Filter | | |
| and set | Input | Tool |
| Lownload products | Select input band set 1 🔮 🗌 Use input normalization) 💿 Z-score 🔘 Linear scaling | <u> </u> |
| Basic tools | | |
| Preprocessing | Use training Macroclass ID Class ID | Help |
| 🔻 🏟 Band processing | Algorithm | Ť |
| Classification | | |
| 🔀 Combination | Maximum Likelihood | |
| Lilation | Minimum Distance | |
| Erosion | Multi-Layer Perceptron | |
| Sieve | | |
| Neighbor | Random Forest | |
| VZ PCA | V Spectral Angle Mapping | |
| Postprocessing | | <u> </u> |
| Band calc | Use Single threshold 0.0000 🗘 Signature threshold | |
| Script | | |
| > 🔆 Settings | Save signature raster | |
| User manual | Calculate classification confidence raster | |
| Help | | |
| 萨 About | | |
| | Support Vector Machine | |
| | Run | |
| | | |
| | Load classifier T Script 📰 RUN | |
| | | |
| | | |

Рис. 32: Spectral Angle Mapping

Use the Spectral Angle Mapping (c. 138) algorithm.

| Tool symbol and name | Description |
|--|--|
| Use single threshold | if checked, it allows for the definition of a classification threshold (applied to all the spectral signatures); pixels are unclassified if spectral angle distance is greater than threshold value (max 90) |
| Signature threshold | if checked, thresholds <i>Signature threshold</i> (c. 60) are evaluated |
| | open the Signature threshold (c. 60) for the definition of signature thresholds |
| Save signature raster | if checked, in addition to the classification raster, for each spectral signature a raster is saved in the same output directory, which represents the distance between pixel and signature |
| Calculate classification confidence raster | if checked, calculate classification confidence raster |

Support Vector Machine

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|---------------------|--|----------|
| Filter | | |
| and set | Input | Tool |
| Lownload products | Select input band set 1 🔮 🗌 Use input normalization 💿 Z-score 🔘 Linear scaling | |
| Basic tools | | ۲ |
| Preprocessing | Use training 🖲 Macroclass ID ု Class ID | Help |
| 👻 🏟 Band processing | Algorithm | <u>5</u> |
| Classification | Maximum Likelihood | |
| Second Combination | | |
| L Dilation | Minimum Distance | |
| Erosion | Multi-Layer Perceptron | |
| Sieve | Random Forest | |
| Neighbor | | |
| PCA Postprocessing | Spectral Angle Mapping | |
| Band calc | Support Vector Machine | |
| Script | | _ |
| > 🔆 Settings | Regularization parameter C 1.0000 🗘 Kernel rbf Gamma scale | |
| User manual | ✓ Cross validation | |
| Help | | |
| 🤛 About | Balanced class weight | |
| | Find best estimator with steps 5 | |
| | | |
| | Calculate classification confidence raster | |
| | | |
| | | |
| | | |
| | | |
| | Run | |
| | kund darah 🖌 🦳 🚛 🗛 👘 👘 | |
| | Load classifier Load classifier T | |
| | | |
| I | | |

Рис. 33: Support Vector Machine

Use the Support Vector Machine (c. 142) algorithm.

| Tool symbol and name | Description | | | |
|--------------------------------|--|--|--|--|
| Regularization parameter C | set the regularization parameter C | | | |
| Kernel T | set the kernel (default: rbf) | | | |
| Gamma T | set the kernel coefficient gamma (default: scale) | | | |
| Cross validation | if checked, perform cross validation | | | |
| Salanced class weight | if checked, balanced weight is computed inversely proportional to class frequency | | | |
| Find best estimator with steps | if checked, find the best estimator iteratively with a number of steps | | | |
| Calculate classification | if checked, calculate classification confidence raster | | | |
| confidence raster | | | | |

Run

It is possible to run the classification, or save and load a trained classifier.

Classification raster is a file .tif (a QGIS style file .qml is saved along with the classification); also other outputs can be optionally calculated. Outputs are loaded in QGIS after the calculation.

| Tool symbol and name | Description |
|----------------------|--|
| Load classifier | open an already save classifier file (.rsmo) |
| Save classifier 个 | save the classifier to file (.rsmo), in order to be loaded later |
| RUN | run this function |

Combination

• Combination of band values (c. 85)

| | Semi-Automatic Classification Plugin | + _ □ × |
|---------------------|--------------------------------------|---------|
| Filter | | 👼 Tool |
| 🥩 Band set | Input | Too |
| 👆 Download products | | |
| 🕨 📉 Basic tools | Combination of band values | ۲ |
| Preprocessing | Select input band set | Help |
| 👻 🏟 Band processing | (of classifications) | q |
| Classification | Use value as NoData 0 | |
| Section Combination | | |
| Dilation | | |
| Erosion | | |
| Sieve | | |
| Neighbor | | |
| VZ PCA | | |
| 🕨 🚭 Postprocessing | | |
| 🔛 Band calc | | |
| Script | | |
| 🕨 🔆 Settings | | |
| User manual | Due | |
| Help | Run | |
| 🤛 About | Script 🔜 RUN 💽 | |
| | Output | |

Рис. 34: Combination

This tab allows for the combination of bands loaded in a *Band set* (c. 45). This tool is intended for combining classifications in order to get a raster where each value corresponds to a combination of class values. Raster values must be integer type. A combination raster is produced as output and the area of each combination is reported in a .csv file.

This tool supports virtual raster output; if the output file name ends with .vrt then the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in *System* (c. 112); for large rasters this can speed up the process.

Совет: Information about APIs of this tool in Remotior Sensus at this link .

Combination of band values

| Tool symbol and name | Description |
|--|--|
| Select input band set (of classifications) | select the input <i>Band set</i> (c. 45) |
| ✓ Use value as NoData 1 | if checked, set the value of NoData pixels, ignored during the calculation |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

The list of combinations and the area thereof will be displayed in the tab Output.

Dilation

| • Dilation (c. | 86) | |
|--|--|--------------------------|
| Filter | Semi-Automatic Classification Plugin | + _ □ × |
| Band set | Band dilation | Tool |
| Download products Basic tools | Select input band set (of classifications) | |
| Preprocessing | Class values | Help |
| Band processing Classification | Size in pixels 1 ≑ 🗌 Circular | 0 |
| | Output name dilation_ | |
| L Dilation | | |
| Erosion | | |
| Sieve | | |
| Neighbor | | |
| VZ PCA | | |
| 🕨 🚭 Postprocessing | | |
| 🔛 Band calc | | |
| Script | | |
| Settings | | |
| User manual | | |
| Help | | |
| About | Run Script RUN | |

Рис. 35: Dilation

This tab allows for dilating the border of a class patch, defining the class values to be dilated and the number of pixels from the border. It is useful for classification refinement.


 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Dilation

| Tool symbol and name | Description |
|--|--|
| Select input band set (of classifications) | select the input <i>Band set</i> (c. 45) |
| Class values | set the class values to be dilated; class values must be separated by , and – can be used to define a range of values (e.g. 1, 3–5, 8 will select classes 1, 3, 4, 5, 8); if the text is red then the expression contains errors |
| Size in pixels | number of pixels to be dilated from the border |
| Circular | if checked, the dilation will be circular, similar to a buffer |
| Output name | set the name prefix for output files |
| Virtual output | if checked, the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in $System$ (c. 112) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Erosion

| • Erosion (c. 8 | 87) | |
|---|--|-------------|
| Filter | Semi-Automatic Classification Plugin | + _ = × |
| ✓ Band set ✓ Download products ✓ Basic tools ✓ Preprocessing ✓ And processing | Band erosion Select input band set (of classifications) 1 Class values | Tool 🛞 Help |
| Classification Combination Dilation Erosion Sieve | Size in pixels 1 Circular Output name erosion_ Virtual output | |
| Neighbor PCA Postprocessing Band calc Script | | |
| Settings Settings Generation Settings Set | Run | |
| | Kun Script 💽 RUN 💽 | |



This tab allows for removing the border of a class patch (erosion), defining the class values to be eroded and the number of pixels from the border. It is useful for classification refinement.

COBET: Information about APIs of this tool in Remotior Sensus at this link .

Erosion

| Tool symbol and name | Description |
|--|---|
| Select input band set (of classifications) | select the input <i>Band set</i> (c. 45) |
| Class values | set the class values to be eroded; class values must be separated by , and – can be used to define a range of values (e.g. 1, $3-5$, 8 will select classes 1, 3, 4, 5, 8); if the text is red then the expression contains errors |
| Size in pixels | number of pixels to be eroded from the border |
| Circular | if checked, the erosion will be circular, similar to a buffer |
| Output name | set the name prefix for output files |
| Virtual | if checked, the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in $System$ (c. 112) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Sieve

• *Sieve* (c. 88)

This tab allows for the replacement of isolated pixel values with the value of the largest neighbour patch. It is useful for removing small patches from a classification.

It is possible to chose 4 pixel connection (in a 3x3 window, diagonal pixels are not considered connected) or 8 pixel connection (in a 3x3 window, diagonal pixels are considered connected).

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|---------------------|--|---------|
| Filter | | |
| 🥩 Band set | Band sieve | Tool |
| 👆 Download products | Select input band set (of classifications) | |
| 🕨 🔜 Basic tools | | ۲ |
| Preprocessing | Size threshold 2 🗘 Pixel connection 4 | * Help |
| 👻 🏟 Band processing | Output name sieve_ | |
| Classification | | , deput |
| 🔀 Combination | | |
| Lilation | | |
| Erosion | | |
| 🚼 Sieve | | |
| Neighbor | | |
| VZ PCA | | |
| 🕨 🚭 Postprocessing | | |
| 🛗 Band calc | | |
| Script | | |
| 🕨 🔆 Settings | | |
| User manual | | |
| 😟 Help | | |
| 🤛 About | | |
| | Run | |
| | | |
| | Script RUN | |
| | | |
| | | |

Рис. 37: Sieve

Sieve

| Tool symbol and name | Description |
|---------------------------|--|
| Select input band set (of | select the input <i>Band set</i> (c. 45) |
| classifications) 1 | |
| Size threshold 1 | size of threshold in number of pixels |
| Pixel connection | select between 4 pixel connection or 8 pixel connection |
| Output name | set the name prefix for output files |
| Virtual output | if checked, the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in $System$ (c. 112) |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Neighbor

- Neighbor (c. 90)
- *Statistic* (c. 90)
- *Run* (c. 90)

This tool allows for the calculation of several neighbor pixels statistics for every band of a band set defined in the Band set (c. 45).

The statistics are calculated for every pixel of the input raster considering the values of the neighbor

| | Semi-Auto | omatic Classification Plugin | + _ = × |
|---------------------|-----------------------------|------------------------------|----------------|
| Filter | | | |
| 🥩 Band set | Band neighbor | | Tool |
| 👆 Download products | Select input band set | 1 | |
| 🕨 🔼 Basic tools | | | 0 |
| Preprocessing | Neighbor distance in pixels | 1 🗘 Circular | нер |
| 🔻 🏟 Band processing | Matrix file (optional) | | |
| Classification | Matrix file (optional) | | |
| Second Combination | Output name | neighbor_ | Virtual output |
| L Dilation | | | |
| Erosion | A | | |
| 🔝 Sieve | Statistic | | |
| Neighbor | Select a statistic Count | • | |
| VZ PCA | | | - |
| 🕨 🚭 Postprocessing | | | |
| 🛗 Band calc | | | |
| Script | | | |
| 🕨 🔆 Settings | | | |
| User manual | | | |
| Help | | | |
| P About | | | |
| | Run | | |
| | | | |
| | | | Script RUN |
| | | | |
| | | | |

Рис. 38: Neighbor

pixels. Neighbor pixels are defined through a distance or through a custom matrix.

For example, the following matrix represents the neighbor pixels within a distance of 1 pixel from a central pixel, resulting in a 3x3 matrix.

| Neighbor | Neighbor | Neighbor |
|----------|----------|----------|
| Neighbor | Center | Neighbor |
| Neighbor | Neighbor | Neighbor |

Several statistics are available. The statistic Sum will result in a raster convolution. For instance, this can be useful to apply an image filter to all the bands of a band set for photointerpretation.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Neighbor

| Tool symbol and name | Description |
|--------------------------------|--|
| Select input band set | select the input <i>Band set</i> (c. 45) |
| Neighbor distance in pixels | create a window defining the size based on the distance from the center (in number of pixels) |
| 🥑 Circular 📍 | if checked, the window will be circular |
| Matrix file (optional) | select a $\tt.csv$ file containing the structure of the window |
| Output name | set the name prefix for output files |
| Virtual | if checked, the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in $System$ (c. 112) |

Statistic

| Tool symbol and name | Description |
|--------------------------------|---|
| Select a statistic T | select a statistic among: Count, Max, Mean, Median, Min, Percentile, StandardDeviation, Sum. For Percentile statistic it is possible to enter the percentile value. |

Run

- Script
- add this function to the Script (c. 108)

• – RUN

– run this function

PCA

• *PCA* (c. 91)

This tab allows for the PCA (Principal Component Analysis (c. 146)) of bands loaded in the Band set.

A report .txt is saved along with the PCA bands, containing the covariance matrix, correlation matrix, eigen vectors, and eigen values.

| | Semi-Automatic Classification Plugin | + <u>-</u> | • × |
|---------------------|---|------------|--------------------------|
| Filter | | | |
| 🥩 Band set | Input | | tool |
| 👆 Download products | | | |
| 🕨 📉 Basic tools | Principal Components Analysis of band set | | ۲ |
| Preprocessing | Select input band set 1 | | Help |
| 🔻 🏟 Band processing | | | d |
| Classification | Number of components 2 | | |
| Combination | Use value as NoData 0 | | |
| L Dilation | | | |
| Erosion | | | |
| Sieve | | | |
| Neighbor | | | |
| PCA | | | |
| 🕨 🚭 Postprocessing | | | |
| Band calc | | | |
| Script | | | |
| 🕨 🔆 Settings | | | |
| User manual | | | |
| | Kun | | |
| 🤛 About | Script 🥃 | RUN 💽 | |
| | | | |
| | | | |
| | Output | <u> </u> | |
| | | | |
| Help | Run Script | | |

Рис. 39: РСА

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

PCA

| Tool symbol and name | Description |
|--|--|
| Select input band set $\square \heartsuit$ | select the input <i>Band set</i> (c. 45) |
| Number of components • | set the number of components to be calculated |
| Use value as NoData 1 | if checked, set the value of NoData pixels, ignored during the calculation |
| | add this function to the $Script$ (c. 108) |
| RUN | run this function |

The Output tab will display the Principal Components Analysis details (Covariance matrix, Correlation matrix, Eigenvectors, and Eigenvalues).

3.4.6 Postprocessing

The tab **Postprocessing** provides several functions that can be applied to the classification output.

Accuracy

• Accuracy (c. 93)

| | Semi-Automat | tic Classification Plugin | | * _ | □ × |
|-------------------------|---------------------------------------|---------------------------|--------------|-----|--------------------------|
| Filter | | | | | |
| and set | Input | | | | tool |
| La Download products | | | | | _ |
| Basic tools | Accuracy assessment | | | | |
| Preprocessing | Select the classification to assess | | | U | Help |
| > 🔖 Band processing | | | | | đ |
| - Postprocessing | Select the reference vector or raster | | - | U | |
| Accuracy | | Vector field | | | |
| Classification report | | vector field | | | |
| 🛃 Classification to vec | Use value as NoData 0 | \$ | | | |
| Cross classification | | | | | |
| 🔂 Reclassification | | | | | |
| Band calc | | | | | |
| Script | | | | | |
| 🕨 🔆 Settings | | | | | |
| User manual | | | | | |
| Help | | | | | |
| 🤛 About | | | | _ | |
| | Run | | | | |
| | | | Script 📃 RUN | | |
| | | | script 🙀 | | |
| | | | | - | |
| | Output | | | | |
| | | | | | |

Рис. 40: Accuracy

This tab allows for the validation of a classification (read Accuracy Assessment (c. 145)).

Classification is compared to a reference raster or reference vector (which is automatically converted to raster). If a vector is selected as reference, it is possible to choose a field describing class values.

Several statistics are calculated such as overall accuracy, user's accuracy, producer's accuracy, and Kappa hat. In particular, these statistics are calculated according to the area based error matrix where each element represents the estimated area proportion of each class. This allows for estimating the unbiased user's accuracy and producer's accuracy, the unbiased area of classes according to reference data, and the standard error of area estimates.

The output is an **error raster** that is a .tif file showing the errors in the map, where pixel values represent the categories of comparison (i.e. combinations identified by the **ErrorMatrixCode** in the error matrix) between the classification and reference. Also, a text file containing the error matrix (i.e. a .csv file separated by tab) is created with the same name defined for the .tif file.

This tool supports virtual raster output; if the output file name ends with .vrt then the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in *System* (c. 112); for large rasters this can speed up the process.

COBET: Information about APIs of this tool in Remotior Sensus at this link .

Accuracy

| Tool symbol and name | Description |
|---------------------------------------|---|
| Select the classification to assess | select a classification raster (already loaded in QGIS) |
| Q | refresh layer list |
| Select the reference vector or raster | select a raster or a vector (already loaded in QGIS), used as reference layer (ground truth) for the accuracy assessment |
| Q | refresh layer list |
| Vector field 🔍 📍 | if a vector is selected as reference, select a vector field containing numeric class values |
| Use value as NoData | if checked, set the value of NoData pixels, ignored during the calculation |
| | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Classification report

• Classification report (c. 94)

| | Semi-Automatic Classification Plugin | • - • × |
|------------------------------------|--------------------------------------|--------------------------|
| Filter | Tract | 5 Tool |
| 🥩 Band set | Input | - 0 |
| 👆 Download products | Classification report | |
| 🕨 🚾 Basic tools | | ۲ |
| Preprocessing | Select the classification 👻 🗸 | Help |
| Band processing | Use value as NoData 0 | q |
| Postprocessing | Use value as NoData | |
| Accuracy | | |
| Classification report | | |
| Classification to vect | | |
| Cross classification | | |
| Reclassification | | |
| 🔡 Band calc | | |
| Script | | |
| > 🕺 Settings | | |
| User manual | | |
| Help | | |
| 🔛 About | | |
| | Run | |
| | Script 📰 RUN 💽 | |
| | Output | - |

Рис. 41: Classification report

This tab allows for the calculation of class statistics such as number of pixels, percentage and area (area unit is defined from the image itself).

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Classification report

| Tool symbol and name | Description |
|-------------------------------------|--|
| Select the classification \square | select a classification raster (already loaded in QGIS) |
| U | refresh layer list |
| Use value as NoData | if checked, set the value of $\tt NoData$ pixels, ignored during the calculation |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

The tab Output will display the report.

Classification to vector

- Classification to vector (c. 95)
- Symbology (c. 95)
- *Run* (c. 95)

| | Semi-Automatic Classification Plugin | ↑ <u> </u> |
|---|---|------------|
| Filter Band set Download products Basic tools Preprocessing Band processing Postprocessing Classification report Classification to vec Cross classification Band calc Script Settings User manual Help About | Semi-Automatic Classification Plugin Classification Select the classification Symbology Use code from Signature list C_ID Dissolve output | |
| | Script | RUN 💽 |

Рис. 42: Classification to vector

This tab allows for the conversion of a classification raster to vector GeoPackage (.gpkg) . Parallel processes are used for the conversion, resulting in a vector output which is split in as many portions as


the process numbers. The argument dissolve allows for merging these portions, but it requires additional processing time depending on vector size.

Совет: Information about APIs of this tool in Remotior Sensus at this link .

Classification to vector


| Tool symbol and name | Description |
|-------------------------------------|---|
| Select the classification \square | select a classification raster (already loaded in QGIS) |
| Q | refresh layer list |

Symbology



Run

- – Script
 - add this function to the *Script* (c. 108)



run this function

Cross classification

• Cross classification (c. 96)

This tab allows for the calculation of a cross classification raster and matrix. Classification is compared to a reference raster or reference vector (which is automatically converted to raster). This is useful for calculating the area for every combination between reference classes and classification values. If a vector is selected as reference, it is possible to choose a field describing class values.

The output is a **cross raster** that is a .tif file where pixel values represent the categories of comparison (i.e. combinations identified by the **CrossMatrixCode**) between the classification and reference. Also, a text file containing the cross matrix (i.e. a .csv file) is created with the same name defined for the .tif file.

| | Semi-Automatic Classification Plugin | • - | • × |
|---|---------------------------------------|----------|--------------------------|
| Filter | Input | | s Tool |
| 🥩 Band set | mpor | <u> </u> | 0 |
| 👆 Download products | Cross classification | | |
| 🕨 📐 Basic tools | | | Help |
| Preprocessing | Select the classification | U | Hel |
| Band processing | Use value as NoData 0 | | Ŭ |
| Postprocessing | | | |
| Accuracy | Select the reference vector or raster | U | |
| Classification report | | | |
| Classification to vect | Vector field | · | |
| Cross classification | Calculate linear regression | | |
| Reclassification | | | |
| | | | |
| Script | | | |
| Settings User manual | | | |
| Help | | | |
| V Help | | | |
| About | Run | | |
| | Kun | | |
| | Script RUN | | |
| | | | |
| | | - | |
| | Output | | |
| | | | |

Рис. 43: Cross classification

This tool supports virtual raster output; if the output file name ends with .vrt then the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in *System* (c. 112); for large rasters this can speed up the process.

Совет: Information about APIs of this tool in Remotior Sensus at this link .

Cross classification

| Tool symbol and name | Description |
|--|---|
| Select the classification \square | select a classification raster (already loaded in QGIS) |
| U | refresh layer list |
| Use value as NoData | if checked, set the value of $\tt NoData$ pixels, ignored during the calculation |
| Select the reference vector or raster \blacksquare | select a raster or a vector (already loaded in QGIS), used as reference layer |
| U | refresh layer list |
| Vector field 🔍 📍 | if a vector is selected as reference, select a vector field containing numeric class values |
| Calculate linear regression | if checked, calculate linear regression between the two input layers |
| Script | add this function to the $Script$ (c. 108) |
| RUN | run this function |

Reclassification

- Cross classification (c. 97)
- Values (c. 98)
- Symbology (c. 98)
- *Run* (c. 99)

| | Semi-Automatic Classification Plugin | + _ = × |
|--|--|---------|
| Filter Filter Solution Filter Solution Filter Solution Filter Solution Filter Solution Filter Solution Solution Filter Solution Filter Solution Solu | Reclassification Select the classification Values calculate C ID to MC ID values Calculate C ID to MC ID values Incremental new values Old value | е |
| Help About | Symbology Use code from Signature list MC_ID Run Script RUN | |

Рис. 44: Reclassification

This tab allows for the reclassification (i.e. assigning a new class code to raster pixels). In particular, it eases the conversion from C ID to MC ID values.

This tool supports virtual raster output; if the output file name ends with .vrt then the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in *System* (c. 112); for large rasters this can speed up the process.

 ${\bf Cobet:}\,$ Information about APIs of this tool in Remotior Sensus at this link .

Cross classification

| Tool symbol and name | Description |
|-------------------------------------|---|
| Select the classification \square | select a classification raster (already loaded in QGIS) |
| U | refresh layer list |

Values

| Teel symphol | Description |
|--------------------|---|
| Tool symbol | Description |
| and name | |
| | if checked, the reclassification table is filled according to the ROI & Signature list |
| calculate | (c. 36) when <i>Calculate unique values</i> is clicked |
| $C \ ID \ to \ MC$ | (c. 36) when <i>Calculate unique values</i> is clicked |
| ID values | |
| Calculate | calculate unique values in the classification and fill the reclassification table |
| unique values | |
| Incremental | calculate a new incremental value (e.g. 1, 2, 3,) for every old value and fill the |
| new values | reclassification table |
| ÷ | add a row to the table |
| | remove highlighted rows from the table |
| U | import rules from a text file .csv separated by comma having the following structure Old_value,New_value (where Old_value cam be also an expression and New_value is an integer value) for instance:: raster < 1,1 (raster > 1) & (raster < 3),2 raster < 3,3 |
| | export the reclassification table to a text file (.csv) that can be imported later |

The reclassification table is structured with the following fields.

| Old value | | | | | New val | ue | | | | |
|----------------------------------|-------------|------------|----|----|------------------|-------|-----|-----|---------------|-----|
| value or expression reclassified | defining of | old values | to | be | integer value | value | for | the | corresponding | Old |


Old value can be a value or an expressions defined using the variable name raster (custom names can be defined in *Variable name for expressions* (c. 111)), following Python operators (e.g.:

- raster > 3 select all pixels having value > 3;
- (raster > 5) | (raster < 2) select all pixels having value $>5 \mbox{ or } < 2 \ ;$
- (raster >= 2) & (raster <= 5) select all pixel values between 2 and 5.

Symbology

| Tool symbol and name | Description |
|--------------------------------|---|
| ✓ Use code from Signature list | if checked, color and class information are defined from <i>ROI & Signature list</i> (c. 36): MC ID: use the ID of macroclasses C ID: use the ID of classes |


Run



3.4.7 Band calc

- Band list (c. 100)
- Expression (c. 100)
- Output raster (c. 101)
- Input variables (c. 102)
- Output variables (c. 103)
- *Functions* (c. 105)
 - Conditional (c. 105)
 - *Logical* (c. 105)
 - *Statistics* (c. 105)
 - Operations (c. 106)
 - Indices (c. 106)
 - Variables (c. 106)

| | Semi-Automatic Classification Plugin | | ÷ _ | □ × |
|---------------------|--|-------------|-----|---------------|
| Filter | Band list Filter | | 1 | too! |
| 👆 Download products | Variable | | | |
| 🕨 🔜 Basic tools | | | | ۲ |
| Preprocessing | | | U | Help |
| 🕨 萨 Band processing | | | | σ |
| Postprocessing | | | | |
| 🔛 Band calc | | | | |
| Script | Expression | | | |
| > 🔆 Settings | | Functions | • | |
| User manual | | + | | |
| About | | | | |
| About | | • | | |
| | | 1 | | |
| | | * | | |
| | | * | | |
| | | | | |
| | | != | | |
| | | | | |
| | □ Input NoData as value 0 ↓ Calculation Float32 ▼ | | | |
| | Output raster | | | |
| | Output data type Float32 V Output NoData value -32768 NoData False V Set 1 | Set 0 ↓ | | |
| | Extent: ULX ULY LRX LRY Align | v Pixel RUN | | |



The Band calc allows for the raster calculation for bands (i.e. calculation of pixel values) using

NumPy functions. Band calc can also work with multiple expression lines to perform multiple calculation at a time; several iteration functions are available for *Band sets* allowing for performing multi-temporal calculations.

This tool supports virtual raster output; if the output file name ends with .vrt then the output is created as virtual raster composed of as many .tif files as the number of CPU threads defined in *System* (c. 112); for large rasters this can speed up the process.

Raster bands must be already loaded in QGIS. Input rasters can also be in different projection, but the output will have the projection of the reference raster.

COBET: Information about APIs of this tool in Remotior Sensus at this link .

Band list

| Tool symbol and name | Description |
|-------------------------|--|
| Band list | table containing a list of single band rasters (already loaded in QGIS) and <i>Input</i> variables (c. 102) defined from <i>Band set</i> |
| Filter T | filter the variable list |
| U | refresh band list |

Expression

Enter a mathematical expression for raster bands. In particular, NumPy functions can be used with the prefix *np*. (e.g. np.log10(raster1)). For a list of NumPy functions see the NumPy page.

The expression can work with *Variable* between ". Double click on any item in the *Band list* (c. 100) for adding the name thereof to the expression.

If text color in the *Expression* is green, then the syntax is correct; if text color is red, then the syntax is incorrect and it is not possible to execute the calculation.

It is possible to enter multiple expressions separated by newlines such as the following example:

```
"raster1" + "raster2"
"raster3" - "raster4"
```

The above example calculates two new rasters in the output directory with the suffix _1 (e.g. calc_raster_1) for the first expression and _2 (e.g. calc_raster_2) for the second expression. Also, it is possible to define the output name using the symbol @ followed by the name, such as the following example:

```
"raster1" + "raster2" @calc_1
"raster3" - "raster4" @calc_2
```

Input variables (c. 102) and Output variables (c. 103) can be used in the expression.

| Tool symbol and name | Description |
|--------------------------|--|
| Input NoData as value | if checked, input NoData pixels are replaced by NoData value and accounted in calculation |
| Use value as NoData | if checked, selected value is used as NoData during calculation |
| Calculation data type | select the data type used during calculation as Float32 (default), Int32, Int16, UInt32, UInt16, Byte; for instance, if Int32 is selected, input float values will be evaluated as integer |
| Functions | list of $Functions$ (c. 105) names (double click to copy one in the expression) such as mathematical, conditional, logical, statistics, indices, and custom |
| | open a text file $(.txt)$ containing custom expressions to be listed in <i>Functions</i> |

A text file can be loaded for adding expressions to the *Functions*. The text must contain an expression for each line; each line must be in the form expression_name; expression (separated by ;) where the expression_name is the expression name that is displayed in the *Functions*. Opening an empty text file will remove custom expressions from the *Functions*. Following an example of text content:

```
NDVI; ( "#NIR#" - "#RED#" ) / ( "#NIR#" + "#RED#" ) @NDVI
EVI; 2.5 * ( "#NIR#" - "#RED#" ) / ( "#NIR#" + 6 * "#RED#" - 7.5 * "#BLUE#" + 1) @EVI
SR; ( "#NIR#" / "#RED#" ) @SR
```

Output raster

The output raster is a .tif file, with the same spatial resolution and projection of input rasters; if input rasters have different spatial resolutions, then the highest resolution (i.e. minimum pixel size) is used for output raster.

COBET: If multiple lines are entered in Expression or output name are defined in line, a directory selection instead of a file selection is prompted for output.

| Tool symbol and name | Description |
|----------------------------|--|
| Output data type | select the output data type as Float32 (default), Int32, Int16, UInt32, UInt16, Byte; it can be different from <i>Calculation data type</i> |
| Output NoData value 1 | set the value of NoData pixels in output raster |
| NoData mask | manage NoData at pixel level; if True, then output is NoData if any input is NoData; if False, then output is NoData if all the inputs are NoData; if None, then NoData is not applied to output |
| Set scale 🔯 📍 | if checked, set a scale in output raster (and output values are divided by scale) |
| Set offset 10 | if checked, set an offset in output raster (and offset is subtracted to output values) |
| Extent UL X UL Y LR X LR Y | set the extent of the output raster among: "Union": the extent union of input rasters "Map extent": the extent of the map currently displayed "Intersection": the extent intersection of input raster extents (i.e. minimum extent) "Custom": coordinates defined in UL X UL Y LR X LR Y Layer name: the extent of the selected layer |
| Align | align the output raster to a specific <i>Layer name</i> or <i>"Default"</i> for automatic alignment to input rasters |
| Pixel size | set pixel size |
| RUN | run this function; it is disabled if the expression syntax is not correct |

Input variables

The following variables related to the *Band set* (c. 45) are available (please note that the character " is always required):

• *bandset#b BAND_NUMBER*: bands in the active *Band set* can be referenced directly; the following example refers to band 1 of the active *Band set*:

"bandset#b1"

• bandset BANDSET_NUMBER b BAND_NUMBER: bands in the Band set can be referenced directly; the following example refers to band 1 of the Band set 1:

"bandset1b1"

• bandset{ BANDSET_NUMBER_LIST }b BAND_NUMBER: list of all the bands X of all the Band sets matching a list between curly brackets (e.g. {1,2,3}) or range of Band sets separated by colon (e.g. {1:3}) or a list of ranges of Band sets (e.g. {1:3, 5:8}), which is equivalent to

[bandset1bX, bandset2bX, ..., bandsetNbX]; this variable can be used in expressions that accept band lists such as the sum:

sum("bandset{1,3}b1")

• bandset#b*: list of all the bands of active Band set, which is equivalent to [bandset#b1, bandset#b2, ..., bandset#bX]; to be used in expressions that accept band lists such as the maximum value:

max("bandset#b*")

• bandset BANDSET_NUMBER b*: list of all the bands of Band set N, which is equivalent to [bandsetNb1, bandsetNb2, ..., bandsetNbX]; to be used in expressions that accept band lists such as the minimum value:

min("bandset1b*")

• bandset*b BAND_NUMBER: list of all the bands X of all the Band sets, which is equivalent to [bandset1bX, bandset2bX, ..., bandsetNbX]; to be used in expressions that accept band lists such as the mean value:

mean("bandset*b1")

• bandset{ DATE }b BAND_NUMBER: list of all the bands X of all the Band sets matching a list of dates (format yyyy-mm-dd) between curly brackets (e.g. {2019-01-01,2019-07-31}) or range of dates separated by colon (e.g. {2019-01-01:2019-07-31}) or a list of ranges of dates (e.g. {2019-01-01:2019-01-31, 2019-04-01:2019-07-31}), which is equivalent to [bandset2bX, bandset5bX, ..., bandsetNbX]; Band sets dates are defined in Band set definition (c. 46); this variable can be used in expressions that accept band lists such as the median value:

median("bandset{2019-01-01,2019-07-31}b1")

- #BLUE#: the band with the center wavelength closest to 0.475 μm ;
- #GREEN#: the band with the center wavelength closest to 0.56 μm ;
- ${}^{\ast}\#RED\#$: the band with the center wavelength closest to 0.65 μm ;
- #NIR#: the band with the center wavelength closest to 0.85 μm ; for example:

("#NIR#" - "#RED#") / ("#NIR#" + "#RED#")

Output variables

Output names can be defined in the expression line entering the symbol **Q** followed by the name, such as the following example:

"raster1" * 2 @first_calculation

If the output name is defined in the expression, an output directory will be selected after clicking the button RUN.

Предупреждение: It is recommended to avoid the use of characters # and @ in the output raster name.

It is possible to set the **output path** directly by defining the output name with this structure **OpathOname**, such as:

"raster1" * 2 @/home/user@first_calculation

The directory will be created if it does not exist.

It is possible to create a **temporary output** (saved in the temporary directory) with <code>@temp@</code> followed by output name, such as:

"raster1" * 2 @temp@first_calculation

The **output name** of calculation can be used **as input variable** for the following calculations; for example:

```
"raster1" * 2 @first_calculation
"first_calculation" + 5 @temp@second_calculation
"second_calculation" - "raster1" @/home/user@third_calculation
```

It is possible to **add the calculation result to a Band set** using the symbol % followed by the *Band set* number such as:

"raster1" @first_calculation%1

It is possible to **add the calculation result to the active Band set** using the symbol % followed by the symbol **#** such as:

"raster1" @first_calculation%#

Also, variables for output name are available:

- #BANDSET#: the name of the first band in the *Band set* (c. 45);
- #DATE#: the current date and time (e.g. 20161110_113846527764);

Using the symbol @ followed by the variable #BANDSET# can save the raster calculation inside the **directory containing the first band** of the active band set, such as:

"raster1" @#BANDSET#@first_calculation

If the output name is defined with the extension .vrt, the output will be a virtual raster referencing the single .tif files calculated by parallel processing. For instance, the following expression will calculate the raster with parallel processing and the output will be a .vrt:

"raster1" @first_calculation.vrt

Virtual file is useful to reduce calculation time of parallel processing by avoiding the writing of the entire output raster.

Предупреждение: A .vrt virtual file is a text file containing the reference to existing .tif files. Moving the .vrt virtual file or the .tif files in different directories can make the virtual file unusable.

Functions

Conditional

• *where*: conditional expression according to the syntax where(condition , value if true, value if false) for example:

```
where("raster1" == 1, 2, "raster1")
```

Parenthesis are required for multiple conditions for instance to select pixel values between 1 and 3:

where(("raster1" > 1) & ("raster1" < 3), 2, "raster1")</pre>

Nested conditions can be defined such as:

where(("raster1" > 1) & ("raster1" < 3), 2, "raster1")</pre>

Logical

- AND: AND;
- *OR*: OR;
- XOR: XOR;
- NOT: NOT;

Statistics

A band list between square brackets or Input variables (c. 102) are required arguments.

• *max*: maximum; for instance:

max(["raster1", "raster2", "raster3"])

• *min*: minimum; for instance:

min(["bandset#b*"])

• *mean*: mean; for instance:

mean("bandset*b1")

• *median*: median; for instance:

median("bandset{2019-01-01,2019-07-31}b1")

• *percentile*: percentile calculation; the expression must have this structure **percentile([band_list], percentile_value)**; for instance, the following expression calculates the 10th percentile of active band set:

percentile("bandset#b*", 10)

• *std*: standard deviation; for instance:

std("bandset{1,3}b1")

• *sum*: sum; for instance:

sum("bandset{1:5}b1")

Operations

• *sin*: sine; for instance:

sin("raster1")

- cos: cosine;
- *tan*: tangent;
- *asin*: inverse sine;
- *acos*: inverse cosine;
- *atan*: inverse tangent;
- *exp*: natural exponential;
- *ln*: natural logarithm;
- *log*: base 10 logarithm;

Indices

• NDVI: if selected, the NDVI calculation is entered in the Expression:

```
( "#NIR#" - "#RED#" ) / ( "#NIR#" + "#RED#" ) @ NDVI
```

• *EVI*: if selected, the EVI calculation is entered in the *Expression*:

2.5 * ("#NIR#" - "#RED#") / ("#NIR#" + 6 * "#RED#" - 7.5 * "#BLUE#" + 1) @ EVI

• *NBR*: if selected, the NBR calculation is entered in the *Expression*:

```
( "#NIR#" - "#SWIR2#" ) / ( "#NIR#" + "#SWIR2#" ) @NBR
```

Variables

• nodata: NoData value of raster (e.g. nodata("raster1")); it can be used as value in the expression:

```
where("raster1" == nodata("raster1"), 0, "raster1")
```

• forbandsets: it allows for the iteration over Band sets defined between square brackets; a range of Band sets separated by colon (e.g. forbandsets[1:3]) or a list separated by commas (e.g. forbandsets[1,2,3]; forbandsets must be entered in the first line of expressions (not compatible with forbandsinbandset), for instance:

```
forbandsets[1:3]
"bandset#b1" @#BANDSET#
```

During the iteration, the *Input variables* (c. 102) related to the active *Band set* are replaced by the iterator, therefore the expression:

```
forbandsets[1:3]
"bandset#b1" @#BANDSET#
```

is equivalent to:

```
"bandset1b1" @calc1
"bandset2b1" @calc2
"bandset3b1" @calc3
```

It is possible to enter a string (or a list of strings separated by comma ,) after the square bracket] to filter *Band sets* by the name of first band in *Band set*; for instance, the following expression will iterate the first 3 *Band sets* selecting only the *Band set* whose name of the first band includes RT:

forbandsets[1,2,3]RT

Also, *forbandsets*: allows for the iteration over *Band sets* dates (format yyyy-mm-dd, defined in *Band set definition* (c. 46)) between square brackets, such as the following examples:

Iterating over a range of dates:

```
forbandsets[2020-01-01:2020-07-31]
"bandset#b1" @#BANDSET#
```

Iterating over a list of dates:

```
forbandsets[2020-02-01,2020-03-11,2020-04-21]
"bandset#b1" @#BANDSET#
```

Iterating over a list of ranges of dates:

```
forbandsets[2010-01-01:2010-06-31, 2010-08-01:2010-08-31, 2010-10-01:2010-12-31]
"bandset#b1" @#BANDSET#
```

During the iteration, the *Input variables* (c. 102) related to the active *Band set* are replaced by the iterator.

It is possible to enter a string (or a list of strings separated by comma ,) after the square bracket] to filter *Band sets* by the name of first band in *Band set*; for instance, the following expression will iterate the *Band sets* in the range selecting only the *Band set* whose name of the first band includes RT:

forbandsets[2020-01-01:2020-07-31]RT

• *forbandsinbandset*: it allows for the iteration over bands in a *Band set* or a range of *Band sets* between square brackets; forbandsinbandset must be entered in the first line of expressions (not compatible with forbandsets); the variable #BAND# must be used to refer to the iterated band such as the following examples:

Iterating over the bands of the first *Band set* (note the " in the expression):

```
forbandsinbandset[1]
where("#BAND#" > 1, 1, 2) @#BAND#)
```

Iterating over all the bands of *Band sets* from 1 to 3:

```
forbandsinbandset[1:3]
where("#BAND#" > 1, 1, 2) @#BAND#)
```

- *#BAND#*:
- #BANDSET#: the name of the first band in the *Band set* (c. 45);
- #DATE#: the current date and time (e.g. 20161110_113846527764);
- *@*: character *@*;

3.4.8 Script

• *Script* (c. 108)

| 2 | Semi-Automatic Classification Plugin | + _ = × |
|---------------------|--|---------|
| Filter | | |
| and set | Script (copy the code in a Python shell) | Tool |
| 👆 Download products | | |
| Basic tools | | ۲ |
| Preprocessing | | Help |
| 🕨 🍫 Band processing | | 9 |
| Postprocessing | | |
| 🛗 Band calc | | |
| Script | | |
| 🕨 🎢 Settings | | |
| User manual | | |
| 💽 Help | | |
| 🔛 About | | |
| | | |
| | Copy Save to file | |

Рис. 46: Script

This tab displays the output of the *Script* buttons that are available in several tools, which ease the creation of Python scripts using Remotior Sensus.

It is possible to edit or copy the Python code and run it in a Python shell. New code is appended to the existing one, when using the Script buttons.

Script

| Tool symbol and name | Description | | |
|----------------------|---|--|--|
| × | clear the content of the script | | |
| Copy | copy the content of the script to the clipboard | | |
| Save to file 个 | save the script to file .py | | |

3.4.9 Settings

The tab *Settings* allows for the customization of *SCP*.

Debug

- *Log file* (c. 110)
- *Test* (c. 110)

| | Semi-Automatic Classification Plugin | + _ □ × |
|--|---|--------------------------|
| Filter | Log file | Tool |
| Download products Basic tools | ✓ Record detailed events in a Log file Test | |
| Preprocessing Band processing Postprocessing | Test dependencies | Help |
| Band calc | | |
| Settings Debug Interface | | |
| Processing setting User manual Help | | |
| About | | |
| | | |
| | | |
| | | |
| | | |

Рис. 47: Debug

This tab allows for the debug of SCP in case of issues, and the check of SCP dependencies.

Log file

| Tool symbol and name | Description |
|---|---|
| Record detailed events in a Log file ullet | if checked, start recording detailed events in a Log file |
| 1 | export the Log file to a .txt file |

Test

| Tool symbol and name | Description |
|-------------------------|--|
| Test dependencies | test <i>SCP</i> dependencies (NumPy, SciPy, Matplotlib, GDAL, PyTorch, scikit-learn, Remotior Sensus, Multiprocess, Internet connection) |

Interface

- *ROI style* (c. 111)
- Variable name for expressions (c. 111)
- Temporary group name (c. 111)
- *Dock* (c. 111)

| | Semi-Automatic Classification Plugin | + _ □ × |
|--|---|---------|
| Filter Fi | ROI style ROI color Transparency 45% Variable name for expressions Variable name raster Project Group name Class_temp_group Create RGB composite of band set when a project is loaded Dock Volume Variable names on startup | Incol |

Рис. 48: Interface

This tab includes a few advanced settings of the SCP interface.

ROI style

Change ROI color and transparency for a better visualization of temporary ROIs on the map.

| Tool symbol and name | Description |
|----------------------|---|
| ROI color | button for changing ROI color |
| Transparency | change ROI transparency |
| × | reset ROI color and transparency to default |

Variable name for expressions

Set the variable name used in expressions of the *Reclassification* (c. 97).

| Tool symbol and name | Description |
|----------------------|---------------------------------------|
| Variable name 🔳 🎴 | set variable name (default is raster) |
| × | reset variable name to default |

Temporary group name

| Tool symbol and name | Description |
|--|---|
| Group name 💶 🔎 | set group name (default is Class_temp_group) |
| × | reset group name to default |
| Create RGB composite of band set when a project is loaded | if checked, a RGB composite of active band set is added to the map when a project is loaded |

Dock

| | symbol and | Description |
|------|------------|---|
| name | | |
| ~ | Download | · · · · · · · · · · · · · · · · · · · |
| news | on startup | and displayed in <i>Dock</i> ; also, it checks for updates of Remotior Sensus |
| • | | |

Processing setting

- *System* (c. 112)
- Calculation process (c. 113)
- SMTP process notification (c. 113)
- Temporary directory (c. 113)
- External programs (c. 114)

| | Semi-Automa | tic Classification Plugin | | ↑ _ □ X |
|--|--|---------------------------|------------|------------|
| Filter Band set Download products Basic tools Preprocessing Band processing | System Available RAM (MB) CPU threads Calculation process | | | 1024 🛊 |
| Postprocessing Band calc | Play sound when finished | V Raster o | ompression | |
| Script Settings Debug Interface | SMTP process notification SMTP server | user | password | ✓ remember |
| Processing setting User manual Help About | Send email of completed process to Temporary directory External programs GDAL installation directory | | | |
| | | | | |

Рис. 49: Processing

System

| Tool symbol and name | Description |
|---|---|
| Available RAM (MB) | set the available RAM (in MB) that is used during the processes in order to improve the SCP performance; this value should be half of the system RAM (e.g. 1024MB if system has 2GB of RAM) |
| $\begin{array}{c} CPU & threads \\ \hline 1 \\ \hline \end{array} \bullet \end{array}$ | set the number of threads available for processing; it is recommended to set a value lower than the maximum number of system threads (e.g. if the system has 4 available threads set value 3) |

Calculation process

| Tool symbol and name | Description |
|--------------------------|--|
| Sound Play sound when | if checked, play a sound when the process is completed |
| Raster compression | if checked, a lossless compression (DEFLATE or PACKBITS) is applied to raster outputs in order to save disk space; it is recommended to check this option to save disk space, or uncheck to faster the calculation |

SMTP process notification

| Tool symbol and name | Description |
|---------------------------------------|---|
| SMTP server | the SMTP server to login for sending a notification email when all the <i>SCP</i> processes are finished (a notification is sent also in case of error, but not in case of crash) |
| user T | the SMTP server user |
| password T | the SMTP server password |
| Send email of completed process to | a list of addresses (separated by comma) to send the notification email to |
| Т | |

| Предупреждение: | $_{\mathrm{If}}$ | remember is | checked, | the password | is stored | unencrypted in QGIS |
|-----------------|------------------|-------------|----------|--------------|-----------|---------------------|
| registry. | | | | | | |

Temporary directory

Г

| Tool symbol and name | Description |
|----------------------------|---|
|] • | select a new temporary directory where temporary files are saved during the processing; the path to the current temporary directory is displayed; default is a system temporary directory |
| × | reset to default temporary directory |

External programs

Some tools require external programs to perform the processing.

| Tool symbol and | l name | Description |
|--------------------|----------|---|
| GDAL inst | allation | enter the path to the GDAL directory containing tools such as |
| directory T |] | gdal_translate and gdalwarp (e.g. /usr/bin); this parameter is usually not required |
| • | | |

3.5 Spectral Signature Plot

The window Spectral Signature Plot includes several functions for displaying spectral signature values as a function of wavelength (defined in the *Band set* (c. 45)). Signatures can be added to the Spectral Signature Plot through the SCP dock (c. 31).

Overlapping signatures (belonging to different classes or macroclasses) are highlighted in orange in the table $Signature \ list$ (c. 115); the overlapping check is performed considering $MC \ ID$ or $C \ ID$ according

to the setting $Use \bowtie MC ID \bowtie C ID$ in *Classification* (c. 75). Overlapping signatures sharing the same ID are not highlighted.




Рис. 50: Spectral Signature Plot

3.5.1 Signature list

The Signature list is a table that includes the spectral signatures added from the SCP dock (c. 31).

| S | MC ID | MC Name | C ID | C Name | Color |
|--|----------|------------|------|-----------|---|
| checkbox field; if checked, the spectral signature is displayed in the plot | Macrocla | 0 | 0 | 0 | signature color; also, the combination MC ID - C ID is displayed in case of overlap with other signatures |

The following tools are available.

| Tool symbol and name | Description |
|-------------------------|--|
| | remove highlighted signatures from this list |
| > | add highlighted spectral signatures to ROI & Signature list (c. 36) |
| 2 | calculate the spectral distances of spectral signatures displayed in the plot; distances are reported in the tab $Spectral \ distances$ (c. 116) |

Plot

Left click and hold inside the plot to move the view of the plot. Use the mouse wheel to zoom in and out the view of the plot. Right click and hold inside the plot to zoom in a specific area of the plot. Legend inside the plot can be moved using the mouse.

The following tools are available.

| Tool symbol and name | Description |
|----------------------|--|
| \sim | automatically fit the plot to data |
| ₩ | save the plot image to file (available formats are .jpg, .png, and .pdf) |
| ✓ Plot value range | if checked, plot the value range for each signature with a semi-transparent area |
| Band lines | if checked, display a vertical line for each band (center wavelength) |
| Grid | if checked, display a grid |
| Max characters | set the maximum length of text in the legend |
| $x \ y$ | display x y coordinates of mouse cursor inside the plot |



Рис. 51: Spectral Signature: Example of plot

Signature details

Display the details about spectral signatures (i.e. Wavelength, Values, and Standard deviation). In case of signatures calculated from ROIs, the ROI size (number of pixels) is also displayed.

Spectral distances

Display spectral distances of signatures (see *Signature list* (c. 115)), which are useful for assessing ROI separability (see *Spectral Distance* (c. 143)).

The following spectral distances are calculated :

- Spectral Angle (c. 143): range [0 = identical, 90 = different]; useful in particular for Spectral Angle Mapping (c. 138) classifications
- Euclidean Distance (c. 143): useful in particular for Minimum Distance (c. 136) classifications
- Bray-Curtis Similarity (c. 144): range [0 = different, 100 = identical]; useful in general

Values are displayed in red if signatures are particularly similar.

| 1 | | MC Nam | e | C ID | C | Name | | | Color | | |
|-----|------------------|------------------|-----------------|------------|---------------|---------|---------|---------|---------|---------|--------|
| · · | 1 Water | | | 1 | Water | | | | | | |
| / 2 | 2 Vegetation | | | 2 | Vegetation | | | | | | |
| / : | 3 Built-up | | | 3 | Built-up | | | | | | |
| | | 1#Water; | 1#Water; Pixe | l count=7 | 22 | | | | | | |
| | Wavelength | 0.49 | 0.56 | 0.665 | 0.705 | 0.74 | 0.783 | 0.842 | 0.865 | 1.61 | 2.19 |
| | Values | 0.14122 | 0.14608 | 0.1173 | 0.11569 | 0.11444 | 0.11473 | 0.11404 | 0.1135 | 0.10627 | 0.1049 |
| St | tandard deviatio | n 0.00156 | 0.00159 | 0.0007 | 75 0.00075 | 0.0009 | 0.00087 | 0.00077 | 0.0009 | 0.00048 | 0.0007 |
| 51 | | 2#Vegetat | ion; 2#Vegeta | ation; Pix | el count=2465 | | | | | | |
| | Wavelength | 0.49 | 0.56 | 0.665 | 0.705 | 0.74 | 0.783 | 0.842 | 0.865 | 1.61 | 2.19 |
| | Values | 0.13272 | 0.16726 | 0.1385 | 5 0.21352 | 0.42234 | 0.4768 | 0.4905 | 0.51066 | 0.31444 | 0.2063 |
| St | tandard deviatio | n 0.00316 | 0.00543 | 0.0050 | 0.00997 | 0.02877 | 0.03365 | 0.0376 | 0.0352 | 0.01395 | 0.0109 |
| | | 3#Built-up | ; 3#Built-up; l | Pixel cou | nt=65 | | | | | | |
| | Wavelength | 0.49 | 0.56 | 0.665 | 0.705 | 0.74 | 0.783 | 0.842 | 0.865 | 1.61 | 2.19 |
| SI | Values | 0.2072 | 0.23034 | 0.2496 | 0.26636 | 0.30849 | 0.32466 | 0.3251 | | 0.33517 | |
| | tandard deviatio | n 0.01377 | 0.01708 | 0.0229 | 0.01814 | 0.02355 | 0.0271 | 0.03783 | 0.02778 | 0.02503 | 0.0252 |

Рис. 52: Spectral Signature: Example of signature details




Рис. 53: Spectral Signature: Example of spectral distances

3.6 Scatter Plot

The window *Scatter plot* displays pixel values for two raster bands as points in the 2D space. Scatter plots are useful for assessing ROI separability between two bands.

| | | 9 | SCP: Scatter Plot | | + _ □ × |
|---------|---------------|-----|-------------------|-------|---|
| Scatter | list | | | | |
| | IC ID MC Name | CID | C Name | Color | Band X 1 Band Y 2 Precision 3 Calculate E |
| | | | | | Plot Colormap 🔹 x=0.979253 y=0.208160 |

Рис. 54: Scatter Plot

The functions are described in detail in the following paragraphs.

3.6.1 Scatter list

The Scatter list is a table that includes the spectral signatures added from the SCP dock (c. 31).

| S | MC ID | MC Name | C ID | C Name | Color |
|---|-------|---------------------------------|-----------------------|----------------------------|--------------------|
| checkbox field; if checked, the spectral signature is displayed in the plot | 0 | signature Macroclass Name | signature Class ID | signature Class Name | signature color |

The following tools are available.

| Tool symbol and name | Description |
|---|---|
| Band X | X band of the plot |
| $\begin{array}{c} Band \qquad Y \\ \hline 1 \diamondsuit \end{array}$ | Y band of the plot |
| | remove highlighted signatures from this list |
| > | add highlighted spectral signatures to $ROI \ & Signature \ list$ (c. 36) |
| ✓ Precision | use custom precision for calculation (precision should be selected according significant digits): * $4 = 10^{-4}$ * $3 = 10^{-3}$ * $2 = 10^{-2}$ * $1 = 10^{-1}$ * $0 = 1$ * $-1 = 10$ * $-2 = 10^{2}$ * $-3 = 10^{3}$ |
| $\boxed{Calculate}_{:}$ | calculate the scatter plot for the ROIs checked in the list |
| | remove highlighted signatures from this list |
| | add a temporary scatter plot to the list (as MC Name = tempScatter) and start the plot calculation of the last temporary ROI (see <i>Working toolbar</i> (c. 41)) |

Предупреждение: Using a precision value that is too high can result in slow calculation or failure.

Plot

Left click and hold inside the plot to move the view of the plot. Use the mouse wheel to zoom in and out the view of the plot. Right click and hold inside the plot to zoom in a specific area of the plot.

| Tool symbol and name | Description |
|----------------------------|---|
| Colormap | select a colormap that is applied to highlighted scatter plots in the list when is clicked; if no scatter plot is highlighted then the colormap is applied to all the scatter plots |
| \sim | automatically fit the plot to data |
| ₩ | save the plot image to file (available formats are .jpg, .png, and .pdf) |
| $x \ y$ | display x y coordinates of mouse cursor inside the plot |




Рис. 55: Example Scatter Plot

3.7 Integration in QGIS Processing

Several SCP tools can be accessed from the QGIS Processing Toolbox, and can be used to create models. The tools are available in the menu *Semi-Automatic Classification Plugin*.

| 2 🔎 🛛 RGB = - 🔽 🙈 🙈 🔎 🔍 ROI 🔀 🕂 💽 🗖 Vock 🛛 🕅 🕅 | iist 0.010000 | 00 🛟 💬 🔍 Preview 📑 🚺 🖬 0 💠 S emi-Automatic Classification Plugin | 200 🗘 🗰 | • - |
|---|---|--|--|--------|
| Filter > Easic too MC ID * C ID Name Type Col Image: Second state of the seco | essing coessing lices sg setting | et definition Active band set 1 🗘 Date NaT Band name | Root directory Center wavelength Multipli | |
| MC ID 1 + MC Name Macroclass 1 C ID 1 + C Name Class 1 C ID 1 + C Name Class 1 | Waveler | uick settings gth Band order et tools e virtual raster (Sreate raster of ban Build band di set (stack bands) | v Wavelen band nubabe d overview Band calc expressio RUN | 2021 - |

The functions described in the following paragraphs use these conventions:




Рис. 56: Integration in QGIS Processing Toolbox

| 1980 🗸 | Input date |
|--------|--|
| T | Input text |
| ~ | List |
| 1\$ | Input number |
| • | Optional |
| ۲ | Configuration stored in the active project of QGIS |
| • | Configuration stored in QGIS registry |
| | Slider |
| | Table |

Глава 4

Brief Introduction to Remote Sensing

- Basic Definitions (c. 124)
 - GIS definition (c. 124)
 - Remote Sensing definition (c. 124)
 - Sensors (c. 125)
 - Radiance and Reflectance (c. 125)
 - Spectral Signature (c. 127)
 - Land Cover (c. 127)
- Multispectral satellites (c. 127)
 - Landsat Satellites (c. 127)
 - Sentinel-2 Satellite (c. 129)
 - Sentinel-3 Satellite (c. 129)
 - ASTER Satellite (c. 130)
 - MODIS Products (c. 130)
 - GOES Products (c. 131)
- SAR satellites (c. 131)
 - Sentinel-1 Satellites (c. 132)
- Land Cover Classification (c. 133)
 - Supervised Classification (c. 133)
 - Color Composite (c. 133)
 - Training Areas (c. 134)
 - Classes and Macroclasses (c. 135)
 - Classification Algorithms (c. 136)
 - Machine Learning (c. 141)

- Spectral Distance (c. 143)
- Classification Result (c. 144)
- Accuracy Assessment (c. 145)
- Image processing (c. 146)
 - Principal Component Analysis (c. 146)
 - Pan-sharpening (c. 146)
 - Spectral Indices (c. 147)
 - Clustering (c. 148)
- Image conversion to reflectance (c. 150)
 - Radiance at the Sensor's Aperture (c. 150)
 - Top Of Atmosphere (TOA) Reflectance (c. 150)
 - Surface Reflectance (c. 151)
 - DOS1 Correction (c. 151)
- Conversion to Temperature (c. 154)
 - Conversion to At-Satellite Brightness Temperature (c. 154)
 - Estimation of Land Surface Temperature (c. 155)
- *References* (c. 155)

4.1 Basic Definitions

This chapter provides basic definitions about GIS and remote sensing.

4.1.1 GIS definition

There are several definitions of **GIS** (Geographic Information Systems), which is not simply a program. In general, GIS are systems that allow for the use of geographic information (data have spatial coordinates). In particular, GIS allow for the view, query, calculation and analysis of spatial data, which are mainly distinguished in raster or vector data structures. Vector is made of objects that can be points, lines or polygons, and each object can have one or more attribute values; a raster is a grid (or image) where each cell has an attribute value (Fisher and Unwin, 2005). Several GIS applications use raster images that are derived from remote sensing.

4.1.2 Remote Sensing definition

A general definition of **Remote Sensing** is «the science and technology by which the characteristics of objects of interest can be identified, measured or analyzed the characteristics without direct contact» (JARS, 1993).

Usually, remote sensing is the measurement of the energy that is emanated from the Earth's surface. If the source of the measured energy is the sun, then it is called **passive remote sensing**, and the result of this measurement can be a digital image (Richards and Jia, 2006). If the measured energy is not emitted by the Sun but from the sensor platform then it is defined as **active remote sensing**, such as radar sensors which work in the microwave range (Richards and Jia, 2006).

The **electromagnetic spectrum** is «the system that classifies, according to wavelength, all energy (from short cosmic to long radio) that moves, harmonically, at the constant velocity of light» (NASA,

2013). Passive sensors measure energy from the optical regions of the electromagnetic spectrum: visible, near infrared (i.e. IR), short-wave IR, and thermal IR (see Figure *Electromagnetic-Spectrum* (c. 126)).

The interaction between solar energy and materials depends on the wavelength; solar energy goes from the Sun to the Earth and then to the sensor. Along this path, **solar energy** is (NASA, 2013):

- **Transmitted** The energy passes through with a change in velocity as determined by the index of refraction for the two media in question.
- Absorbed The energy is given up to the object through electron or molecular reactions.
- **Reflected** The energy is returned unchanged with the angle of incidence equal to the angle of reflection. Reflectance is the ratio of reflected energy to that incident on a body. The wavelength reflected (not absorbed) determines the color of an object.
- **Scattered** The direction of energy propagation is randomly changed. Rayleigh and Mie scatter are the two most important types of scatter in the atmosphere.
- **Emitted** Actually, the energy is first absorbed, then re-emitted, usually at longer wavelengths. The object heats up.


4.1.3 Sensors


Sensors can be on board of airplanes or on board of satellites, measuring the electromagnetic radiation at specific ranges (usually called bands). As a result, the measures are quantized and converted into a digital image, where each picture elements (i.e. pixel) has a discrete value in units of Digital Number (DN) (NASA, 2013). The resulting images have different characteristics (resolutions) depending on the sensor. There are several kinds of **resolutions**:

- **Spatial resolution**, usually measured in pixel size, «is the resolving power of an instrument needed for the discrimination of features and is based on detector size, focal length, and sensor altitude» (NASA, 2013); spatial resolution is also referred to as geometric resolution or IFOV;
- **Spectral resolution**, is the number and location in the electromagnetic spectrum (defined by two wavelengths) of the spectral bands (NASA, 2013) in multispectral sensors, for each band corresponds an image;
- Radiometric resolution, usually measured in bits (binary digits), is the range of available brightness values, which in the image correspond to the maximum range of DNs; for example an image with 8 bit resolution has 256 levels of brightness (Richards and Jia, 2006);
- For satellites sensors, there is also the **temporal resolution**, which is the time required for revisiting the same area of the Earth (NASA, 2013).

4.1.4 Radiance and Reflectance

Sensors measure the **radiance**, which corresponds to the brightness in a given direction toward the sensor; it useful to define also the **reflectance** as the ratio of reflected versus total power energy.





via Wikimedia Commons

http://commons.wikimedia.org/wiki/File%3AElectromagnetic-Spectrum.svg

4.1.5 Spectral Signature

The **spectral signature** is the reflectance as a function of wavelength (see Figure *Spectral Reflectance Curves of Four Different Targets* (c. 127)); each material has a unique signature, therefore it can be used for material classification (NASA, 2013).




Рис. 2: Spectral Reflectance Curves of Four Different Targets (from NASA, 2013)

4.1.6 Land Cover

Land cover is the material at the ground, such as soil, vegetation, water, asphalt, etc. (Fisher and Unwin, 2005). Depending on the sensor resolutions, the number and kind of land cover classes that can be identified in the image can vary significantly.

4.2 Multispectral satellites

There are several satellites with different characteristics that acquire multispectral images of earth surface. The following satellites are particularly useful for land cover monitoring because images are provided for free and can be downloaded directly from SCP; data have been acquired for the past few decades and the archive is continuously growing with recent images.

4.2.1 Landsat Satellites

Landsat is a set of multispectral satellites developed by the NASA (National Aeronautics and Space Administration of USA), since the early 1970's.

Landsat images are very used for environmental research. The resolutions of Landsat 4 and Landsat 5 sensors are reported in the following table (from http://landsat.usgs.gov/band_designations_landsat_ satellites.php); also, Landsat temporal resolution is 16 days (NASA, 2013).

Landsat 4 and Landsat 5 Bands

| Landsat 4, Landsat 5 Bands | Wavelength [micrometers] | Resolution [meters] |
|------------------------------|--------------------------|--------------------------|
| Band 1 - Blue | 0.45 - 0.52 | 30 |
| Band 2 - Green | 0.52 - 0.60 | 30 |
| Band 3 - Red | 0.63 - 0.69 | 30 |
| Band 4 - Near Infrared (NIR) | 0.76 - 0.90 | 30 |
| Band 5 - SWIR | 1.55 - 1.75 | 30 |
| Band 6 - Thermal Infrared | 10.40 - 12.50 | 120 (resampled to 30) |
| Band 7 - SWIR | 2.08 - 2.35 | 30 |

The resolutions of Landsat 7 sensor are reported in the following table (from http://landsat.usgs.gov/band_designations_landsat_satellites.php); also, Landsat temporal resolution is 16 days (NASA, 2013).

Landsat 7 Bands

| Landsat 7 Bands | Wavelength [micrometers] | Resolution [meters] |
|------------------------------|--------------------------|-------------------------|
| Band 1 - Blue | 0.45 - 0.52 | 30 |
| Band 2 - Green | 0.52 - 0.60 | 30 |
| Band 3 - Red | 0.63 - 0.69 | 30 |
| Band 4 - Near Infrared (NIR) | 0.77 - 0.90 | 30 |
| Band 5 - SWIR | 1.57 - 1.75 | 30 |
| Band 6 - Thermal Infrared | 10.40 - 12.50 | 60 (resampled to 30) |
| Band 7 - SWIR | 2.09 - 2.35 | 30 |
| Band 8 - Panchromatic | 0.52 - 0.90 | 15 |

The resolutions of Landsat 8 sensor are reported in the following table (from http://landsat.usgs.gov/band_designations_landsat_satellites.php); also, Landsat temporal resolution is 16 days (NASA, 2013).

Landsat 8 Bands

| Landsat 8 Bands | Wavelength [micrometers] | Resolution [meters] |
|-------------------------------------|--------------------------|--------------------------|
| Band 1 - Coastal aerosol | 0.43 - 0.45 | 30 |
| Band 2 - Blue | 0.45 - 0.51 | 30 |
| Band 3 - Green | 0.53 - 0.59 | 30 |
| Band 4 - Red | 0.64 - 0.67 | 30 |
| Band 5 - Near Infrared (NIR) | 0.85 - 0.88 | 30 |
| Band 6 - SWIR 1 | 1.57 - 1.65 | 30 |
| Band 7 - SWIR 2 | 2.11 - 2.29 | 30 |
| Band 8 - Panchromatic | 0.50 - 0.68 | 15 |
| Band 9 - Cirrus | 1.36 - 1.38 | 30 |
| Band 10 - Thermal Infrared (TIRS) 1 | 10.60 - 11.19 | 100 (resampled to 30) |
| Band 11 - Thermal Infrared (TIRS) 2 | 11.50 - 12.51 | 100 (resampled to 30) |

A vast archive of images is freely available from the U.S. Geological Survey . For more information about how to freely download Landsat images read this .

Images are identified with the paths and rows of the WRS (Worldwide Reference System for Landsat).

4.2.2 Sentinel-2 Satellite

Sentinel-2 is a multispectral satellite developed by the European Space Agency (ESA) in the frame of Copernicus land monitoring services. Sentinel-2 acquires 13 spectral bands with the spatial resolution of 10m, 20m and 60m depending on the band, as illustrated in the following table (ESA, 2015).

Sentinel-2 Bands

| Sentinel-2 Bands | Central Wavelength [micrometers] | Resolution [meters] |
|-------------------------------|----------------------------------|---------------------|
| Band 1 - Coastal aerosol | 0.443 | 60 |
| Band 2 - Blue | 0.490 | 10 |
| Band 3 - Green | 0.560 | 10 |
| Band 4 - Red | 0.665 | 10 |
| Band 5 - Vegetation Red Edge | 0.705 | 20 |
| Band 6 - Vegetation Red Edge | 0.740 | 20 |
| Band 7 - Vegetation Red Edge | 0.783 | 20 |
| Band 8 - NIR | 0.842 | 10 |
| Band 8A - Vegetation Red Edge | 0.865 | 20 |
| Band 9 - Water vapour | 0.945 | 60 |
| Band 10 - SWIR - Cirrus | 1.375 | 60 |
| Band 11 - SWIR | 1.610 | 20 |
| Band 12 - SWIR | 2.190 | 20 |

Sentinel-2 images are freely available from the ESA website https://scihub.copernicus.eu.

4.2.3 Sentinel-3 Satellite

Sentinel-3 is a satellite developed by the European Space Agency (ESA) in the frame of Copernicus land monitoring services. It carries several instruments, in particular the Ocean and Land Colour Instrument (OLCI) is a push-broom imaging spectrometer acquiring 21 bands in the range 0.4-1.02 m with a swath width of 1,270km and 300m spatial resolution (ESA, 2013). The revisit time is about 2 days.

Sentinel-3 Bands

| Sentinel-3 Bands | Central Wavelength [micrometers] |
|------------------|----------------------------------|
| Oa1 | 0.400 |
| Oa2 | 0.4125 |
| Oa3 | 0.4425 |
| Oa4 | 0.490 |
| Oa5 | 0.510 |
| Oa6 | 0.560 |
| Oa7 | 0.620 |
| Oa8 | 0.665 |
| Oa9 | 0.67375 |
| Oa10 | 0.68125 |
| Oa11 | 0.70875 |
| Oa12 | 0.75375 |
| Oa13 | 0.76125 |
| Oa14 | 0.764375 |
| Oa15 | 0.7675 |
| Oa16 | 0.77875 |
| Oa17 | 0.865 |
| Oa18 | 0.885 |
| Oa19 | 0.900 |
| Oa20 | 0.940 |
| Oa21 | 1.020 |

4.2.4 ASTER Satellite

The **ASTER** (Advanced Spaceborne Thermal Emission and Reflection Radiometer) satellite was launched in 1999 by a collaboration between the Japanese Ministry of International Trade and Industry (MITI) and the NASA. ASTER has 14 bands whose spatial resolution varies with wavelength: 15m in the visible and near-infrared, 30m in the short wave infrared, and 90m in the thermal infrared (USGS, 2015). ASTER bands are illustrated in the following table (due to a sensor failure **SWIR data acquired since April 1, 2008 is not available**). An additional band 3B (backwardlooking near-infrared) provides stereo coverage.

ASTER Bands

| ASTER Bands | Wavelength [micrometers] | Resolution [meters] |
|-------------------------------|--------------------------|---------------------|
| Band 1 - Green | 0.52 - 0.60 | 15 |
| Band 2 - Red | 0.63 - 0.69 | 15 |
| Band 3N - Near Infrared (NIR) | 0.78 - 0.86 | 15 |
| Band 4 - SWIR 1 | 1.60 - 1.70 | 30 |
| Band 5 - SWIR 2 | 2.145 - 2.185 | 30 |
| Band 6 - SWIR 3 | 2.185 - 2.225 | 30 |
| Band 7 - SWIR 4 | 2.235 - 2.285 | 30 |
| Band 8 - SWIR 5 | 2.295 - 2.365 | 30 |
| Band 9 - SWIR 6 | 2.360 - 2.430 | 30 |
| Band 10 - TIR 1 | 8.125 - 8.475 | 90 |
| Band 11 - TIR 2 | 8.475 - 8.825 | 90 |
| Band 12 - TIR 3 | 8.925 - 9.275 | 90 |
| Band 13 - TIR 4 | 10.25 - 10.95 | 90 |
| Band 14 - TIR 5 | 10.95 - 11.65 | 90 |

4.2.5 MODIS Products

The **MODIS** (Moderate Resolution Imaging Spectroradiometer) is an instrument operating on the Terra and Aqua satellites launched by NASA in 1999 and 2002 respectively. Its temporal resolutions allows for viewing the entire Earth surface every one to two days, with a swath width of 2,330km. Its sensors measure 36 spectral bands at three spatial resolutions: 250m, 500m, and 1,000m (see https: //lpdaac.usgs.gov/dataset_discovery/modis).

Several products are available, such as surface reflectance and vegetation indices. In this manual we are considering the surface reflectance bands available at 250m and 500m spatial resolution (Vermote, Roger, & Ray, 2015).

MODIS Bands

| MODIS Bands | Wavelength [micrometers] | Resolution [meters] |
|------------------------------|--------------------------|---------------------|
| Band 1 - Red | 0.62 - 0.67 | 250 - 500 |
| Band 2 - Near Infrared (NIR) | 0.841 - 0.876 | 250 - 500 |
| Band 3 - Blue | 0.459 - 0.479 | 500 |
| Band 4 - Green | 0.545 - 0.565 | 500 |
| Band 5 - SWIR 1 | 1.230 - 1.250 | 500 |
| Band 6 - SWIR 2 | 1.628 - 1.652 | 500 |
| Band 7 - SWIR 3 | 2.105 - 2.155 | 500 |

The following products (Version 6, see https://lpdaac.usgs.gov/dataset_discovery/modis/modis_products_table) are available for download (Vermote, Roger, & Ray, 2015):

- MOD09GQ: daily reflectance at 250m spatial resolution from Terra MODIS;
- MYD09GQ: daily reflectance at 250m spatial resolution from Aqua MODIS;

- MOD09GA: daily reflectance at 500m spatial resolution from Terra MODIS;
- MYD09GA: daily reflectance at 500m spatial resolution from Aqua MODIS;
- MOD09Q1: reflectance at 250m spatial resolution, which is a composite of MOD09GQ (each pixel contains the best possible observation during an 8-day period);
- MYD09Q1: reflectance at 250m spatial resolution, which is a composite of MYD09GQ (each pixel contains the best possible observation during an 8-day period);
- MOD09A1: reflectance at 250m spatial resolution, which is a composite of MOD09GA (each pixel contains the best possible observation during an 8-day period);
- MYD09A1: reflectance at 250m spatial resolution, which is a composite of MYD09GA (each pixel contains the best possible observation during an 8-day period);

4.2.6 GOES Products

The **Geostationary Operational Environmental Satellite-R Series** (**GOES-R**) are geostationary satellites developed for weather monitoring by the National Oceanic and Atmospheric Administration (NOAA) and the NASA (NOAA, 2020).

GOES constellation is composed of **GOES-R** satellite (also known as GOES-16 that replaced GOES-13 on December 2017), and **GOES-S** satellite (also known as GOES-17, operational since February 2019). Other satellites (GOES-T and GOES-U) are planned to be launched in the future. For more information please visit https://www.goes-r.gov/mission/mission.html .

GOES geostationary satellites monitor continuously the same area, a very large portion of Earth surface with three geographic coverage regions: Full Disk, Continental United States (CONUS), and Mesoscale. In particular, Full Disk products have hemispheric coverage of 83° local zenith angle, and images are acquired every 5-15 minutes. GOES-16 monitors from 75.2 degrees west longitude, including America, the Atlantic Ocean, and the west coast of Africa. GOES-17 monitors from 137.2 degrees west longitude, including the Pacific Ocean.

GOES sensors include several spectral bands.

GOES Bands

| GOES Bands | Central Wavelength [micrometers] | Resolution [meters] |
|------------------------------|----------------------------------|---------------------|
| Band 1 - Blue | 0.47 | 1000 |
| Band 2 - Red | 0.64 | 500 |
| Band 3 - Near Infrared (NIR) | 0.87 | 1000 |
| Band 4 - SWIR - Cirrus | 1.38 | 2000 |
| Band 5 - SWIR | 1.61 | 1000 |
| Band 6 - SWIR | 2.25 | 2000 |

4.3 SAR satellites

Synthetic Aperture Radar (SAR) is a technique of active remote sensing that is the sensor platform emits microwaves in order to acquire images of the ground (Richards and Jia, 2006). In fact, the sensor platform emits the radiation (at a specific wavelength) and measures the magnitude and the phase of radiation that bounces back from the ground to the sensor.

Unlike passive sensors, SAR systems can work day and night and can penetrate clouds allowing for the monitoring of surface also with adverse meteorological conditions; depending on the microwave wavelength, the radiation can penetrate different types of materials allowing for different applications (NASA, 2020).

The main SAR systems can be divided according to the wavelength as illustrated in the following table (NASA, 2020):

| Band | Wavelength [centimeters] | Application |
|------|-----------------------------|---|
| Х | 3.8 - 2.4 | High Resolution SAR, urban monitoring, ice and snow, little penetration into vegetation cover |
| С | 7.5 - 3.8 | global mapping, change detection, ice, low penetration into vegetation cover |
| S | 15 - 7.5 | global mapping, agriculture monitoring, medium penetration into vegetation cover |
| L | 30 - 15 | Medium resolution SAR, biomass and vegetation mapping, high penetration into vegetation cover |

Main SAR Bands

Usually, SAR sensors can emit and measure different polarizations (i.e. orientation of the microwaves of the electric field), for instance vertical (i.e. polarization oriented in the vertical direction in antenna coordinates) and horizontal (i.e. polarization oriented in the horizontal direction in antenna coordinates) (ESA, 2020).

SAR systems can acquire in both ascending and descending orbits, however the acquired images are affected by the different acquisition geometries, which should be considered when mixing ascending and descending images.

Acquisitions are called **swaths** and usually they are composed of sub-swaths. With particular acquisition modes, the resolution of pixels along track (the side parallel to the flight direction) can be different than slant-range (the side perpendicular to the flight direction).

SAR phase information is used to perform interferometry (also InSAR) to measure the distance from the sensor to the target (NASA, 2020).

For more information, please read the ESA introduction to SAR and the NASA definition of SAR.

4.3.1 Sentinel-1 Satellites

Sentinel-1 is a Copernicus mission of satellites that operate at C-band to provide SAR imagery at medium resolution (about 10m).

The Sentinel-1 constellation provides high revisit time (about 5 days), a wide swath (250 km), and acquires images in different operational modes. The primary operation mode on land is the Interferometric Wide swath (IW), which is data is acquired in three swaths using the Terrain Observation with Progressive Scanning SAR (TOPSAR) imaging technique (ESA, 2020b).

The Level-1 products systematically delivered by Copernicus are Single Look Complex (SLC, data comprising complex imagery with amplitude and phase) and **Ground Range Detected** (GRD, Level-1 data with multi-looked intensity only).

Sentinel-1 supports dual polarization, which are horizontal (H) or vertical (V); VV and VH polarimetric channels are available to classify and analyze land cover such as built-up areas or vegetation.

4.4 Land Cover Classification

This chapter provides basic definitions about land cover classifications.

4.4.1 Supervised Classification

A semi-automatic classification (also supervised classification) is an image processing technique that allows for the identification of materials in an image, according to their spectral signatures. There are several kinds of classification algorithms, but the general purpose is to produce a thematic map of the land cover.

Image processing and GIS spatial analyses require specific software such as the Semi-Automatic Classification Plugin for QGIS.




Рис. 3: A multispectral image processed to produce a land cover classification (Landsat image provided by USGS)

4.4.2 Color Composite


Often, a combination is created of three individual monochrome images, in which each is assigned a given color; this is defined **color composite** and is useful for photo interpretation (NASA, 2013). Color composites are usually expressed as:

where:

- R stands for Red;
- G stands for Green;
- B stands for Blue;
- Br is the band number associated to the Red color;
- Bg is the band number associated to the Green color;
- Bb is the band number associated to the Blue color.

The following Figure Color composite of a Landsat 8 image (c. 134) shows a color composite «R G B = 432» of a Landsat 8 image (for Landsat 7 the same color composite is R G B = 321; for Sentinel-2 is R G B = 432) and a color composite «R G B = 543» (for Landsat 7 the same color composite is R G B = 432; for Sentinel-2 is R G B = 843). The composite «R G B = 543» is useful for the interpretation of the image because vegetation pixels appear red (healthy vegetation reflects a large part

of the incident light in the near-infrared wavelength, resulting in higher reflectance values for band 5, thus higher values for the associated color red).



Puc. 4: Color composite of a Landsat 8 image Data available from the U.S. Geological Survey

4.4.3 Training Areas

Usually, supervised classifications require the user to select one or more Regions of Interest (ROIs, also Training Areas) for each land cover class identified in the image. **ROIs** are polygons drawn over homogeneous areas of the image that overlay pixels belonging to the same land cover class.

Region Growing Algorithm

The Region Growing Algorithm allows to select pixels similar to a seed one, considering the **spectral similarity** (i.e. spectral distance) of adjacent pixels. In *SCP* the Region Growing Algorithm is available for the training area creation. The parameter **distance** is related to the similarity of pixel values (the lower the value, the more similar are selected pixels) to the seed one (i.e. selected clicking on a pixel). An additional parameter is the **maximum width**, which is the side length of a square, centred at the seed pixel, which inscribes the training area (if all the pixels had the same value, the training area would be this square). The **minimum size** is used a constraint (for every single band), selecting at least the pixels that are more similar to the seed one until the number of selected pixels equals the minimum size.

In figure *Region growing example* (c. 135) the central pixel is used as seed (image a) for the region growing of one band (image b) with the parameter spectral distance = 0.1; similar pixels are selected to create the training area (image c and image d).




Рис. 5: Region growing example

4.4.4 Classes and Macroclasses

Land cover classes are identified with an arbitrary ID code (i.e. Identifier). *SCP* allows for the definition of **Macroclass ID** (i.e. MC ID) and **Class ID** (i.e. C ID), which are the identification codes of land cover classes. A **Macroclass** is a group of ROIs having different Class ID, which is useful when one needs to classify materials that have different spectral signatures in the same land cover class. For instance, one can identify grass (e.g. ID class = 1 and Macroclass ID = 1) and trees (e.g. ID class = 2 and Macroclass ID = 1) as vegetation class (e.g. Macroclass ID = 1). Multiple Class IDs can be assigned to the same Macroclass ID, but the same Class ID cannot be assigned to multiple Macroclass IDs, as shown in the following table.

Example of Macroclasses

| Macroclass name | Macroclass ID | Class name | Class ID |
|-----------------|---------------|------------|----------|
| Vegetation | 1 | Grass | 1 |
| Vegetation | 1 | Trees | 2 |
| Built-up | 2 | Buildings | 3 |
| Built-up | 2 | Roads | 4 |

Therefore, Classes are subsets of a Macroclass as illustrated in Figure Macroclass example (c. 136).

If the use of Macroclass is not required for the study purpose, then the same Macroclass ID can be defined for all the ROIs (e.g. Macroclass ID = 1) and Macroclass values are ignored in the classification process.




Рис. 6: Macroclass example

4.4.5 Classification Algorithms

The **spectral signatures** (spectral characteristics) of reference land cover classes are calculated considering the values of pixels under each ROI having the same Class ID (or Macroclass ID). Therefore, the classification algorithm classifies the whole image by comparing the spectral characteristics of each pixel to the spectral characteristics of reference land cover classes. *SCP* implements the following classification algorithms.

Minimum Distance

Minimum Distance algorithm calculates the Euclidean distance d(x, y) between spectral signatures of image pixels and training spectral signatures, according to the following equation:

$$d(x,y) = \sqrt{\sum_{i=1}^{n} (x_i - y_i)^2}$$

where:

- x = spectral signature vector of an image pixel;
- y = spectral signature vector of a training area;
- n = number of image bands.

Therefore, the distance is calculated for every pixel in the image, assigning the class of the spectral signature that is closer, according to the following discriminant function (adapted from Richards and Jia, 2006):

$$x \in C_k \iff d(x, y_k) < d(x, y_j) \forall k \neq j$$

where:

- $C_k = \text{land cover class } k;$
- y_k = spectral signature of class k;
- y_j = spectral signature of class j.

It is possible to define a threshold T_i in order to exclude pixels below this value from the classification:

$$\begin{array}{l} x \in C_k \iff d(x,y_k) < d(x,y_j) \forall k \neq j \\ and \\ d(x,y_k) < T_i \end{array}$$

Maximum Likelihood

Maximum Likelihood algorithm calculates the probability distributions for the classes, related to Bayes' theorem, estimating if a pixel belongs to a land cover class. In particular, the probability distributions for the classes are assumed the of form of multivariate normal models (Richards & Jia, 2006). In order to use this algorithm, a sufficient number of pixels is required for each training area allowing for the calculation of the covariance matrix. The discriminant function, described by Richards and Jia (2006), is calculated for every pixel as:

$$g_k(x) = \ln p(C_k) - \frac{1}{2} \ln |\Sigma_k| - \frac{1}{2} (x - y_k)^t \Sigma_k^{-1} (x - y_k)$$

where:

- $C_k = \text{land cover class } k;$
- x = spectral signature vector of a image pixel;
- $p(C_k)$ = probability that the correct class is C_k ;
- $|\Sigma_k|$ = determinant of the covariance matrix of the data in class C_k ;
- $\Sigma_k^{-1} = \text{inverse of the covariance matrix};$
- y_k = spectral signature vector of class k.

Therefore:

$$x \in C_k \iff g_k(x) > g_j(x) \forall k \neq j$$

In addition, it is possible to define a threshold to the discriminant function in order to exclude pixels below this value from the classification. Considering a threshold T_i the classification condition becomes:

$$x \in C_k \iff g_k(x) > g_j(x) \forall k \neq j$$

and
 $g_k(x) > T_i$

Maximum likelihood is one of the most common supervised classifications, however the classification process can be slower than *Minimum Distance* (c. 136).




Рис. 7: Maximum Likelihood example

Spectral Angle Mapping

The Spectral Angle Mapping calculates the spectral angle between spectral signatures of image pixels and training spectral signatures. The spectral angle θ is defined as (Kruse et al., 1993):

$$\theta(x,y) = \cos^{-1}\left(\frac{\sum_{i=1}^{n} x_i y_i}{(\sum_{i=1}^{n} x_i^2)^{\frac{1}{2}} * (\sum_{i=1}^{n} y_i^2)^{\frac{1}{2}}}\right)$$

Where:

- x = spectral signature vector of an image pixel;
- y = spectral signature vector of a training area;
- n = number of image bands.

Therefore a pixel belongs to the class having the lowest angle, that is:

$$x \in C_k \iff \theta(x, y_k) < \theta(x, y_j) \forall k \neq j$$

where:

- $C_k = \text{land cover class } k;$
- y_k = spectral signature of class k;
- y_j = spectral signature of class j.

In order to exclude pixels below this value from the classification it is possible to define a threshold T_i :

$$\begin{aligned} x \in C_k \iff \theta(x,y_k) < \theta(x,y_j) \forall k \neq j \\ and \\ \theta(x,y_k) < T_i \end{aligned}$$

Spectral Angle Mapping is largely used, especially with hyperspectral data.




Рис. 8: Spectral Angle Mapping example

Parallelepiped Classification

Parallelepiped classification is an algorithm that considers a range of values for each band, forming a multidimensional parallelepiped that defines a land cover class. A pixel is classified if the values thereof are inside a parallelepiped. One of the major drawbacks is that pixels whose signatures lie in the overlapping area of two or more parallelepipeds cannot be classified (Richards and Jia, 2006).

Land Cover Signature Classification

This classification allows for the definition of spectral thresholds for each training input signature (a minimum value and a maximum value for each band). The thresholds of each training input signature define a spectral region belonging to a certain land cover class.

Spectral signatures of image pixels are compared to the training spectral signatures; a pixel belongs to class X if pixel spectral signature is completely contained in the spectral region defined by class X. In case of pixels falling inside overlapping regions or outside any spectral region, it is possible to use additional classification algorithms (i.e. *Minimum Distance* (c. 136), *Maximum Likelihood* (c. 137), *Spectral Angle Mapping* (c. 138)) considering the spectral characteristics of the original input signature.

In the following image, a scheme illustrates the Land Cover Signature Classification for a simple case of two spectral bands x and y. User defined spectral regions define three classes $(g_a, g_b, \text{ and } g_c)$. Point p_1 belongs to class g_a and point p_2 belongs to class g_b . However, point p_3 is inside the spectral regions of both classes g_b and g_c (overlapping regions); in this case, point p_3 will be unclassified or classified according to an additional classification algorithm. Point p_4 is outside any spectral region, therefore it will be unclassified or classified according to an additional classification algorithm. Given that point p_4 belongs to class g_c , the spectral region thereof could be extended to include point p_4 .

This is similar to *Parallelepiped Classification* (c. 139), with the exception that spectral regions are defined by user, and can be assigned independently for the upper and lower bounds. One can imagine spectral regions as the set of all the spectral signatures of pixels belonging to one class.

In figure *Plot of spectral ranges* (c. 141) the spectral ranges of three classes $(g_a, g_b, \text{ and } g_c)$ are displayed;




Рис. 9: Land cover signature classification

the colored lines inside the ranges (i.e. semi-transparent area) represent the spectral signatures of pixels that defined the upper and lower bounds of the respective ranges. Pixel p_1 (dotted line) belongs to class g_b because the spectral signature thereof is completely inside the range of class g_b (in the upper limit); pixel p_2 (dashed line) is unclassified because the spectral signature does not fall completely inside any range; pixel p_3 (dotted line) belongs to class g_a .

It is worth noticing that these spectral thresholds can be applied to any spectral signature, regardless of spectral characteristics thereof; this function can be very useful for separating similar spectral signatures that differ only in one band, defining thresholds that include or exclude specific signatures. In fact, classes are correctly separated if the spectral ranges thereof are not overlapping at least in one band. Of course, even if spectral regions are overlapping, chances are that no pixel will fall inside the overlapping region and be misclassified; which is the upper (or lower) bound of a range do not imply the existence, in the image, of any spectral signature having the maximum (or minimum) range values for all the bands (for instance pixel p_1 of figure *Plot of spectral ranges* (c. 141) could not exist).

One of the main benefit of the *Land Cover Signature Classification* is that it is possible to select pixels and and include the signature thereof in a spectral range; therefore, the classification should be the direct representation of the class expected for every spectral signature. This is very suitable for the classification of a single land cover class (defined by specific spectral thresholds), and leave unclassified the rest of the image that is of no interest for the purpose of the classification.




Рис. 10: Plot of spectral ranges

Algorithm raster

An algorithm raster represents the «distance» (according to the definition of the classification algorithm) of an image pixel to a specific spectral signature.

In general, an algorithm raster is produced for every spectral signature used as training input. The value of every pixel is the result of the algorithm calculation for a specific spectral signature. Therefore, a pixel belongs to class X if the value of the algorithm raster corresponding to class X is the lowest in case of *Minimum Distance* (c. 136) or *Spectral Angle Mapping* (c. 138) (or highest in case of *Maximum Likelihood* (c. 137)).

Given a classification, a combination of algorithm rasters can be produced, in order to create a raster with the lowest «distances» (i.e. pixels have the value of the algorithm raster corresponding to the class they belong in the classification). Therefore, this raster can be useful to identify pixels that require the collection of more similar spectral signatures (see *Classification preview* (c. 44)).

4.4.6 Machine Learning

Machine Learning is a broad set of classification techniques that aim to build mathematical models based on training data.

In general, Machine Learning algorithms split the data in (ESA, 2019):

- Training Dataset: the sample data used to fit the model;
- Validation Dataset: the sample data used to tune the model parameters to fit on the training dataset;
- Test Dataset: the sample data used to provide an evaluation of the final model;

Usually, the training and model evaluation are performed iteratively.

Random Forest

Random Forest is a particular machine learning technique, based on the iterative and random creation of decision trees (i.e. a set of rules and conditions that define a class).

First, the input features should be defined, which can be spectral bands or ancillary rasters. *Training Areas* (c. 134) should be created to define the classes used for training the model.

Random Forest calculates several random decision trees, based on the following parameters:

- number of training samples: is the number of training data (pixels) randomly used to train the model; it should be set lower than total training input pixels;
- number of trees: is the number of decision trees; the more the number of trees, the more is the model accuracy, but it also increases the calculation time.

For instance, a decision tree could be defined as:

- class 1 = band 1 > 0.1 -> band 2 < 0.3 -> band 3 > 0.4
- class 2 = band 1 > 0.4 -> band 2 > 0.6 -> band 3 < 0.1
- class 3 = band 1 < 0.7 -> band 2 > 0.1 -> band 3 < 0.5

Random Forest creates several decision trees randomly. Usually, the Gini coefficient is calculated to split the trees. Therefore, a model based on the decision trees is created and used to classify all the pixels.

A pixel is classified according to the majority vote of decision trees, for example a pixel is classified as class 1 if most decision trees evaluated it as class 1. Also, a confidence layer is produced, which measures the uncertainty of the model based on training data.

Random Forest can be used to evaluate the importance of input features, according to the contribution thereof to the model.

Multi-Layer Perceptron

Multi-Layer Perceptron is a supervised classification algorithm that is based on the definition of an artificial neural network. A Multi-Layer Perceptron is made of an input layer, one or more hidden layers (made of a defined number of neurons that are fully connected by non-linear activation functions), and the output layer (also read this documentation

Several parameters can be defined as described here

Support Vector Machine

Support Vector Machine is a supervised classification algorithm that is based on the calculation of hyperplanes in order to separate input data values.

Several parameters can be defined as described at this link

4.4.7 Spectral Distance

It is useful to evaluate the spectral distance (or separability) between training signatures or pixels, in order to assess if different classes that are too similar could cause classification errors. The *SCP* implements the following algorithms for assessing similarity of spectral signatures.

Jeffries-Matusita Distance

Jeffries-Matusita Distance calculates the separability of a pair of probability distributions. This can be particularly meaningful for evaluating the results of *Maximum Likelihood* (c. 137) classifications.

The Jeffries-Matusita Distance J_{xy} is calculated as (Richards and Jia, 2006):

$$J_{xy} = 2\left(1 - e^{-B}\right)$$

where:

$$B = \frac{1}{8}(x-y)^t \left(\frac{\Sigma_x + \Sigma_y}{2}\right)^{-1} (x-y) + \frac{1}{2} \ln \left(\frac{\left|\frac{\Sigma_x + \Sigma_y}{2}\right|}{\left|\sum_x\right|^{\frac{1}{2}} |\Sigma_y|^{\frac{1}{2}}}\right)$$

where:

- x =first spectral signature vector;
- y = second spectral signature vector;
- Σ_x = covariance matrix of sample x;
- Σ_y = covariance matrix of sample y;

The Jeffries-Matusita Distance is asymptotic to 2 when signatures are completely different, and tends to 0 when signatures are identical.

Spectral Angle

The Spectral Angle is the most appropriate for assessing the *Spectral Angle Mapping* (c. 138) algorithm. The spectral angle θ is defined as (Kruse et al., 1993):

$$\theta(x,y) = \cos^{-1}\left(\frac{\sum_{i=1}^{n} x_i y_i}{\left(\sum_{i=1}^{n} x_i^2\right)^{\frac{1}{2}} * \left(\sum_{i=1}^{n} y_i^2\right)^{\frac{1}{2}}}\right)$$

Where:

- x = spectral signature vector of an image pixel;
- y = spectral signature vector of a training area;
- n = number of image bands.

Spectral angle goes from 0 when signatures are identical to 90 when signatures are completely different.

Euclidean Distance

The Euclidean Distance is particularly useful for the evaluating the result of *Minimum Distance* (c. 136) classifications. In fact, the distance is defined as:

$$d(x, y) = \sqrt{\sum_{i=1}^{n} (x_i - y_i)^2}$$

where:

- x =first spectral signature vector;
- y = second spectral signature vector;
- n = number of image bands.

The Euclidean Distance is 0 when signatures are identical and tends to increase according to the spectral distance of signatures.

Bray-Curtis Similarity

The Bray-Curtis Similarity is a statistic used for assessing the relationship between two samples (read this). It is useful in general for assessing the similarity of spectral signatures, and Bray-Curtis Similarity S(x, y) is calculated as:

$$S(x,y) = 100 - \left(\frac{\sum_{i=1}^{n} |(x_i - y_i)|}{\sum_{i=1}^{n} x_i + \sum_{i=1}^{n} y_i}\right) * 100$$

where:

- x =first spectral signature vector;
- y = second spectral signature vector;
- n = number of image bands.

The Bray-Curtis similarity is calculated as percentage and ranges from 0 when signatures are completely different to 100 when spectral signatures are identical.

4.4.8 Classification Result

The result of the classification process is a raster (see an example of Landsat classification in Figure *Landsat classification* (c. 144)), where pixel values correspond to class IDs and each color represent a land cover class.




Рис. 11: Landsat classification Data available from the U.S. Geological Survey

A certain amount of errors can occur in the land cover classification (i.e. pixels assigned to a wrong land cover class), due to spectral similarity of classes, or wrong class definition during the ROI collection.

4.4.9 Accuracy Assessment

After the classification process, it is useful to assess the accuracy of land cover classification, in order to identify and measure map errors. Usually, **accuracy assessment** is performed with the calculation of an error matrix, which is a table that compares map information with reference data (i.e. ground truth data) for a number of sample areas (Congalton and Green, 2009).

The following table is a scheme of error matrix, where k is the number of classes identified in the land cover classification, and n is the total number of collected sample units. The items in the major diagonal (aii) are the number of samples correctly identified, while the other items are classification error.

Scheme of Error Matrix

| | Ground truth 1 | Ground truth 2 | | Ground truth k | Total |
|---------|----------------|----------------|-------|----------------|----------|
| Class 1 | a_{11} | a_{12} | | a_{1k} | a_{1+} |
| Class 2 | a_{21} | a_{22} | | a_{2k} | a_{2+} |
| | | | | | |
| Class k | a_{k1} | a_{k2} | • • • | a_{kk} | a_{k+} |
| Total | a_{+1} | a_{+2} | | a_{+k} | n |

Therefore, it is possible to calculate the overall accuracy as the ratio between the number of samples that are correctly classified (the sum of the major diagonal), and the total number of sample units n (Congalton and Green, 2009).

The overall accuracy (also expressed in percentage) is defined as:

$$O = \sum_{i=1}^{k} a_{ii}/n$$

The user's accuracy for each class is defined as the ratio (also expressed in percentage) between correct samples and the row total:

$$U_i = a_{ii}/a_{i+}$$

The commission error $CE_i = 1 - U_i$ corresponds to pixels classified as class *i* that actually belong to a different class.

The producer's accuracy for each class is calculated as the ratio (also expressed in percentage) between correct samples and the column total:

$$P_i = a_{ii}/a_{+i}$$

The omission error $OE_i = 1 - P_i$ corresponds to pixels actually belonging to class *i* that were classified erroneously as a different class.

It is recommended to calculate the area based error matrix (Olofsson et al., 2014) where each element represents the estimated area proportion of each class. This allows for estimating the unbiased user's accuracy and producer's accuracy, the unbiased area of classes according to reference data, and the standard error of area estimates.

For further information, the following documentation is freely available: Landsat Data Users Handbook.

4.5 Image processing

Remote sensing images can be processed in various ways in order to obtain classification, indices, or other derived information that can be useful for land cover characterization.

4.5.1 Principal Component Analysis

Principal Component Analysis (PCA) is a method for reducing the dimensions of measured variables (bands) to the principal components (JARS, 1993).

Th principal component transformation provides a new set of bands (principal components) having the following characteristic: principal components are uncorrelated; each component has variance less than the previous component. Therefore, this is an efficient method for extracting information and data compression (Ready and Wintz, 1973).

Given an image with N spectral bands, the principal components are obtained by matrix calculation (Ready and Wintz, 1973; Richards and Jia, 2006):

$$Y = D^t X$$

where:

- Y = vector of principal components
- $D = \text{matrix of eigenvectors of the covariance matrix } C_x \text{ in X space}$
- t denotes vector transpose

And X is calculated as:

$$X = P - M$$

- P = vector of spectral values associated with each pixel
- M = vector of the mean associated with each band

Thus, the mean of X associated with each band is 0. D is formed by the eigenvectors (of the covariance matrix C_x) ordered as the eigenvalues from maximum to minimum, in order to have the maximum variance in the first component. This way, the principal components are uncorrelated and each component has variance less than the previous component(Ready and Wintz, 1973).

Usually the first two components contain more than the 90% of the variance. For example, the first principal components can be displayed in a *Color Composite* (c. 133) for highlighting *Land Cover* (c. 127) classes, or used as input for *Supervised Classification* (c. 133).

4.5.2 Pan-sharpening

Pan-sharpening is the combination of the spectral information of multispectral bands (MS), which have lower spatial resolution (for Landsat bands, spatial resolution is 30m), with the spatial resolution of a panchromatic band (PAN), which for Landsat 7 and 8 it is 15m. The result is a multispectral image with the spatial resolution of the panchromatic band (e.g. 15m). In *SCP*, a Brovey Transform is applied, where the pan-sharpened values of each multispectral band are calculated as (Johnson, Tateishi and Hoan, 2012):

$$MSpan = MS * PAN/I$$

where I is Intensity, which is a function of multispectral bands.

The following weights for I are defined, basing on several tests performed using the *SCP*. For Landsat 8, Intensity is calculated as:

I = (0.42 * Blue + 0.98 * Green + 0.6 * Red)/2

For Landsat 7, Intensity is calculated as:

$$I = (0.42 * Blue + 0.98 * Green + 0.6 * Red + NIR)/3$$



Рис. 12: Example of pan-sharpening of a Landsat 8 image. Left, original multispectral bands (30m); right, pan-sharpened bands (15m)

Data available from the U.S. Geological Survey

4.5.3 Spectral Indices

Spectral indices are operations between spectral bands that are useful for extracting information such as vegetation cover (JARS, 1993). One of the most popular spectral indices is the **Normalized Difference Vegetation Index** (NDVI), defined as (JARS, 1993):

$$NDVI = (NIR - Red)/(NIR + Red)$$

NDVI values range from -1 to 1. Dense and healthy vegetation show higher values, while non-vegetated areas show low NDVI values.

Another index is the **Enhanced Vegetation Index** (EVI) which attempts to account for atmospheric effects such as path radiance calculating the difference between the blue and the red bands (Didan, et al., 2015). EVI is defined as:

$$EVI = G(NIR - Red)/(NIR + C_1Red - C_2Blue + L)$$

where: G is a scaling factor, C_1 and C_2 are coefficients for the atmospheric effects, and L is a factor for accounting the differential NIR and Red radiant transfer through the canopy. Typical coefficient values are: G = 2.5, L = 1, $C_1 = 6$, $C_2 = 7.5$ (Didan, et al., 2015).

4.5.4 Clustering

Clustering is the grouping of pixels based on spectral similarity (e.g. *Euclidean Distance* (c. 143) or *Spectral Angle* (c. 143)) calculated for a multispectral image (Richards and Jia, 2006).

Clustering can be used for unsupervised classification or for the automatic selection of spectral signatures. It is worth noticing that, while *Supervised Classification* (c. 133) produces a classification whit the classes identified during the training process, the classes produced by clustering (i.e. clusters) have no definition and consequently the user must assign a land cover label to each class.

The main advantage of clustering resides in automation. Of course, clusters do not necessarily represent a particular land cover type and additional processing could be required for producing an accurate classification.

There are several types of clustering, mainly based on iterative methods; the following are the algorithms provided in *SCP*.

K-means

The K-means method is based on the calculation of the average spectral signature of clusters (Wikipedia, 2017; JARS, 1993).

At first, the user defines the number of clusters expected in the image, which correspond to as many spectral signatures (i.e. seeds). Starting spectral signatures can be selected in various ways (e.g. randomly, provided by the user, calculated automatically from image values).

During the first iteration clusters are produced calculating the pixel spectral distance with initial spectral signatures. The algorithms *Euclidean Distance* (c. 143) or *Spectral Angle* (c. 143) can be used for distance calculation. Pixels are assigned according to the most similar spectral signature, therefore producing clusters.

Then, the average spectral signature is calculated for each cluster of pixels, resulting in the spectral signatures that will be used in the following iteration.

This process continues iteratively producing clusters and mean spectral signatures, until one of the following condition is verified:

- the spectral distance between the spectral signatures produced in this iteration with the corresponding ones produced in the previous iteration is lower than a certain threshold;
- the maximum number of iterations is reached.

After the last iteration, a raster of clusters is produced using the spectral signatures derived from the last iteration.

ISODATA

The ISODATA (Iterative Self-Organizing Data Analysis Technique) method is similar to K-means but with the additional steps of merging clusters having similar spectral signatures and splitting clusters having too high variability (i.e. standard deviation) of spectral signatures (Ball & Hall, 1965). Following, the *SCP* implementation of ISODATA is described.

At first, the user defines the number of clusters expected in the image, which correspond to as many spectral signatures (i.e. seeds). Starting spectral signatures can be selected in various ways (e.g. randomly, provided by the user, calculated automatically from image values). Initial parameters provided by user are:

- C = number of desired clusters
- N_{min} = minimum number of pixels for a cluster
- σ_t = maximum standard deviation threshold for splitting
- D_t = distance threshold for merging

During the first iteration clusters are produced calculating the *Euclidean Distance* (c. 143) of pixels with initial spectral signatures. Pixels are assigned according to the most similar spectral signature, therefore producing clusters.

Therefore, the following parameters are calculated:

- N_i = number of pixels of cluster i
- S_i = average spectral signature of cluster i
- $AVERAGEDIST_i$ = average distance of cluster *i* with the seed spectral signature
- AVERAGEDISTANCE = overall average distance of all clusters
- σ_{ij} = standard deviation of cluster *i* in band *j*
- $\sigma max_i = \text{maximum standard deviation of cluster } i \text{ (i.e. } max(\sigma_{ij}))$
- $k_i = \text{band}$ where σmax_i occurred
- Sk_i = value of S_i at band k_i
- P = number of clusters

Then, for each cluster i, if $N_i < N_{min}$, then the cluster i is discarded.

If $P \le C$ then try to split clusters. For each cluster *i*:

- If $\sigma max_i > \sigma_t$:
 - If $((AVERAGEDIST_i > AVERAGEDISTANCE)$ AND $(N_i > (2 * N_{min} + 2)))$ OR (C > 2 * P):
 - * create a new spectral signature $S_{p+1} = S_i$
 - * in S_i set the value $Sk_i = Sk_i + \sigma max_i$
 - * in S_{p+1} set the value $Sk_{p+1} = Sk_i \sigma max_i$
 - $* \ P = P + 1$
 - * start a new iteration

If P > (2 * C) then try to merge clusters.

- For each combination xy of spectral signatures calculate $D_{xy} = Euclidean Distance$ (c. 143) of spectral signatures S_x and S_y .
- If the minimum D_{xy} is greater than D_t :
 - $-S_{i} = (N_{i} * S_{i} + N_{j} * S_{j})/(N_{i} + N_{j})$
 - discard S_{j}
 - -P = P 1
 - start a new iteration

After the last iteration, a raster of clusters is produced using the spectral signatures derived from the last iteration. The number of clusters can vary according to the processes of splitting and merging.

4.6 Image conversion to reflectance

This chapter provides information about the conversion to reflectance implemented in SCP.

4.6.1 Radiance at the Sensor's Aperture

Radiance is the «flux of energy (primarily irradiant or incident energy) per solid angle leaving a unit surface area in a given direction», «Radiance is what is measured at the sensor and is somewhat dependent on reflectance» (NASA, 2011, p. 47).

Images such as Landsat or Sentinel-2 are composed of several bands and a metadata file which contains information required for the conversion to reflectance.

Landsat images are provided in radiance, scaled prior to output. For Landsat images **Spectral Radiance** at the sensor's aperture $(L_{\lambda}, \text{ measured in [watts/(meter squared * ster * <math>\mu m)]})$ is given by (https://www.usgs.gov/core-science-systems/nli/landsat/using-usgs-landsat-level-1-data-product):

$$L_{\lambda} = M_L * Q_{cal} + A_L$$

where:

- M_L = Band-specific multiplicative rescaling factor from Landsat metadata (RADIANCE_MULT_BAND_x, where x is the band number)
- A_L = Band-specific additive rescaling factor from Landsat metadata (RADIANCE_ADD_BAND_x, where x is the band number)
- $Q_{cal} =$ Quantized and calibrated standard product pixel values (DN)

Sentinel-2 images (Level-1C) are already provided in *Top Of Atmosphere (TOA) Reflectance* (c. 150), scaled prior to output (ESA, 2015).

4.6.2 Top Of Atmosphere (TOA) Reflectance

Images in radiance can be converted to Top Of Atmosphere (TOA) Reflectance (combined surface and atmospheric reflectance) in order to reduce the in between-scene variability through a normalization for solar irradiance. This TOA reflectance (ρ_p), which is the unitless ratio of reflected versus total power energy (NASA, 2011), is calculated by:

$$\rho_p = (\pi * L_\lambda * d^2) / (ESUN_\lambda * \cos\theta_s)$$

where:

- L_{λ} = Spectral radiance at the sensor's aperture (at-satellite radiance)
- $d = \text{Earth-Sun distance in astronomical units (provided with Landsat 8 metadata file, and an excel file is available from http://landsathandbook.gsfc.nasa.gov/excel_docs/d.xls)$
- $ESUN_{\lambda}$ = Mean solar exo-atmospheric irradiances
- θ_s = Solar zenith angle in degrees, which is equal to θ_s = 90° θ_e where θ_e is the Sun elevation

It is worth pointing out that Landsat 8 images are provided with band-specific rescaling factors that allow for the direct conversion from DN to TOA reflectance.

Sentinel-2 images are already provided in scaled TOA reflectance, which can be converted to TOA reflectance with a simple calculation using the Quantification Value provided in the metadata (see https://sentinel.esa.int/documents/247904/349490/S2 MSI Product Specification.pdf).

Sentinel-3 images are already provided in scaled TOA radiance. Conversion to reflectance is performed applying the coefficients scale_factor and add_offset provided in the metadata of each band. The ancillary raster tie_geometries.nc provides the value of sun zenith angle and the ancillary raster instrument_data provides information about the solar flux for each band, which are used for the

conversion to reflectance with the correction for sun angle. In addition, the georeferencing of the bands is performed using the ancillary raster geo_coordinates.nc which provides coordinates of every pixel.

4.6.3 Surface Reflectance

The effects of the atmosphere (i.e. a disturbance on the reflectance that varies with the wavelength) should be considered in order to measure the reflectance at the ground.

As described by Moran et al. (1992), the land surface reflectance (ρ) is:

$$\rho = [\pi * (L_{\lambda} - L_p) * d^2] / [T_v * ((ESUN_{\lambda} * \cos\theta_s * T_z) + E_{down})]$$

where:

- L_p is the path radiance
- T_v is the atmospheric transmittance in the viewing direction
- T_z is the atmospheric transmittance in the illumination direction
- E_{down} is the downwelling diffuse irradiance

Therefore, we need several atmospheric measurements in order to calculate ρ (physically-based corrections). Alternatively, it is possible to use **image-based techniques** for the calculation of these parameters, without in-situ measurements during image acquisition. It is worth mentioning that **Landsat Surface Reflectance High Level Data Products** for Landsat 8 are available (for more information read http://landsat.usgs.gov/CDR_LSR.php).

4.6.4 DOS1 Correction

The **Dark Object Subtraction** (DOS) is a family of image-based atmospheric corrections. Chavez (1996) explains that «the basic assumption is that within the image some pixels are in complete shadow and their radiances received at the satellite are due to atmospheric scattering (path radiance). This assumption is combined with the fact that very few targets on the Earth's surface are absolute black, so an assumed one-percent minimum reflectance is better than zero percent". It is worth pointing out that the accuracy of image-based techniques is generally lower than physically-based corrections, but they are very useful when no atmospheric measurements are available as they can improve the estimation of land surface reflectance. The **path radiance** is given by (Sobrino et al., 2004):

$$L_p = L_{min} - L_{DO1\%}$$

where:

- $L_{min} =$ «radiance that corresponds to a digital count value for which the sum of all the pixels with digital counts lower or equal to this value is equal to the 0.01% of all the pixels from the image considered" (Sobrino et al., 2004, p. 437), therefore the radiance obtained with that digital count value (DN_{min})
- $L_{DO1\%}$ = radiance of Dark Object, assumed to have a reflectance value of 0.01

In particular for Landsat images:

$$L_{min} = M_L * DN_{min} + A_L$$

Sentinel-2 images are converted to radiance prior to DOS1 calculation.

The radiance of Dark Object is given by (Sobrino et al., 2004):

$$L_{DO1\%} = 0.01 * [(ESUN_{\lambda} * cos\theta_s * T_z) + E_{down}] * T_v / (\pi * d^2)$$

Therefore the **path radiance** is:

 $L_{p} = M_{L} * DN_{min} + A_{L} - 0.01 * [(ESUN_{\lambda} * \cos\theta_{s} * T_{z}) + E_{down}] * T_{v} / (\pi * d^{2})$

There are several DOS techniques (e.g. DOS1, DOS2, DOS3, DOS4), based on different assumption about T_v , T_z , and E_{down} . The simplest technique is the **DOS1**, where the following assumptions are made (Moran et al., 1992):

- $T_v = 1$
- $T_z = 1$
- $E_{down} = 0$

Therefore the **path radiance** is:

$$L_p = M_L * DN_{min} + A_L - 0.01 * ESUN_\lambda * \cos\theta_s / (\pi * d^2)$$

And the resulting **land surface reflectance** is given by:

$$\rho = [\pi * (L_{\lambda} - L_p) * d^2] / (ESUN_{\lambda} * \cos\theta_s)$$

ESUN [W /(m2 * μm)] values for Landsat sensors are provided in the following table.

ESUN values for Landsat bands

| Band | Landsat MSS* | 1 | Landsat MSS* | 2 | Landsat MSS* | 3 | Landsat TM* | 4 | Landsat TM* | 5 | Landsat ETM+** | 7 |
|------|-----------------|---|-----------------|---|-----------------|---|----------------|---|----------------|---|-------------------|---|
| 1 | | | | | | | 1983 | | 1983 | | 1970 | |
| 2 | | | | | | | 1795 | | 1796 | | 1842 | |
| 3 | | | | | | | 1539 | | 1536 | | 1547 | |
| 4 | 1823 | | 1829 | | 1839 | | 1028 | | 1031 | | 1044 | |
| 5 | 1559 | | 1539 | | 1555 | | 219.8 | | 220 | | 225.7 | |
| 6 | 1276 | | 1268 | | 1291 | | | | | | | |
| 7 | 880.1 | | 886.6 | | 887.9 | | 83.49 | | 83.44 | | 82.06 | |
| 8 | | | | | | | | | | | 1369 | |

* from Chander, Markham, & Helder (2009)

** from http://landsathandbook.gsfc.nasa.gov/data_prod/prog_sect11_3.html

For Landsat 8, ESUN can be calculated as (from http://grass.osgeo.org/grass65/manuals/i.landsat. toar.html):

$$ESUN = (\pi * d^2) * RADIANCE MAXIMUM/REFLECTANCE MAXIMUM$$

where RADIANCE_MAXIMUM and REFLECTANCE_MAXIMUM are provided by image metadata. ESUN [W /(m2 * μm)] values for **Sentinel-2** sensor (provided in image metadata) are illustrated in the following table.

ESUN values for Sentinel-2 bands

| Band | Sentinel-2 |
|------|------------|
| 1 | 1913.57 |
| 2 | 1941.63 |
| 3 | 1822.61 |
| 4 | 1512.79 |
| 5 | 1425.56 |
| 6 | 1288.32 |
| 7 | 1163.19 |
| 8 | 1036.39 |
| 8A | 955.19 |
| 9 | 813.04 |
| 10 | 367.15 |
| 11 | 245.59 |
| 12 | 85.25 |

ESUN [W /(m2 * $\mu m)]$ values for ASTER sensor are illustrated in the following table (from Finn et al., 2012).

ESUN values for ASTER bands

| Band | ASTER |
|------|-------|
| 1 | 1848 |
| 2 | 1549 |
| 3 | 1114 |
| 4 | 225.4 |
| 5 | 86.63 |
| 6 | 81.85 |
| 7 | 74.85 |
| 8 | 66.49 |
| 9 | 59.85 |

An example of comparison of to TOA reflectance, DOS1 corrected reflectance and the Landsat Surface Reflectance High Level Data Products (ground truth) is provided in Figure *Spectral signatures of a built-up pixel* (c. 153).




Рис. 13: Spectral signatures of a built-up pixel

Comparison of TOA reflectance, DOS1 corrected reflectance and Landsat Surface Reflectance High Level Data Products

4.7 Conversion to Temperature

This chapter provides the basic information about the conversion to At-Satellite Brightness Temperature implemented in *SCP* and the estimation of Land Surface Temperature.

4.7.1 Conversion to At-Satellite Brightness Temperature

For thermal bands, the conversion of DN to At-Satellite Brightness Temperature is given by (from https://www.usgs.gov/core-science-systems/nli/landsat/using-usgs-landsat-level-1-data-product):

$$T_B = K_2/ln[(K_1/L_\lambda) + 1]$$

where:

- $K_1 =$ Band-specific thermal conversion constant (in watts/meter squared * ster * μm)
- $K_2 =$ Band-specific thermal conversion constant (in kelvin)

and L_{λ} is the Spectral Radiance at the sensor's aperture, measured in watts/(meter squared * ster * μm).

The K_1 and K_2 constants for Landsat sensors are provided in the following table.

Thermal Conversion Constants for Landsat

| Constant | Landsat 4* | Landsat 5* | Landsat 7** |
|----------|------------|------------|-------------|
| K_1 | 671.62 | 607.76 | 666.09 |
| K_2 | 1284.30 | 1260.56 | 1282.71 |

* from Chander & Markham (2003)

** from NASA (2011)

For Landsat 8, the K_1 and K_2 values are provided in the image metadata file.

 K_1 and K_2 are calculated as (Jimenez-Munoz & Sobrino, 2010):

$$K_1 = c_1 / \lambda^5$$

$$K_2 = c_2/\lambda$$

where (Mohr, Newell, & Taylor, 2015):

- $c_1 = \text{first radiation constant} = 1.191 * 10^{-16} W m^2 s r^{-1}$
- $c_2 = \text{second radiation constant} = 1.4388 * 10^{-2} mK$

Therefore, for ASTER bands K_1 and K_2 are provided in the following table.

Thermal Conversion Constants for ASTER

| Constant | Band 10 | Band 11 | Band 12 | Band 13 | Band 14 |
|----------|----------------|----------------|----------------|----------------|----------------|
| K_1 | $3.024 * 10^3$ | $2.460 * 10^3$ | $1.909 * 10^3$ | $8.900 * 10^2$ | $6.464 * 10^2$ |
| K_2 | $1.733 * 10^3$ | $1.663 * 10^3$ | $1.581 * 10^3$ | $1.357 * 10^3$ | $1.273 * 10^3$ |

4.7.2 Estimation of Land Surface Temperature

Several studies have described the estimation of Land Surface Temperature. Land Surface Temperature can be calculated from At-Satellite Brightness Temperature T_B as (Weng et al., 2004):

$$T = T_B / [1 + (\lambda * T_B / c_2) * ln(e)]$$

where:

- λ = wavelength of emitted radiance
- $c_2 = h * c/s = 1.4388 * 10^{-2} \text{ m K}$
- $h = \text{Planck's constant} = 6.626 * 10^{-34} \text{ J s}$
- $s = \text{Boltzmann constant} = 1.38 * 10^{-23} \text{ J/K}$
- c = velocity of light = $2.998 * 10^8 \text{ m/s}$

The values of λ for the thermal bands of Landsat and ASTER satellites can be calculated from the tables in *Landsat Satellites* (c. 127) and *ASTER Satellite* (c. 130).

Several studies used NDVI for the estimation of land surface emissivity (Sobrino et al., 2004); other studies used a land cover classification for the definition of the land surface emissivity of each class (Weng et al. 2004). For instance, the emissivity (e) values of various land cover types are provided in the following table (from Mallick et al., 2012).

Emissivity values

| Land surface | Emissivity e |
|--------------|--------------|
| Soil | 0.928 |
| Grass | 0.982 |
| Asphalt | 0.942 |
| Concrete | 0.937 |

4.8 References

- Ball, G. H. & Hall, D. J., 1965. ISODATA. A novel method of data analysis and pattern classification. Menlo Park: Stanford Research Institute.
- Chander, G. & Markham, B., 2003. Revised Landsat-5 TM radiometric calibration procedures and postcalibration dynamic ranges Geoscience and Remote Sensing, IEEE Transactions on, 41, 2674 - 2677
- Chavez, P. S., 1996. Image-Based Atmospheric Corrections Revisited and Improved Photogrammetric Engineering and Remote Sensing, [Falls Church, Va.] American Society of Photogrammetry, 62, 1025-1036
- Congalton, R. and Green, K., 2009. Assessing the Accuracy of Remotely Sensed Data: Principles and Practices. Boca Raton, FL: CRC Press
- Didan, K.; Barreto Munoz, A.; Solano, R. & Huete, A., 2015. MODIS Vegetation Index User's Guide. Collection 6, NASA
- ESA, 2020. Sentinel-1 SAR Definitions. Available at https://sentinel.esa.int/web/sentinel/user-guides/sentinel-1-sar/definitions
- ESA, 2020b. Sentinel-1 SAR Definitions. Available at https://sentinel.esa.int/web/sentinel/user-guides/sentinel-1-sar/overview

- ESA, 2019. A machine learning glossary. Available at https://blogs.esa.int/philab/2019/03/29/a-machine-learning-glossary/
- ESA, 2015. Sentinel-2 User Handbook. Available at https://sentinels.copernicus.eu/documents/ 247904/685211/Sentinel-2_User_Handbook
- ESA, 2013. Sentinel-3 User Handbook. Available at https://sentinels.copernicus.eu/documents/247904/685236/Sentinel-3 User Handbook
- Finn, M.P., Reed, M.D, and Yamamoto, K.H., 2012. A Straight Forward Guide for Processing Radiance and Reflectance for EO-1 ALI, Landsat 5 TM, Landsat 7 ETM+, and ASTER. Unpublished Report from USGS/Center of Excellence for Geospatial Information Science, 8 p, http://cegis.usgs.gov/soil_moisture/pdf/A%20Straight%20Forward%20guide%20for% 20Processing%20Radiance%20and%20Reflectance V 24Jul12.pdf
- Fisher, P. F. and Unwin, D. J., eds., 2005. Representing GIS. Chichester, England: John Wiley & Sons
- JARS, 1993. Remote Sensing Note. Japan Association on Remote Sensing. Available at http://www.jars1974.net/pdf/rsnote e.html
- Jimenez-Munoz, J. C. & Sobrino, J. A., 2010. A Single-Channel Algorithm for Land-Surface Temperature Retrieval From ASTER Data IEEE Geoscience and Remote Sensing Letters, 7, 176-179
- Johnson, B. A., Tateishi, R. and Hoan, N. T., 2012. Satellite Image Pansharpening Using a Hybrid Approach for Object-Based Image Analysis ISPRS International Journal of Geo-Information, 1, 228. Available at http://www.mdpi.com/2220-9964/1/3/228)
- Kruse, F. A., et al., 1993. The Spectral Image Processing System (SIPS) Interactive Visualization and Analysis of Imaging spectrometer. Data Remote Sensing of Environment
- Mallick, J.; Singh, C. K.; Shashtri, S.; Rahman, A. & Mukherjee, S., 2012. Land surface emissivity retrieval based on moisture index from LANDSAT TM satellite data over heterogeneous surfaces of Delhi city International Journal of Applied Earth Observation and Geoinformation, 19, 348 -358
- Mohr, P. J.; Newell, D. B. & Taylor, B. N., 2015. CODATA Recommended Values of the Fundamental Physical Constants: 2014 National Institute of Standards and Technology, Committee on Data for Science and Technology
- Moran, M.; Jackson, R.; Slater, P. & Teillet, P., 1992. Evaluation of simplified procedures for retrieval of land surface reflectance factors from satellite sensor output Remote Sensing of Environment, 41, 169-184
- NASA, 2020. What is Synthetic Aperture Radar?. Available at https://earthdata.nasa.gov/learn/what-is-sar
- NASA, 2013. Landsat 7 Science Data User's Handbook. Available at https://www.usgs.gov/land-resources/nli/landsat/landsat-7-data-users-handbook
- NASA, 2011. Landsat 7 Science Data Users Handbook Landsat Project Science Office at NASA's Goddard Space Flight Center in Greenbelt, 186 http://landsathandbook.gsfc.nasa.gov/pdfs/Landsat7_Handbook.pdf
- NOAA, 2020. GOES-R Series. Available at https://www.ncdc.noaa.gov/data-access/satellite-data/goes-r-series-satellites
- Olofsson, P.; Foody, G. M.; Herold, M.; Stehman, S. V.; Woodcock, C. E. & Wulder, M. A., 2014. Good practices for estimating area and assessing accuracy of land change. Remote Sensing of Environment, 148, 42 – 57
- Ready, P. and Wintz, P., 1973. Information Extraction, SNR Improvement, and Data Compression in Multispectral Imagery. IEEE Transactions on Communications, 21, 1123-1131
- Richards, J. A. and Jia, X., 2006. Remote Sensing Digital Image Analysis: An Introduction. Berlin, Germany: Springer

- Sobrino, J.; Jiménez-Muñoz, J. C. & Paolini, L., 2004. Land surface temperature retrieval from LANDSAT TM 5 Remote Sensing of Environment, Elsevier, 90, 434-440
- USGS, 2015. Advanced Spaceborne Thermal Emission and Reflection Radiometer (ASTER) Level 1 Precision Terrain Corrected Registered At-Sensor Radiance Product (AST_L1T). AST_L1T Product User's Guide. USGS EROS Data Center.
- Vermote, E. F.; Roger, J. C. & Ray, J. P., 2015. MODIS Surface Reflectance User's Guide. Collection 6, NASA
- Weng, Q.; Lu, D. & Schubring, J., 2004. Estimation of land surface temperature-vegetation abundance relationship for urban heat island studies. Remote Sensing of Environment, Elsevier Science Inc., Box 882 New York NY 10159 USA, 89, 467-483
- Wikipedia, 2017. k-means clustering. Available at https://en.wikipedia.org/wiki/K-means_clustering

Глава 5

Basic Tutorials

The following are very basic tutorials for land cover classification using the Semi-Automatic Classification Plugin (SCP). It is assumed that you have a basic knowledge of QGIS (you can find a guide to QGIS interface at this page).

5.1 Tutorial 1: Basic Land Cover Classification

The following is a basic tutorial about the land cover classification using the Semi-Automatic Classification Plugin (SCP). It is assumed that you have a basic knowledge of QGIS. Following the video of the tutorial.

 $https://www.youtube.com/watch?v{=}7SZDCFXjIbA$

- Tutorial 1: Basic Land Cover Classification (c. 159)
 - Download the Data (c. 160)
 - Define the Band set and create the Training Input File (c. 160)
 - Create the ROIs (c. 162)
 - Create a Classification Preview (c. 166)
 - Create the Classification Output (c. 172)

5.1.1 Tutorial 1: Basic Land Cover Classification

This is a basic tutorial about the use of SCP for the classification of a multispectral image. It is recommended to read the *Brief Introduction to Remote Sensing* (c. 123) before following this tutorial.

The purpose of the classification is to identify the following land cover classes:

- 1. Water;
- 2. Built-up;
- 3. Vegetation;
- 4. Soil.

The basic steps are:

- 1. the definition of input data (image bands) in a *Band set* (c. 45);
- 2. the creation of a *Training input* (c. 33) to collect training areas to train the classification algorith;
- 3. the *Classification* (c. 75) of input data.

Download the Data

Other tutorials will show how to search and download satellite images within *SCP*. In this tutorial we are going to use a *Sentinel-2 Satellite* (c. 129) image, already converted to reflectance and clipped to the study area, downloading a .zip file (which contains modified Copernicus Sentinel data 2023).

The study area of this tutorial covers part of the Lake Garda in the Northern Italy. Download the .zip file from this link and extract the directory containing the image bands.

Define the Band set and create the Training Input File

We are going to use a subset of *Sentinel-2 Satellite* (c. 129) image (Copernicus land monitoring services) and use the bands illustrated in the following table.

| Sentinel-2 Bands | Central Wavelength [micrometers] | Resolution [meters] |
|-------------------------------|----------------------------------|---------------------|
| Band 2 - Blue | 0.490 | 10 |
| Band 3 - Green | 0.560 | 10 |
| Band 4 - Red | 0.665 | 10 |
| Band 5 - Vegetation Red Edge | 0.705 | 20 |
| Band 6 - Vegetation Red Edge | 0.740 | 20 |
| Band 7 - Vegetation Red Edge | 0.783 | 20 |
| Band 8 - NIR | 0.842 | 10 |
| Band 8A - Vegetation Red Edge | 0.865 | 20 |
| Band 11 - SWIR | 1.610 | 20 |
| Band 12 - SWIR | 2.190 | 20 |

First, we need to define the Band set which is the input image for SCP classification. Open the tab Band

set (c. 45) clicking the button in the SCP menu (c. 29) or the SCP dock (c. 31).

Click the button **L** to select the .tif files from the extracted directory to the *Band set* tab.

COBET: It is possible to define multiple *Band sets*. It is also possible to add to a *Band set* bands that are already loaded in QGIS. Each *Band set* definition is saved with the QGIS project.

In the table *Band set definition*, we need to order the band names in ascending order and assign the center wavelength to each bands (required for spectral signature calculation). We can do this in one step by selecting *Sentinel-2* in the *Wavelength* list of the *Band quick settings* (c. 47).

We can display a *Color Composite* (c. 133) of bands: Near-Infrared, Red, and Green.

Cobet: If a *Band set* (c. 45) is defined, a temporary virtual raster (named Virtual Band Set 1) is created automatically, which allows for the display of a *Color Composite* (c. 133).

In the Working toolbar (c. 41), click the list RGB= and select the item 7-3-2 (corresponding to the band numbers in Band set (c. 45)). You can see that Virtual Band Set 1 is added to QGIS Layers as multiband image, and the displayed bands correspond to the selected color composite.

| lter | Filter | Band set definition | Active band set 1 🗘 Date NaT | Root direct | ory | |
|--------------------------------|----------------|---------------------|----------------------------------|--------------------|----------------------------|-----|
| Band set Download production | Band set table | | Band name | Center wave | length Multiplicative Fact | |
| Basic tools | 1 RT_T32TPR_A0 | 1 RT_T32TPR_A0429 | 19 20230910T101420 B02 | 0.49 | 1.0 | Ŧ |
| Preprocessing | | 2 RT_T32TPR_A0429 | 19_20230910T101420_B03 | 0.56 | 1.0 | |
| Band processing Postprocessing | | 3 RT_T32TPR_A0429 | 19_20230910T101420_B04 | 0.665 | 1.0 | |
| Postprocessing Band calc | | 4 RT_T32TPR_A0429 | 19_20230910T101420_B05 | 0.705 | 1.0 | Ŧ |
| Script | | 5 RT_T32TPR_A0429 | 19_20230910T101420_B06 | 0.74 | 1.0 | ¥ |
| 🔉 Settings | | 6 RT_T32TPR_A0429 | 19_20230910T101420_B07 | 0.783 | 1.0 | a' |
| User manual | | 7 RT_T32TPR_A0429 | 19_20230910T101420_B08 | 0.842 | 1.0 | |
| Help About | | 8 RT_T32TPR_A0429 | 19_20230910T101420_B8A | 0.865 | 1.0 | |
| About | | 9 RT_T32TPR_A0429 | 19_20230910T101420_B11 | 1.61 | 1.0 | |
| | | 10 RT_T32TPR_A0429 | 19_20230910T101420_B12 | 2.19 | 1.0 | × |
| | | 4 | | | Þ | |
| | | Band guick settings | | | | |
| | | | bands 1, 2, 3, 4, 5, 6, 7, 👻 📘 W | avelongth unit han | d num - Data 2020 01 0 | 1 - |
| | | | bands 1, 2, 3, 4, 5, 6, 7, + | avelength unit ban | Date 2020-01-0 | 1 * |
| | | Band set tools | and and the | | | |

Рис. 1: Definition of a band set

Because we selected Near-Infrared, Red, and Green bands, in the map, vegetation is highlighted in red. Selecting the color composite 3-2-1, natural colors would be displayed.




Рис. 2: Color composite RGB=7-3-2

After *Band set* (c. 45) creation, we need to create a *Training input* (c. 33) file in order to collect *Training Areas* (c. 134) (ROIs) and calculate the *Spectral Signature* (c. 127) thereof (which are required to train the classification algorithm).

In the *SCP dock* (c. 31) select the tab *Training input* (c. 33) and click the button \square to create the *Training input* (define a name such as training.scpx).

COBET: A *Training input* is a .scpx file which stores the geometries and the spectral signatures. Once it is created, it is configured with the wavelength properties of the corresponding *Band set*. To use a

Training input create with a different Band set, one should create a new Training input, and then import the existing Training input with Import library file (c. 55).

The path of the file is displayed and a vector is added to QGIS layers with the same name as the *Training input*.

Предупреждение: In order to prevent data loss, one should not edit the *Training input* using QGIS vector tools.

Create the ROIs

We are going to create ROIs defining the *Classes and Macroclasses* (c. 135). Each ROI is identified by a Class ID (i.e. C ID), and each ROI is assigned to a land cover class through a Macroclass ID (i.e. MC ID).

Macroclasses are composed of several materials having different spectral signatures; in order to achieve good classification results we should separate spectral signatures of different materials, even if belonging to the same macroclass. Thus, we are going to create several ROIs for each macroclass (setting the same MC ID, but assigning a different C ID to every ROI).

We are going to use the Macroclass IDs defined in the following table.

| Macroclass name | Macroclass ID |
|-----------------|---------------|
| Water | 1 |
| Built-up | 2 |
| Vegetation | 3 |
| Soil | 4 |

Cobet: ROIs can be created by manually drawing a polygon or with an automatic region growing algorithm.

In the map zoom over the dark blue area in the upper left corner of the image which is a water body. To

manually create a ROI inside the dark area, click the button \square in the *Working toolbar* (c. 41). Left click on the map to define the ROI vertices and right click to define the last vertex closing the polygon. An orange semi-transparent polygon is displayed over the image, which is a temporary polygon (i.e., it is not saved in the *Training input* (c. 33)).

COBET: You can draw temporary polygons (the previous one will be overridden) until the shape covers the intended area.

If the shape of the temporary polygon sufficiently covers the water area, we can save it to the *Training input* (c. 33).

Open the Training input (c. 33) to define the Classes and Macroclasses (c. 135). In the ROI & Signature list (c. 36) set MC ID = 1 and MC Name = Water; also set C ID = 1 and C Name = Lake. Now click

to save the ROI in the *Training input*.

After a few seconds, the ROI is listed in the ROI & Signature list (c. 36) and the spectral signature is

calculated (because Signature is checked).

| SCP Dock | 0 × |
|--|-----|
| Point Image: Desktop/sample_data/training.scpx ROI & Signature list (band set 1) Filter MC ID * C ID Name Type Color | |
| Filter | |
| MC ID C ID Name Type Color | |
| | |
| Trait | |
| | |
| ROI options | |
| | |
| | |
| | |
| MC ID 1 C MC Name Macroclass 1 | |
| CID 1 CName Class 1 | |
| Autosave V Signature | |
| SCP Dock Layers | |

Рис. 3: Definition of Training input in SCP




Рис. 4: A temporary ROI created manually

As you can see, the *C ID* in *ROI* & *Signature list* (c. 36) is automatically increased by 1. Saved ROI is displayed as a dark polygon in the map and the temporary ROI is removed. Also, in the *ROI* & *Signature list* (c. 36) you can notice that the *Type* is RS (i.e., ROI and spectral signature), meaning that the ROI spectral signature was calculated and saved in the *Training input*.

Now we are going to create a second ROI for the built-up class using the automatic region growing algorithm. Zoom near the center of the image. In *Working toolbar* (c. 41) set the *Dist* value to 0.03.

Click the button in the *Working toolbar* (c. 41) and click over the light blue area of the map. After a while the orange semi-transparent polygon is displayed over the image.

COBET: *Dist* value should be set according to the range of pixel values; in general, increasing this value creates larger ROIs.

In the ROI & Signature list (c. 36) set MC ID = 2 and MC Name = Built-up; also set C ID = 2 (it should be already set) and C Name = Buildings.

Again, the C ID in ROI & Signature list (c. 36) is automatically increased by 1.

Create a ROI for the class Vegetation (red pixels in color composite RGB=7-3-2) and a ROI for the class Soil (bare soil or low vegetation) (yellow pixels in color composite RGB=7-3-2) following the same steps described previously. The following images show a few examples of these classes identified in the map.

COBET: It is possible to display the *Spectral signatures* of created ROIs in the *Spectral Signature Plot* (c. 114).

| CP Dock | ð× |
|--|----|
| Image: Desktop/sample_data/training.scpx ROI & Signature list (band set 1) Filter MC ID* C ID Name Type Color 1 Water 1 <td>×</td> | × |
| Filter | |
| MC ID* C ID Name Type Color | |
| C 1 Water ✓ 1 1 Lake R&S | |
| | |
| | |
| ROI options | |
| | |
| | |
| | |
| MC ID 1 C MC Name Water | |
| CID 2 CName Lake | |
| Autosave 🗸 Signature | |
| SCP Dock Layers | |

Phc. 5: The ROI saved in the Training input



Puc. 6: A temporary ROI created with the automatic region growing algorithm

Create a Classification Preview

The classification process is based on collected ROIs (and spectral signatures thereof). It is useful to create a *Classification preview* (c. 44) in order to assess the results (influenced by spectral signatures) before the final classification. In case the results are not good, we can collect additional ROIs to better classify land cover.

Before running a classification (or a preview), set the color of land cover classes that will be displayed in the classification raster. In the *ROI* & *Signature list* (c. 36), double click the color (in the column *Color*) of each ROI to choose a representative color of each class. Also, we need to set the color for macroclasses in *ROI* & *Signature list* (c. 36).

Now we need to select the classification algorithm. In this tutorial we are going to use the *Maximum Likelihood* (c. 137).

Open the tool *Classification* (c. 75) to set the use of classes or macroclasses. Check *Use* \bowtie *Class ID* and in *Algorithm* (c. 76) select the *Maximum Likelihood*. The *input band set* is 1 because it is the number of the band set containing the image (bands) that we want to classify.

In *Classification preview* (c. 44) set Size = 300; click the button \Box and then left click a point of the image in the map. The classification process should be rapid, and the result is a classified square centered in the clicked coordinates.

Previews are temporary rasters (deleted after QGIS is closed) placed in a group named

Class_temp_group in the QGIS panel Layers. Now in Classification (c. 75) check Use 🗹 MC ID and

click the button in *Classification preview* (c. 44). The preview now represents the colors defined for macroclass.

| SCP D | ock | | | | | | | | ð× | | |
|-----------------------|-----------------------------------|-----------------------------------|------|-----|------------------|-----|--------|----------|----|--|--|
| Training input 뎋 Home | Desktop/sample_data/training.scpx | | | | | | | | | | |
| | _ | ROI & Signature list (band set 1) | | | | | | | | | |
| H | Filter | | | | | | | | | | |
| ndu | | MC | ID₹ | CID | Name | | Туре | Color | | | |
| i gr | | - 1 | 1 | 1 | Water | | DCC | | | | |
| inir | _ | - 2 | 1 | 1 | Lake Built-up | | R&S | | | | |
| Tra | > | | 2 | 2 | Buildings | | R&S | | | | |
| | | | | | - | | | | | | |
| sc | | | | | | | | | | | |
| ROI options | | | | | | | | | | | |
| do | | | | | | | | | | | |
| õ | 4 | | | | | | | | | | |
| | | | | | | | | | | | |
| X | | | | | | | | | | | |
| <u>ن</u> | | | | | | | | | | | |
| Ł | | | | | | | | | | | |
| | MC | ID 🗌 | 2 | 2 ‡ | MC Name | Bu | ilt-up | | | | |
| (→ | C ID | | 3 | 3 ‡ | C Name | Bu | ilding | IS | | | |
| × | | 7 | | | ✓ Autosa | ave | ✓ S | ignature | - | | |
| SCP I | Dock | Li | ayer | s | | | | | | | |

Рис. 7: The ROI saved in the Training input




Рис. 8: Vegetation. Color composite RGB = 7-3-2




Рис. 9: Soil. Color composite RGB = 7-3-2




Рис. 10: Definition of class colors

| | Semi-Automatic Classification Plugin | ↑ _ □ | × | | | | | | |
|-----------------------------|---|-------|------|--|--|--|--|--|--|
| Filter | | | | | | | | | |
| Band set | Input | | Tool | | | | | | |
| | Preprocessing Use training O Macroclass ID I Class ID Band processing Algorithm | | | | | | | | |
| Num | | | | | | | | | |
| Band processing | | | | | | | | | |
| Classification | | | | | | | | | |
| Second Combination | Maximum Likelinood | | | | | | | | |
| Dilation | Use 🗌 Single threshold 👘 0.0000 🛊 📄 Signature threshold 📉 | | | | | | | | |
| Erosion | | | | | | | | | |
| Sieve | Save signature raster Calculate classification confidence raster | | | | | | | | |
| Neighbor | | | | | | | | | |
| V PCA | | | | | | | | | |
| Postprocessing Band calc | | | | | | | | | |
| Script | Minimum Distance | | | | | | | | |
| > X Settings | Multi Lavor Descentrop | | | | | | | | |
| User manual | Multi-Layer Perceptron | | | | | | | | |
| Help | Random Forest | | | | | | | | |
| P About | Spectral Angle Mapping | | | | | | | | |
| | Support Vector Machine | | | | | | | | |
| | Run | | | | | | | | |
| | Load classifier Save classifier Script 📄 RUI | N | | | | | | | |

Рис. 11: Setting the algorithm and using C ID



Рис. 12: Classification preview displayed over the image using C ID




Рис. 13: Classification preview displayed over the image using MC ID

COBET: It is useful to perform a classification preview every time a ROI (or a spectral signature) is added to the *ROI & Signature list* (c. 36), in order to assess the contribution thereof to the classification;

if the ROI causes errors, it can be removed from the *Training input* with the button

Create the Classification Output

Assuming that the results of classification previews show a good agreement with the image (i.e. pixels are assigned to the correct class defined in the $ROI \ \ Signature \ list$ (c. 36)), we can perform the actual land cover classification of the whole image.

In *Classification* (c. 75) check *Use* \checkmark *Macroclass ID*. Click the button *Run* (c. 84) \checkmark and define the path of the classification output, which is a raster file (.tif).

Cobet: If \bowtie *Play sound when finished* is checked in *Calculation process* (c. 113) settings, a sound is played when the process is finished.

Well done! You have just performed your first land cover classification.

However, you can see that there are several classification errors, because the number of ROIs (spectral signatures) is insufficient.

In other tutorials we are going to learn about the download and preprocessing of bands, the classification algorithms, and the postprocessing of classifications.




Рис. 14: Result of the land cover classification






Рис. 15: Example of error: Soil classified as Built-up

5.2 Tutorial 2: Managing input bands, the Band set tab

The following is a basic tutorial about the *Band set* (c. 45) tab, which allows for managing input bands. Following the video of the tutorial.

https://www.youtube.com/watch?v=DQXfBPke2J4

5.3 Tutorial 3: Downloading free satellite images, the Download product tab

The following is a basic tutorial about the *Download products* (c. 48) tab, which allows for downloading free satellite images such as Landsat and Sentinel-2.

Following the video of the tutorial.

https://www.youtube.com/watch?v=NwL2f5Nrn3U

Глава б

Thematic Tutorials

The following are thematic tutorials. Before these tutorials, it is recommended to read the *Basic Tutorials* (c. 159).

Глава 7

Frequently Asked Questions

If you have comments or questions please join the Facebook group .

Before asking, please check the official site From GIS to Remote Sensing and the following Frequently Asked Questions.

- Plugin installation (c. 178)
 - How to install the plugin manually? (c. 178)
 - How to install the plugin from the official SCP repository? (c. 178)
 - Can I use the previous version 7 of SCP? (c. 180)
- Pre processing (c. 182)
 - Which image bands should I use for a semi-automatic classification? (c. 182)
 - Which Landsat bands can be converted to reflectance by the SCP? (c. 183)
 - Can I apply the conversion to Sentinel-2 images downloaded from the web? (c. 183)
 - Can I apply the conversion to Sentinel-2 L2A downloaded from the web? (c. 183)
 - Can I apply the Landsat conversion and DOS correction to clipped bands? (c. 183)
 - Can I apply the DOS correction to bands with black border (i.e. with NoData value)? (c. 183)
 - How to remove cloud cover from images? (c. 183)
- *Processing* (c. 183)
 - I get classification errors. How can I improve the accuracy? (c. 183)
 - Is it possible to use the same training input for multiple images? (c. 184)
 - What is the difference between classes and macroclasses? (c. 184)
 - Can I use SCP with images from drones or aerial photographs? (c. 184)
 - Why using only Landsat 8 band 10 in the estimation of surface temperature? (c. 184)
 - How can I speed up the processing? (c. 184)
 - How do I perform accuracy assessment and how to design the number of samples? (c. 184)

- *Warnings* (c. 185)
 - Warning [12]: The following signature will be excluded if using Maximum Likelihood. Why? (c. 185)
- *Errors* (c. 185)
 - How can I report an error? (c. 185)
- Various (c. 187)
 - What can I do with the SCP? (c. 187)
 - How to contribute to SCP (c. 187)
 - How can I translate this user manual to another language? (c. 188)
 - Where is the source code of SCP? (c. 188)

7.1 Plugin installation

7.1.1 How to install the plugin manually?

The SCP can be installed manually (this can be useful when an internet connection is not available, or the installation is required on multiple computers), following a few steps:

- 1. download the SCP zip archive from https://github.com/semiautomaticgit/ SemiAutomaticClassificationPlugin/archive/master.zip ;
- 2. extract the content of the archive (several files such as COPYING.txt and folders such as ui) in a new folder named SemiAutomaticClassificationPlugin (without -master);
- 3. open the QGIS plugins directory (in Windows usually C:\Users\username\AppData\ Roaming\QGIS\QGIS3\profiles\default\python\plugins, in Linux and Mac usually / home/username/.local/share/QGIS/QGIS3/profiles/default/python/plugins) and delete the folder SemiAutomaticClassificationPlugin if present;
- 4. copy the folder SemiAutomaticClassificationPlugin inside the QGIS plugins directory;
- 5. the plugin should be installed; start QGIS, open the Plugin Manager and be sure that Semi-Automatic Classification Plugin is checked.

7.1.2 How to install the plugin from the official SCP repository?


It is possible to install the SCP using the official repository. This repository allows for the installation of the latest version of SCP (master), in some cases also before the availability thereof in the QGIS repository. Therefore, this can be useful if you need a fix or a new function that is still not available in the QGIS repository. Moreover, the master version in the SCP repository can be installed along with the version available in the QGIS repository.

In order to install the SCP repository follow these steps:

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| 🔇 Untit | led Pr | oject - | - QGIS | | | | | | | | | |
|---------|--------|---------|---------------|----------|---------|-----------------|----------------|------------------|-------------|-----------|------------|-------|
| Project | Edit | View | <u>L</u> ayer | Settings | Plugins | Vect <u>o</u> r | <u>R</u> aster | <u>D</u> atabase | <u>W</u> eb | Mesh | Processing | Help |
| | | | | 💐 💕 | 🌲 Mar | nage and | l Install Plu | ugins | | | DC | |
| | | • | | SJ ∎a | ne Pyt | hon Cons | sole | | Ct | rl +Alt+P | | 1 L 🔯 |

• Click Settings then click the button Add;



• Inside the Repository details enter:

Name:

SCP


URL:

 $\tt https://semiautomaticgit.github.io/SemiAutomaticClassificationPlugin/repository.xml$

and click OK;

| Q | Repository details 🔷 🛧 🗙 |
|----------------|---|
| Name | SCP |
| URL | https://semiautomaticgit.github.io/SemiAutomaticC |
| Parameters | ?qgis=3.10 |
| Authentication | Clear Edit |
| Enabled | \checkmark |
| | |
| | |
| | <mark>⊘</mark> Cancel ∨ OK |

• After the repository update, the item Semi-Automatic Classification Plugin - master should be listed with the other plugins;



• From the menu All, select the Semi-Automatic Classification Plugin - master and click the button Install plugin; the latest version of SCP should be automatically activated (ignore errors, the restart of QGIS could be necessary to complete the SCP installation); it is possible to deactivate the other SCP installed in the QGIS repository;

| 0 | | Plugins Installed (24) | | | |
|--|---|---|---------------------|--|--|
| Al | Search | | | | |
| Mar At Martaled Normataled ⇒ Upgraduative Settings | Search C. Coordinate Capture C. Coordinate | Stote: Category Reset: () 60 devrices: Category Reset: Category Reset: () 80 devrices: Tays: Reset: Category Reset: () 80 devrices: Andro: Land Count, Land Count, Rence Brows: () 80 devrices: () 80 devrices: Andro: Land Count: () 80 devrices: () 80 devrices: () 80 devrices: Andro: Land Count: () 80 devrices: () 80 devrices: () 80 devrices: Analysis: () 80 devrices: () 80 devrices: () 80 devrices: () 80 devrices: Analysis: () 80 devrices: () 80 devrices: () 80 devrices: () 80 devrices: Analysis: () 80 devrices: () 80 devrices: () 80 devrices: () 80 devrices: S.0.6 () 80 devrices: () 80 devrices: () 80 devrices: () 80 devrices: () 80 devrices: | | | |
| | Semi-Actinguic Classification (P Semi-Actinguic Classification (P))) ()) ()) ()) () | | | | |
| | tit Help | Upgrade all Uninstall plug | in Reinstall plugin | | |

7.1.3 Can I use the previous version 7 of SCP?


It is possible to install the previous version 7 of SCP using the official repository. Also, this version can be installed along with the SCP version 8.

In order to install the SCP repository follow these steps:

- Run QGIS;
- From the main menu, select Plugins > Manage and Install Plugins;

| 🔇 Untit | led Pr | oject - | – QGIS | | | | | | | | | |
|---------|--------|--------------|---------------|----------|---------|-----------------|----------------|------------------|-------------|------------|------------|-------|
| Project | Edit | <u>V</u> iew | <u>L</u> ayer | Settings | Plugins | Vect <u>o</u> r | <u>R</u> aster | <u>D</u> atabase | <u>W</u> eb | Mesh | Processing | Help |
| | | | | 31 🛀 | 🌲 Mai | nage and | Install Plu | ugins | | | DC | |
| | | • | | SJ ∎a | ne Pyt | hon Cons | sole | | Ct | rl +Alt +P | | 1 L 🔯 |

• Click Settings then click the button Add;



• Inside the Repository details enter:

Name:

SCP

URL:

```
https://semiautomaticgit.github.io/SemiAutomaticClassificationPlugin_v7/repository.xml
```

and click $\mathsf{OK};$

| Q | Repository details 4 | × | | | | |
|----------------|---|---|--|--|--|--|
| Name | SCP | | | | | |
| URL | https://semiautomaticgit.github.io/SemiAutomaticC | | | | | |
| Parameters | ?qgis=3.10 | | | | | |
| Authentication | Clear Edit | | | | | |
| Enabled | | | | | | |
| | | | | | | |
| | | | | | | |
| | <mark>⊘</mark> Cancel √ OK | | | | | |

• After the repository update, the item Semi-Automatic Classification Plugin - master should be listed with the other plugins;



• From the menu All, select the Semi-Automatic Classification Plugin - master and click the button Install plugin; the latest version of SCP should be automatically activated (ignore errors, the restart of QGIS could be necessary to complete the SCP installation); it is possible to deactivate the other SCP installed in the QGIS repository;

| J | | Plugins Installed (24) | | |
|---|---|--|---|--|
| Al | Search | | | |
| natad Ne instalad Uggssesbe Settings | Constants oppore Constants Constant | Semi-Automatic Classific High that allows for the supervised class for the dominal, the supervised class to the dominal of the supervised class to the dominal of the supervised class to the supervised classification of the supervised supervised to the supervised classification of the supervised clas | stituation of remote sensing i and potpocessing of Imag Sandaro Pagic (SCP) allow for the for the download, the preprocess that and Sentole - Image. Fernal majories the installation of (SDA, C) (SPE - 2008), and (SPE - 2008), and (SPE - 2008), an | images, providing ges. the supervised ing and potprocessing algorithms are GR, Numy, SoPy, and AR, Numy, SoPy, and and Cover Supervised lastificação de lastificação de de della Copentura del upervised classification |
| | | Minor update: Upprade all | Uninstall plugin | Reinstall plugin |
| | | opgrade an | | -winstall plugin |

7.2 Pre processing

7.2.1 Which image bands should I use for a semi-automatic classification?

In general, it is preferable to avoid thermal infrared bands. If you are using Landsat 4, 5 or 7 you should select bands: 1, 2, 3, 4, 5, 7 avoiding band 6 that is thermal infrared; for Landsat 8 you should select bands: 2, 3, 4, 5, 6, 7. Landsat 8 band 1 is generally avoided because it is very similar to the blue band and it is mainly used for coastal aerosol study. Landsat thermal infrared band is excluded from classifications because values are mainly related to object temperature.

For Sentinel-2 images you can use bands: 2, 3, 4, 5, 6, 7, 8, 8A, 11, 12.

7.2.2 Which Landsat bands can be converted to reflectance by the SCP?

All Landsat 1,2, and 3 MSS and Landsat 4, 5, 7, and 8 images downloaded from http://earthexplorer.usgs.gov/ and processed with the Level 1 Product Generation System (LPGS) can be converted to reflectance automatically by the SCP; products generated by the LPGS have a MTL file included that is required for the conversion.

7.2.3 Can I apply the conversion to Sentinel-2 images downloaded from the web?

Yes, you can convert also images downloaded from the web (actually the conversion is recommended). You should move all the bands (.jp2 files) and if available the .xml file whose name contains MDT_SAFL1C in the same directory. Then select this directory in *Image conversion* (c. 64). Images are converted to reflectance.

7.2.4 Can I apply the conversion to Sentinel-2 L2A downloaded from the web?

Yes, you should move all the .jp2 files inside the same directory and rename the files with the band number in the ending of the name (e.g. from name_02_10m.jp2 to name_02.jp2) Then select this directory in *Image conversion* (c. 64). Images are converted to reflectance.

7.2.5 Can I apply the Landsat conversion and DOS correction to clipped bands?

Yes, you can clip the images before the conversion to reflectance and then copy the MTL file (contained in the Landsat dataset) inside the directory with the clipped bands. If you want to apply the DOS correction (which is an image based technique) you should convert the original Landsat bands (the entire image) and then clip the conversion output (i.e. bands converted to reflectance).

7.2.6 Can I apply the DOS correction to bands with black border (i.e. with NoData value)?

If you want to apply the DOS correction to an entire band which has NoData values (the black border with value = 0) then you have to check the checkbox Use value as NoData and set the value to 0. This is because DOS is an image based technique, and NoData values must be excluded from the calculation.

7.2.7 How to remove cloud cover from images?

DOS1 correction does not remove clouds from the image. However, Landsat 8 images include Band 9 that identifies clouds (see this NASA site). You can use this band for the creation of a mask.

7.3 Processing

7.3.1 I get classification errors. How can I improve the accuracy?

Several materials have similar spectral signatures (e.g. soil and built-up, or forest and other types of dense low vegetation), which can cause classification errors if ROIs, and spectral signatures thereof, are not acquired correctly. In order to improve the results, you can try to collect more ROIs over these areas, in order to train the algorithm for these very similar areas, also, display the spectral signatures of these areas in *Spectral Signature Plot* (c. 114) to assess their similarity. You can also use a *Signature threshold* (c. 60) for these signatures in order to reduce the variability thereof (only pixels very similar to the input signatures will be classified).

7.3.2 Is it possible to use the same training input for multiple images?

Yes, it is possible if all the images have the same number of bands. However, if images are acquired in different months, land cover changes (especially of vegetation state) will affect the spectral signature (i.e. the same pixel has different spectral signature in different periods). Atmospheric effects could also affect the images differently. That could reduce classification accuracy. Therefore, it is suggested to collect always the ROIs and spectral signatures for every image.

7.3.3 What is the difference between classes and macroclasses?

Please see Classes and Macroclasses (c. 135).

7.3.4 Can I use SCP with images from drones or aerial photographs?

Yes, you can use them if they have at least 4 bands. With less than 4 bands, semi-automatic classification algorithms are unable to classify the land cover correctly. Alternative classification methods exist, such as object oriented classification, which is not implemented in SCP.

7.3.5 Why using only Landsat 8 band 10 in the estimation of surface temperature?

Several methods were developed for estimating surface temperature. The method described in the tutorial for temperature estimation requires only one band. Moreover, USGS recommends that users refrain from relying on Landsat 8 Band 11 data in quantitative analysis of the Thermal Infrared Sensor data (see Changes to Thermal Infrared Sensor (TIRS) data by USGS).

7.3.6 How can I speed up the processing?

In order to speed up the processing you should set the available RAM and the number of threads available in *System* (c. 112). *Available RAM (MB)* should be half of the system RAM (e.g. 1024MB if system has 2GB of RAM) or more if the system has a large amount of RAM (e.g. 10240MB if system has 16GB of RAM). *CPU threads* should be a value lower than the maximum number of system threads (e.g. if the system has 4 available threads set value 3).

Also, several tools allow for selecting the output format .vrt avoiding the time required to create a unique .tif raster (after multiprocess), especially useful for large rasters.

7.3.7 How do I perform accuracy assessment and how to design the number of samples?

Accuracy assessment is described in this tutorial.

Sample design is required to provide an adequate number of samples for each class, as described in «Olofsson, et al., 2014. Good practices for estimating area and assessing accuracy of land change. Remote Sensing of Environment, 148, 42 - 57».

The number of samples (N) should be calculated as (Olofsson, et al., 2014):

$$N = (\sum_{i=1}^{c} (W_i - S_i) / S_o)^2$$

where:

- W_i = mapped area proportion of class i;
- S_i = standard deviation of stratum i;
- S_o = expected standard deviation of overall accuracy;

• c = total number of classes;

To stratify the sample we should conjecture user's accuracy and standard deviations of strata (Olofsson, et al., 2014). One can hypothesize that user's accuracy is lower and standard deviations S_i is higher for classes having low area proportion, but of course these values should be carefully evaluated.

This requires some conjectures about overall accuracy and user's accuracy of each class. We should base these conjectures on previous studies.

As starting values, we could assume $S_o = 0.01$ and perform a rough accuracy assessment with random samples, and eventually calculate the S_i to perform the sampling design. Alternatively, one could start with Si = 0.5 for all the classes. Basically the higher is Si, the larger is the number of samples for that class.

7.4 Warnings

7.4.1 Warning [12]: The following signature will be excluded if using Maximum Likelihood. Why?

The ROI is too small (or too homogeneous) for the *Maximum Likelihood* (c. 137) algorithm because that ROI has a singular covariance matrix. You should create larger ROIs or don't use the Maximum Likelihood algorithm in the classification process.

7.5 Errors

7.5.1 How can I report an error?

If you found an error of the Semi-Automatic Classification Plugin please follow these steps in order to collect the required information (log file):


- 1. close QGIS if already open;
- 2. open QGIS, open the Plugin tab *Debug* (c. 109) and check the checkbox Seconds detailed events in a log file;
- 3. click the button *Test dependencies* in the tab *Debug* (c. 109);
- 4. load the data in QGIS (or open a previously saved QGIS project) and repeat all the steps that cause the error in the Plugin;
 - if the issue could be related to the image data, please use this sample dataset ;
- 5. if an error message appears (like the one in the following image), copy the whole content of the message in a text file;
- 6. open the tab *Debug* (c. 109) and uncheck the checkbox \checkmark *Records events in a log file*, then click


the button **III** and save the **log file** (which is a text file containing information about the Plugin processes);

- 7. open the log file and copy the whole content of the file;
- 8. join the Facebook group , create a new post and copy the error message and the log file (or attach them).

| | Semi-Automatic Classification Plugin | ↑ _ □ × |
|---|---|--------------------------|
| Filter Filter | Log file | 5 Tool |
| Download products Sasic tools | Record detailed events in a Log file Test | |
| Preprocessing Band processing | Test dependencies | Help |
| Postprocessing Band calc Script | | |
| Settings Debug | | |
| Interface Processing setting | | |
| Help About | | |
| | | |
| | | |
| | | |
| | | |

Рис. 1: Debug





7.6 Various

7.6.1 What can I do with the SCP?

SCP allows for the **land cover classification** of remote sensing images through Supervised Classification (c. 133). You can produce a land cover raster using one of the Classification Algorithms (c. 136) available in SCP. These algorithms require spectral signatures or ROIs as input (for definitions please read Brief Introduction to Remote Sensing (c. 123)) that define the land cover classes to be identified in the image.




Рис. 3: A multispectral image processed to produce a land cover classification (Landsat image provided by USGS)

SCP can work with **multispectral images** acquired by satellites, airplanes, or drones. Also, *SCP* allows for the direct search and download of free images (see *Download products* (c. 48)). You cannot use orthophotos with less than 4 bands and LIDAR data with SCP.

Input image in SCP is called *Band set* (c. 45), which is used as input for the classification. SCP provides several tools for the *Preprocessing* (c. 62) of downloaded images, such as the conversion to reflectance and manipulation of bands.

The *Spectral Signature Plot* (c. 114) and *Scatter Plot* (c. 118) allow for the **analysis of spectral signatures and ROIs**. Also, several *Basic tools* (c. 54) are available for easing the ROI creation and editing spectral signatures.

Raster calculation is available through the seamless integration of the tool *Band calc* (c. 99) with bands in the *Band set* (c. 45), calculating mathematical expressions and spectral indices.

See the Basic Tutorials (c. 159) for more information and examples.

7.6.2 How to contribute to SCP

You can contribute to *SCP* by fixing and adding functionalities (see *Where is the source code of SCP*? (c. 188)), or translating the user manual (see *How can I translate this user manual to another language*? (c. 188)).

7.6.3 How can I translate this user manual to another language?

It is possible to easily translate the user manual to any language, because it is written in reStructuredText as markup language (using Sphinx). Therefore, your contribution is fundamental for the translation of the manual to your language. The following guide illustrates the main steps for the translation, which can be performed:

- using the free online service Transifex;
- using the gettext .po files.

Before translating, please read this document from the QGIS translation guide, which helps you understand the reStructuredText.

Method 1. Translation using the free online service Transifex

This is probably the easiest way to translate the manual using an online service.

1. Join the Semi-automatic Classification Manual project

Go to the page https://www.transifex.com/semi-automatic-classification/semi-automatic-classification-plugin-manual and click the button Help translate. You can sign in using your Google or Facebook account, or with a free registration.

2. Select your language

Select your language and click the button Join team. If your language is not listed, click the button Request language.

3. Translation

There are several files to be translated, which refer to the sections of the SCP documentation. To translate the SCP interface you should select the file semiautomaticclassificationplugin.ts.

Method 2. Translation using the gettext .po files

In order to use this method, you should be familiar with GitHub. This translation method allows for the translation of the PO files locally.

1. Download the translation files

Go to the GitHub project https://github.com/semiautomaticgit/SemiAutomaticClassificationManual_v4/tree/master/locale and download the .po files of your language (you can add your language, if it is not listed), or you can fork the repository. Every file .po is a text file that refers to a section of the User Manual.

2. Edit the translation files

Now you can edit the .po files. It is convenient to edit those file using one of the following programs: for instance Poedit for Windows and Mac OS X, or Gtranslator for Linux or OmegaT (Java based) for Windows, Linux and Mac OS X. These editors allow for an easy translation of every sentence in the User Manual.

7.6.4 Where is the source code of SCP?

The source code of SPC is available at the following link $\rm https://github.com/semiautomaticgit/SemiAutomaticClassificationPlugin$